



ENGINEERING DESIGN
AND CONSTRUCTION STANDARDS
Last Updated 6/15/2022

Prepared by:

DAVIS • MARTIN • POWELL
ENGINEERS & SURVEYORS **dmp**

T: 336-886-4821 • F: 336-886-4458 • License: F-0245
6415 Old Plank Road, High Point, NC 27265 • www.dmp-inc.com



CITY OF DUNN

ENGINEERING DESIGN AND CONSTRUCTION STANDARDS

Public Utilities Department
P.O. Box 1065
Dunn, NC 28335

These Engineering Design and Construction Standards shall be reviewed on a periodic basis by the Director of Public Utilities.

This document shall be available for purchase per the latest fee schedule, or on the City's Website at <http://www.dunn-nc.org/>. Updates will be posted periodically on the City's website. It shall be the responsibility of the holder of this document to maintain an up-to-date copy of the Engineering Design and Construction Standards by obtaining and inserting all revisions.

TABLE OF CONTENTS

SECTION 0.00	DESIGN CERTIFICATION REQUIREMENTS AND GENERAL INFORMATION FOR DESIGN PROFESSIONALS
SECTION 1.00	DEFINITIONS AND ABBREVIATIONS
	1.01 Definitions
	1.02 Abbreviations
SECTION 2.00	GENERAL PROVISIONS
	2.01 General
	2.02 Quality of Materials
	2.03 Inspections
	2.04 Clearing and Grubbing
	2.05 Earthwork
	2.06 Maintenance of Traffic
	2.07 Concrete
	2.08 Permits
	2.09 Acceptance Procedures
	2.10 Planting, Fences, or Structures within City Utility Easements
	2.11 License Requirements
	2.12 Retaining Walls
	2.13 OSHA Standards
	2.14 Safety and Health Hazards
	2.15 Geodetic Monuments
	2.16 Failure to Respond
SECTION 3.00	STREETS, DRIVEWAYS, AND PARKING LOTS
	3.01 General
	3.02 Design
	3.03 Sight Distance
	3.04 Materials
	3.05 Construction and Inspection
	3.06 Fire Lanes
	3.07 Traffic Control and Street Name Signs
	3.08 Traffic Calming Devices
	3.09 Pedestrian Crossings
	3.10 Street Trees
	3.11 Throughfare / Median Plantings
	3.12 Greenway Specifications

SECTION 4.00 SEDIMENTATION AND EROSION CONTROL

- 4.01 General
- 4.02 Applicability
- 4.03 Temporary Measures
- 4.04 Permanent Measures
- 4.05 Stabilization Measures
- 4.06 Slopes
- 4.07 Calculations
- 4.08 Construction Sequence
- 4.09 Minimum Standards for Residential Lots

SECTION 5.00 PIPE TRENCHES

- 5.01 Excavation and Preparation of Pipe Trenches
- 5.02 Pipe Laying and Backfilling
- 5.03 Boring and Jacking
- 5.04 Horizontal Directional Drilling

SECTION 6.00 WATER DISTRIBUTION

- 6.01 Water Distribution Pipe
- 6.02 Fire Hydrants
- 6.03 Valves and Appurtenances
- 6.04 Water Service Taps
- 6.05 Clearance Between Water Mains, Sanitary and Storm Sewers
- 6.06 Backflow Prevention and Cross Connection
- 6.07 Automatic Fire Sprinkler System Standard
- 6.08 Testing and Inspection
- 6.09 Fire Protection during Construction
- 6.10 Irrigation Systems
- 6.11 Repair of Water Lines

SECTION 7.00 SANITARY SEWER

- 7.01 Gravity Sewer Mains
- 7.02 Force Sewer Mains
- 7.03 Manholes
- 7.04 Service Connections
- 7.05 Testing and Inspection
- 7.06 Repair of Sanitary Sewer Lines
- 7.07 Wastewater Pump Stations

SECTION 8.00 STORM DRAINAGE

- 8.01 Storm Drainage Materials
- 8.02 Storm Sewers
- 8.03 Stormwater Impoundments

SECTION 9.00 AS-BUILT DRAWING REQUIREMENTS

- 9.01 As-Built Check List

SECTION 10.00 ENVIRONMENTAL

- 10.01 General
- 10.02 Tree Protection and Preservation
- 10.03 Individual Lot Requirements
- 10.04 Utility Installation Associated with Environmentally Sensitive Areas

STANDARD DETAILS

SECTION 0.00

Design Certification Requirements and General Information for Design Professionals

The City of Dunn Engineering Design and Construction Standards contained herein are to be utilized as a minimum standard for construction within the jurisdiction of the City of Dunn. The purpose of these specifications is to present typical standards for typical conditions encountered. This manual may also be subject to periodic change by the City. Where the specifications or standard drawings differ from the City Ordinance, the City Ordinance shall prevail. When changes are required, revisions will be posted on the City's website. Extensive reference is made to state and federal publications. Unless otherwise indicated, the designer is to use the most current version. It is not the intent of these standard specifications and details to relieve the engineer of record for projects of any responsibility for the correct adaptation of these standards to the actual site conditions encountered on any project. The engineer preparing detailed drawings for a specific project must review the applicable portions of these specifications and details and satisfy himself or herself that these minimum standards will function correctly in his or her particular project. There may be circumstances in which the project engineer will wish to increase the material strengths, stone bedding requirements, reinforcing, etc. In situations where these modifications occur, the City of Dunn recommends that they be consulted regarding these proposed changes prior to plan submittal to the City. This will help insure that plan review takes a minimum amount of time. In order to ensure adequate engineering design, the City may occasionally require more stringent standards than those presented here. Where the designer determines that conformance with this manual would create an unreasonable hardship or where an alternative design may be more appropriate, those items must be submitted to the City for written authorization of the Director of Public Utilities prior to inclusion on construction documents presented for review by the City. In addition, any proposed deviations from these specifications must be clearly shown on the construction drawings, on the cover sheet, with the heading "Exceptions requested to the adopted City of Dunn Engineering Design and Construction Standards." All of these deviations will be subject to approval by the Director of Public Works, or designee. Additionally, on every set of plans submitted to the City for review, the cover sheet or first sheet in the plan set shall have the following certification affixed:

"This project shall be constructed in accordance with the following plans, and the adopted Engineering Design and Construction Standards of the City of Dunn. These plans were prepared in conformance with the approved preliminary plan approved by the City. Furthermore, the engineer whose seal and signature appear below this certifies that the City of Dunn Engineering Design and Construction and Standards have been thoroughly reviewed for applicability to this particular project. Any proposed exceptions or deviations from either the standards and/or form the approved preliminary plan are listed below:"

The professional engineer shall then list such deviations

1. _____
2. _____
3. _____

Signature & Seal of Professional Engineer

**SECTION 1.00
DEFINITIONS AND ABBREVIATIONS**

SUB-INDEX

1.01 DEFINITIONS

1.02 ABBREVIATIONS

SECTION 1.00

DEFINITIONS AND ABBREVIATIONS

1.01 DEFINITIONS

CERTIFICATE OF OCCUPANCY - Approval granted by the City for a new or renovated structure to be occupied.

CITY – The City of Dunn, North Carolina

CODE - The City of Dunn Code of Ordinances.

CONSTRUCTION INSPECTOR - The Construction Inspector, an assistant, or other representative duly authorized by the Director of Public Utilities.

CONTRACTOR – Person or persons performing construction activity, either as a primary or sub-contractor within the City, either for the City, for owners/developers, for utility companies, or any other entity.

DETAILS – The drawings found within the City of Dunn Engineering Design and Construction Standards Manual

DEVELOPMENT PLAN - Specific plans for residential, commercial/mixed use or industrial development of property filed in connection with an Architectural and Site Design Review or development incentives review under the terms of this UDO. A development plan may include, but not limited to: a site plan; landscape plan; Master Sign Plan; lighting plans; building elevations; and pedestrian and vehicular circulation plans, which are reasonably necessary to depict or describe certain information and data as required by this UDO.

DEVELOPMENT PROCEDURES MANUAL – The City of Dunn procedural manual companion document to the Code of Ordinances.

DIRECTOR OF PUBLIC UTILITIES – The Public Utilities Department Director, an assistant, or other representative duly authorized by the Director of Public Utilities.

DIRECTOR OF PUBLIC WORKS – The Public Works Department Director, an assistant, or other representative duly authorized by the Director of Public Works.

EASEMENT - A property right to use or control real property of another.

ENGINEER – A person licensed to practice engineering in the State of North Carolina.

INVERT - The lowest point in the internal cross section of a pipe or other culvert.

MASTER PLAN - A drawing, map, plan or other graphic representation of an overall project, drawn to an appropriate scale by hand or other drawing method, but containing sufficient detail to depict the patterns proposed for an overall project and to determine compliance with the use and development standards provisions of the Code of Ordinances.

OWNER/DEVELOPER - Person or persons who are responsible financially for the construction activity.

PLANS – City-approved plans, profiles, standard details, supplemental plans, and working drawings, which show the location, dimensions, and details of the work to be performed.

PROJECT - Any design, repair or construction activity occurring within the jurisdiction of the City of Dunn.

RIGHT OF WAY - The land area between the back of curb or edge of pavement and the property boundary, including the area containing the street.

STANDARDS - The general term comprising all the directions, provisions, and requirements contained or referred to in this book entitled “City of Dunn Engineering Design and Construction Standards” and in any subsequent revisions or additions to this document.

SUBGRADE - That portion of the roadbed prepared as a foundation for the pavement structure.

1.02 ABBREVIATIONS

AASHTO	American Association of State Highway and Transportation Officials
ABS	Acrylonitrile Butadiene Styrene
AFF	Above Finish Floor
ANSI	American National Standards Institute
ASTM	American Society of Testing and Materials
AWWA	American Water Works Association
BHP	Brake Horsepower
°C	Degrees Centigrade
CO	Certificate of Occupancy
Cy/CuYd	Cubic Yard
DEM	Division of Environmental Management
DHS	Division of Health Services
DIP	Ductile Iron Pipe
DIPRA	Ductile Iron Pipe Research Association
NCDEQ	NC Dept. of Environmental Quality
ETJ	Extraterritorial Jurisdiction
°F	Degrees Fahrenheit
FEMA	Federal Emergency Management Agency
Ft	foot
FTS	Fast Track Sewer Application
FTSE	Flow Tracking For Sewer Extension
GPD	gallons per day

GPM	gallons per minute
HDPE	High Density Polyethylene
HP	Horsepower
HGL	hydraulic grade line
ID	Internal Diameter
In	inches
lbs	pounds
MSL	Mean Sea Level
MUTCD	Manual on Uniform Traffic Control Devices
NCDEQ	North Carolina Department of Environmental Quality
NCDOT	North Carolina Department of Transportation
NCPWS	North Carolina Public Water Supply
NEC	National Electric Code
NFiPA	National Fire Protection Association
NRCS	National Resource Conservation Service
NYDOT	New York Department of Transportation
OC	On Center
oz	ounce
OD	Outside Diameter
OSHA	Occupational Safety & Health Administration
PC	Point of Curvature
PE	Professional Engineer, Registered in the State of North Carolina

PLS	Professional Land Surveyor, Registered in the State of North Carolina
PPM	parts per million
PSI	pounds per square inch
PT	Point of Tangency
PUD	Public Utilities Director
PVC	Polyvinyl Chloride
PVC	Point of Curvature on Vertical Curve
PVT	Point of Tangency on Vertical Curve
PWD	Public Works Director
Q_{max}	maximum discharge
Q_{min}	minimum discharge
RH	Relative Humidity
SCS	Soil Conservation Service
sec	second
Sq Ft	square feet
SU	Single Unit Truck (with 20 foot wheelbase and 30 foot overall length)
Sq Yd	square yard
TDH	Total Dynamic Head
TRC	Technical Review Committee
UL	Underwriters' Laboratories, Inc.
V	Volts
VAC	Voltage - Alternating Current

VDC Voltage (Direct Current)

WB-50 Semitrailer Truck (with 30 foot wheelbase and 55 foot overall length)

END OF SECTION 1.00

**SECTION 2.00
GENERAL PROVISIONS**

SUB-INDEX

- 2.01 GENERAL**
- 2.02 QUALITY OF MATERIALS**
- 2.03 INSPECTIONS**
- 2.04 CLEARING AND GRUBBING**
- 2.05 EARTHWORK**
- 2.06 MAINTENANCE OF TRAFFIC**
 - A. General**
 - B. Materials**
 - C. Installation and Maintenance**
- 2.07 CONCRETE**
- 2.08 PERMITS**
 - A. City Permits**
 - B. State and Federal Permits**
- 2.09 ACCEPTANCE PROCEDURES**
- 2.10 PLANTINGS, FENCES, OR STRUCTURES WITHIN CITY UTILITY EASEMENTS**
- 2.11 LICENSE REQUIREMENTS**
- 2.12 RETAINING WALLS**
- 2.13 OSHA STANDARDS**
- 2.14 SAFETY AND HEALTH HAZARDS**
- 2.15 GEODETIC MONUMENTS**
- 2.16 FAILURE TO RESPOND**

SECTION 2.00

GENERAL PROVISIONS

2.01 GENERAL

All construction, both Development and City projects, shall conform to the requirements and dimensions on City approved construction plans, the City of Dunn Engineering Design and Construction Standards, and the Code of Ordinances of the City of Dunn. The design of streets, water systems, sanitary sewer systems, storm drainage systems, dam design, and grading plans shall be signed and sealed by a licensed North Carolina Professional Engineer in accordance with N.C. General Statute 89. In addition, refer to Section 9 of these standards "As-Built Drawing Requirements."

2.02 QUALITY OF MATERIALS

It is the intent of this specification to provide materials of the highest standard known to the trade and to provide materials free from defects in workmanship and product. Equal materials not specified may be used if provided necessary documentation and samples necessary for the City to determine their acceptability and ISSUE A WRITTEN APPROVAL are provided to him or her a MINIMUM of 30 DAYS before being brought onto the construction site. Current standards and/or the latest revisions shall apply in all cases where materials are described by these standards.

2.03 INSPECTIONS

The Contractor shall provide the necessary manpower and equipment required as a part of the inspection process. The presence of the City's Engineer or Public Works or Public Utilities Staff at the work site shall in no way lessen the Contractor's responsibility for conformity with the plans and specifications. Should the City's Engineer or City Staff accept materials, or work that does not conform with plans and specifications, whether from lack of discovery or for any other reason, it shall in no way prevent later rejection or corrections to the unsatisfactory materials or work when discovered. The Contractor shall have no claim for losses suffered due to any necessary removals or repairs resulting from the unsatisfactory work. Any work which has been covered without the City's Engineer or City Staff's approval, shall, at the City's Engineer or City Staff's request, be uncovered and be made available for inspection at the Contractor's expense. Work performed before or after City staff's normal work hours or during the weekend or City holidays shall comply with the City Code and shall include only such tasks that do not require observation by the City's Engineer, unless previous arrangements have been made for overtime with the City Inspection Services.

2.04 CLEARING AND GRUBBING

The work of clearing and grubbing shall consist of the cutting, removal, and satisfactory disposal of all vegetation and all surface debris. Clearing and grubbing shall be conducted in a manner to prevent damage to vegetation that is intended to remain growing and also to prevent damage to adjacent property. Tree protection fencing shall be installed to protect all areas that are to remain undisturbed or protected.

2.05 EARTHWORK

Earthwork shall be defined as removal of earth or rock from its natural location or as the depositing of such material into fills areas as designated on the plans.

Fill material shall be free from construction material, debris, frozen material, organic matter or unstable material. For the top 2 feet below finished sub grade, no fill material shall be used weighing less than 100 pounds per cubic foot. The top 2 feet of backfill material shall be free from stones greater than 4 inches.

For all areas under a proposed roadway, the sub base, and the entire base course shall be compacted to a density of 100% maximum Standard Proctor dry density as determined by AASHTO method T99. For that portion of fill beyond the back of curb, to the right-of-way compact to a density of NO LESS THAN 98% of the maximum Standard Proctor dry density as determined by AASHTO method T99. Fill material shall be placed in lifts of 8 inches or less of uncompacted soil.

Other fill material shall be compacted to a density of NO LESS THAN 90% of the maximum Standard Proctor dry density as determined by AASHTO method T99. Backfill material shall be placed in lifts of 12 inches or less of uncompacted soil.

In areas where landscaping and vegetation is proposed within the median or behind the back of curb, the top 12" of material shall be prepared to support installation and growth of landscaping and vegetation.

2.06 MAINTENANCE OF TRAFFIC

A. General

When construction occurs in a traffic zone, traffic control devices must be erected, maintained, relocated, and removed in accordance with the plans, specifications, NCDOT Supplement to the MUTCD, and the MUTCD. This requirement shall apply for all construction occurring on public streets, including construction or repairs by utility companies. The MUTCD referred to in this provision shall be the current edition of the Manual on Uniform Traffic Control Devices for Streets and Highways, as prepared by the National Advisory Committee on Uniform Traffic Control Devices, including all standard documents referred to in Section 1A-7 of the MUTCD.

Traffic control devices shall include but not be limited to signs, drums, barricades, cones, delineators, flashing arrow panels, temporary guardrail, temporary concrete median barrier, vehicle-mounted temporary impact attenuators, pavement marking, raised reflective pavement markers, flaggers, and pilot vehicles.

B. Materials

Unless otherwise required, materials used in the fabrication and installation of construction traffic control devices shall be in accordance with the applicable provisions of the MUTCD.

All enclosed lens (Engineers Grade) sheeting required for use on traffic control devices shall have an identification mark on the surface. This mark signifies that the sheeting meets the requirements of Federal Specification L-S-300C for Minimum Reflectivity 1 Sheeting and Tape. The identification mark shall not interfere with the function of the device, but shall be visible both day and under illumination at night without the use of special devices.

C. Installation and Maintenance

Existing public streets or highways shall be kept open to traffic at all times by the Contractor unless permission to close the street, or portions thereof, is granted by the Director of Public Utilities and NCDOT. The City of Dunn Police Department must be contacted BY THE CONTRACTOR A MINIMUM OF 24 HOURS before any streets are closed or partially closed. The Contractor must also contact NCDOT as required prior to closing any street or portions thereof.

Work on any project shall not start until all traffic control devices required for the particular work activity are properly installed.

Traffic control devices shall be properly maintained, relocated as necessary, cleaned and operated during the time they are in use. During periods when use of the devices is not warranted, they shall be removed from the work area, covered, or otherwise positioned so that they do not convey their message to the traveling public.

The location, legends, sheeting, dimension, number of supports, and horizontal and vertical placement of warning signs, barricades, and other traffic control devices shall be as required by the plans or the MUTCD.

Weeds, brush, trees, construction materials, equipment, etc., shall not be allowed to obscure any traffic control device in use.

Competent and properly trained, attired, and equipped flaggers, using "stop" and "slow" paddles shall be provided when two-way traffic cannot be maintained.

The Contractor shall assume full responsibility for the continuous and expeditious maintenance or replacement of all construction warning signs, barricades, and other traffic control devices. The Contractor shall continuously review and maintain all traffic control measures to assure that adequate provisions have been made for the safety of the public and workers. Failure to maintain all traffic control devices in a satisfactory condition shall be cause for suspension of construction operations until proper traffic control is re-established.

2.07 CONCRETE

Concrete shall be only plant-mixed or transit-mixed concrete conforming to ASTM C33 for aggregates and to ASTM C94 for ready-mixed concrete. Any concrete poured that has a slump over 5" inches as per ASTM C143, or has a batched time of more than 90 minutes, will be considered unacceptable. Concrete shall not be deposited on frozen sub grade. Concrete shall not be poured when the air temperature is falling below 40°F and the predicted low temperature for the succeeding 24-hour period is less than 32°F. All concrete when placed in the forms shall have a temperature of between 50° and 90°F and shall be maintained at a temperature of not less than 50°F for at least 72 hours for normal concrete and 24 hours for high early strength concrete, or for as much time as is necessary to secure proper rate of curing and designed compressive strength. Concrete shall be air entrained with 5-7% air. Retarders and accelerators shall be used only as directed by the Engineer.

2.08 PERMITS

Prior to construction of any project, it is the responsibility of the Owner/Developer to insure that any applicable permits from the City, County, and State and Federal Governments are obtained. Following is a list of the most common permits and/or approvals required:

A. City Permits

1. **Construction Drawing Approval:** Every construction site within the City of Dunn shall require the approval of a construction drawing by the Public Works Department. A preconstruction conference shall also be required prior to the beginning of construction.
2. **Work Permit:** The creation of excessive noise associated with construction that is regulated under this document, including but not limited to, erection, alteration, repair or demolition of any earthmoving activities, land clearing activities, street paving, or utility construction in a residential or business district, shall be limited to the guide lines as set forth in the Code of Ordinances and shall require approval by the Departments of Public Utilities & Public Works. Work on Sundays and on holidays shall also require approval by the Department of Public Works. The applicant shall designate an individual person or persons in control of the construction who shall be responsible for seeing that the activity complies with the terms of the approval.
3. **Driveway Permit:** A Driveway Permit is required for all new residential and non-residential driveways on existing City-maintained streets. The location of the driveway shall be shown on a plot plan. This permit may be obtained from the City of Dunn.
4. **Burning Permit:** A Burning Permit shall be obtained prior to any burning. This permit may be obtained from the Dunn Emergency Services, Inc. (DES) for a fee.
5. **Blasting Permit:** A Blasting Permit is required any time there is to be transportation, use or storage of explosive materials. This permit is required a minimum of 24 hours in advance of any explosive materials or blasting agents being transported into the corporate limits of the City. This permit may be obtained from the Dunn Emergency Services, Inc. (DES) for a fee.

6. **Certificate of Erosion Control Plan Approval and Land Disturbance Permit:** An Erosion Control Plan and a Land Disturbance Permit are required whenever the denuded area on a project exceeds the area of disturbance as specified in the City Sedimentation and Erosion Control Ordinance. A Land Disturbance Permit may be issued by Dunn after both Construction Drawings and Erosion Control Plan approval are granted by the City, prior to any grading or site work. No building permits will be issued by the City until Certificate of Compliance (indicating that all sedimentation and erosion control measures are installed) is issued by the City. A Certificate of Completion (also issued by the City) will be required before City acceptance of project infrastructure.
7. **Timbering Plan:** A separate timbering plan is required for timbering or forestry activities and shall be in compliance with the rules of the State of North Carolina and any applicable Erosion Control laws and regulations. Encroachment into buffer or tree save areas must be permitted by the Department of Public Works or the Department of Planning & Zoning as specified in the Code of Ordinances, and be in compliance with the North Carolina Administrative Code 15A NCAC 02B.0311 Middle Cape Fear River Basin: Nutrient Sensitive Waters Management Strategy: Protection and Maintenance of Existing Riparian Buffers.

Additional permits may be required by other departments of the City of Dunn.

B. State and Federal Permits

Applications for State Permits are to be submitted for City approval before submission to the applicable State agency, or as indicated below. **It is the responsibility of the Owner/Developer to ensure all permit applications, fees, and final plans are submitted and approvals obtained by the appropriate agency, after City Board, Technical Review Committee and/or City staff approval. All applicable permits MUST BE OBTAINED PRIOR TO ANY CONSTRUCTION.**

1. **Sanitary Sewer System Extension:** For any proposed extension of the public sanitary sewer system or for the construction of a privately maintained sanitary sewer collection system, a Non-Discharge Permit from the NCDEQ. The plans shall be designed in accordance with these specifications and in accordance with 02T Rules published by NCDEQ. The application for the permit should be submitted for City approval sometime after City approval of construction drawings for the project. Both FTA & FTSE forms shall be drafted by the Site Development Design Engineer. Four copies (2 originals and 2 copies) of the application, a set of plans, and any pump station or gravity sanitary sewer calculations are required for approval by the City. Fee schedules and application forms

may be obtained from the NCDEQ. As-builts and a P.E. certification for the system must be provided to the Construction Inspector prior to the sanitary sewer system being placed in service. Sewer capacities shall not be provided by the City for any project until respective sewer permits for the project are issued from the state. Sewer extension permits shall expire within one year of issuance if construction has not begun. The City may limit the number of units which are permitted in any development, or development phase at any one time.

2. **Water System Extension:** For all public water line extensions 2” and greater, a Water Main Extension Permit from the NCDEQ-PWS must be obtained. The application for a permit should be submitted for City approval sometime after approval of construction drawings for the project. Four copies of the application, 3 sets of plans, 3 Engineer Reports, signed, sealed and dated and any flow calculations are required for approval by the City. Application forms may be obtained from the NCDEQ-PWS. Fees are based upon length of line proposed and can be found in the Permit Application. As-builts and a P.E. certification must be provided to the Construction Inspector prior to the water system being placed in service. Water capacities shall not be provided by the City for any project until respective water permits for the project are issued from the state. Water extension permits shall expire within one year of issuance if construction has not begun. The City may limit the number of units which are permitted in any development, or development phase at any one time.
3. **North Carolina Department of Transportation Encroachment Forms and Driveway Permit:** When any part of the project will encroach on NCDOT right of way, an encroachment form must be submitted and approved by NCDOT prior to construction. All encroachment applications and driveway permits require 5 sets of plans and 5 copies of the encroachment form. Fee schedules and encroachment forms are available from the NCDOT. Design Engineer shall submit information requested by NCDOT on-line encroachment processing procedures.
 - a) For installation of utilities a 3-party agreement between the Developer, the City of Dunn and the NCDOT is required. The fee is determined by NCDOT. The City of Dunn will be the party of the second part.
 - b) For roadway widening, sidewalk installation, addition of curb and gutter, storm drainage, etc., a 2-party agreement between the Developer and the NCDOT is required. Before submitted to NC DOT, the City must first approve proposed improvement plans. The fee is determined by the NCDOT.
 - c) Driveway Permits must be obtained prior to the installation of any driveway cuts to be made on a State maintained road. These

permits must be approved by the City before submittal to NC DOT. The fee is determined by the NCDOT.

4. **North Carolina Division of Water Quality and United States Corps of Engineers Permits:** Appropriate permits for impacts to jurisdictional streams, wetlands and riparian buffers are required for all projects. Permits shall be for all impacts associated with the entire project as defined by a master type plan, unless approved by the Department of Public Utilities. Copies of approval letters and corresponding maps must be provided prior to construction drawing approval unless approved by the Director of Public Utilities. USGS stream information and Harnett County Soil Survey information for all projects are required at initial construction drawing submittal. A Land Disturbance Permit will not be issued for any plan that reflects a discrepancy in the location of any Cape Fear River Basin Buffer rules unless the buffer shown on the plan is more conservative, or NC Division of Water Quality has approved the new location of the buffer.
5. **Federal Emergency Management Agency (FEMA):** Encroachment into floodplains which appear on a map of a community issued by the Federal Emergency Management Agency must comply with the City of Dunn Flood Damage Prevention Ordinance, the North Carolina Department of Crime Control and Public Safety, Division of Emergency Management, Floodplain Management Branch and the Federal Emergency Management Agency Regulation. Final versions of approved studies, map, digital files and as-built information shall be submitted to the Department of Public Utilities for historical reference.

2.09 ACCEPTANCE PROCEDURES

All improvements intended for public maintenance are eligible for acceptance by the City of Dunn following the procedures outlined below:

1. After the installation of improvements in accordance with the City Engineering Design and Construction Standards, and with plans approved by the Council and Directors of Public Utilities and Public Works, the Owner/Developer or designee shall contact the Construction Inspector to schedule a warranty inspection. Note that this inspection must be performed prior to recordation of a final plat for the project.
2. The Public Utilities and the Public Works Departments will respond with a punch list within 10 working days from the punchlist inspection date.
3. The Owner/Developer or designee must complete all items indicated on the punch list, and any additional items noted, within 60 days of the date of the warranty inspection, for the City to accept the infrastructure and

begin one-year warranty. The Owner/Developer or designee must then request another warranty inspection if more than 60 days passes before the punchlist work is complete.

4. In accordance with the Code of Ordinances, building permits will be withheld on any project that does not receive a Beginning of One Year Warranty Acceptance Letter by the time 25% of the building permits are issued for a platted phase of a project.
5. Upon the acceptable completion of all punch list items and payment of any outstanding fees, the Owner/Developer or designee will receive a Beginning of One Year Warranty letter from the City of Dunn. This acceptance begins a warranty for materials and workmanship of not less than 1 year in duration from the date of acceptance. The warranty will be to the City from the Owner/Developer or designee. The City will perform routine maintenance during the warranty period.
6. A warranty bond is required to guarantee the workmanship and materials during the warranty period. Refer to the City Code of Ordinances for more information.
7. Sixty days before the end of the warranty period, the Owner/Developer or Designee shall request a final (end of one year warranty) inspection from the Construction Inspector.
8. The Public Utilities and the Public Works Departments will respond with a punch list on workmanship or materials within 30 days of the request.
9. The Owner/Developer or designee must complete all items indicated on the punch list, and any additional items noted, within 60 days of the final inspection. The Owner/Developer or designee must request another final inspection if more than 60 days passes before the punchlist work is complete.
10. Upon the acceptable completion of all final punchlist items, the Owner/Developer or designee will receive a final evaluation of One Year Warranty Acceptance Letter from the Public Utilities and the Public Works Departments. The City will begin total maintenance of the project as of the date of the letter.
11. In accordance with the City of Dunn Code of Ordinances, building permits may be withheld on any project that does not have an End of One Year Warranty Acceptance Letter by the time 75% of the building permits are issued for the project.

Until an End of One Year Warranty Acceptance Letter has been issued, all materials and workmanship are the responsibility of the Owner/Developer.

2.10 PLANTINGS, FENCES, OR STRUCTURES WITHIN CITY UTILITY EASEMENTS

An “easement” shall mean any area to which the City has unlimited access for servicing utility lines. Any plantings installed within an easement may be damaged or destroyed during the course of servicing. The City will not be liable for any damage to plantings, fences, accessory structures located either within an easement or in any manner restricting access to the easement. Further, the City shall not be liable for any incidental or consequential damage caused by the City’s removal of any structure impairing the easement. Any contractor or landowner who has impaired the easement by allowing an obstruction to be placed on the easement shall indemnify and hold harmless the City for any resulting incidental or consequential damages. The City will reseed as necessary any bare or disturbed soil for erosion control purposes.

Small and medium shrubs, groundcovers, or grasses may be planted by the property owner within an easement (subject to the preceding paragraph) and as long as those planting do not inhibit access of the easement with required equipment by the City and/or its agents.

Large trees, fences, gates, or any type of structures (e.g. retaining walls or utility sheds) shall not be placed within any City utility easement.

2.11 LICENSE REQUIREMENTS

All Contractors performing any construction activity involving the City of Dunn utility system or street system shall be licensed to practice general contracting in the State of North Carolina. The Contractor shall be classified in the appropriate area of license for the type of construction to be performed and shall not perform construction activity which exceeds the limitations of the designated Contractor’s license.

2.12 RETAINING WALLS

All retaining walls with a height of 3 feet or greater must be designed by a Professional Engineer and shall be signed and sealed. Design and construction drawings shall be submitted to the Director of Public Works for approval prior to construction. All necessary permits (e.g., building permit) must be obtained prior to any construction associated with retaining walls. Safety rails or fencing may also be required.

2.13 OSHA STANDARDS

All Contractors and their employees must comply with all OSHA standards while working on City projects, while on City of Dunn property or rights of way, and for all development projects within the City of Dunn.

2.14 SAFETY AND HEALTH HAZARDS

The operations of any Contractor shall not expose City of Dunn employees or residents to any hazardous chemicals or other occupational safety and health hazards. All Contractors working on City projects or on City of Dunn property or rights of way shall inform every individual who enters the project concerning hazardous chemicals which the Contractor might be using and to which the individual might become exposed by working in that area.

2.15 GEODETIC MONUMENTS

NAD83 Geodetic monuments must be tied to the project when the project is within 2000 feet of a monument. .

2.16 FAILURE TO RESPOND

Where the Project Owner does not respond to directives by the City to complete certain repairs and/or work that, in the City's opinion, causes a safety hazard or the potential for damages, the City may have such work performed and charge the project owner all associated expenses plus a 25% mobilization fee (examples: trench repairs, street washing, etc.). This section shall not create an obligation of the City to undertake such work or to be liable in any way for failure to undertake such work. The time frame for responding to the City's directives shall be as directed by the Public Works Director.

END OF SECTION 2.00

**SECTION 3.0
STREETS, DRIVEWAYS, AND PARKING LOTS**

SUB-INDEX

3.01 GENERAL

3.02 DESIGN

- A. Street Classifications for City Specifications**
- B. Horizontal Street Design**
- C. Vertical Design**
- D. Geometric-Radii**
- E. Cul-de-sacs**
- F. Driveways/Access**
- G. Curb and Gutter**
- H. Parking Lots/Off Street Parking**
- I. Sidewalks**
- J. Pavement Design**
- K. Pavement Markings and Signage**
- L. Bridge Design**
- M. Shoulder Sections**
- N. Roadway Connectivity**
- O. Phased Construction**

3.03 SIGHT DISTANCE

- A. Intersection Sight Distance**
- B. Stopping Sight Distance**

3.04 MATERIALS

3.05 CONSTRUCTION AND INSPECTION

- A. Streets**
- B. Curb and Gutter, Driveways, and Sidewalks**

3.06 FIRE LANES

3.07 TRAFFIC CONTROL AND STREET NAME SIGNS

3.08 TRAFFIC CALMING DEVICES

3.09 PEDESTRIAN CROSSINGS

**SECTION 3.00
STREETS, DRIVEWAYS, AND PARKING LOTS**

3.10 STREET TREES

3.11 THOROUGHFARE MEDIAN PLANTINGS

3.12 GREENWAY SPECIFICATIONS

3.01 GENERAL

The latest revision of the *Standard Specifications for Roads and Structures* of the North Carolina Department of Transportation shall apply unless otherwise specified herein.

Whenever the following terms are used in above said specifications the intended meaning of such terms shall be as follows:

“State” or “Commission” shall be replaced by “City of Dunn.”

“Resident Engineer” shall be replaced by the words “Director of Public Utilities.”

“Sampling and testing by Commission” shall be replaced by the words “sampling and testing by the City or its authorized testing agent.”

“Inspection by Commission” shall be replaced by “Inspection by City or its duly authorized representative.”

3.02 DESIGN

All streets (private and public) shall be designed and fully constructed to the City of Dunn Engineering Design and Construction Standards in accordance with all ordinances and policies of the City. Refer to the City of Dunn Code of Ordinances for requirements for improving existing thoroughfares and streets. NCDOT standards shall be used on all existing State roads, extensions of existing State roads, or roads to be maintained by NCDOT.

Street design is based primarily on criteria dictated by the street classification, design speed, surrounding terrain, and traffic volumes. The following factors shall also be considered in determining street and right-of-way widths: urban-type development, on-street parking, alley-loaded units, zoning, depth of lots (length of driveways), garages, street trees, street network, setbacks, street classification, speed limit, and sidewalks. The Technical Review Committee shall make the final approval for necessary street and right of way widths for the City of Dunn. The following is intended to be recommended street and right of way widths minimum. Specific information and documentation on development and/or product types to be serviced by roadways should be provided for consideration of street widths, and such information may be incorporated into development and/or plan approval conditions.

Note that a Transportation Impact Analysis may be required to accompany plans submitted to the City for consideration of traffic impacts due to development according to the City of Dunn Code of Ordinances.

In special circumstances, the City may elect to require payment of a fee-in-lieu of installation of roadway improvements.

A. Street Classifications for City Specifications

*See above paragraph regarding factors that determine street cross-section and right-of-way section. Early communication (in preliminary design) with the City of Dunn to determine the appropriate street and right-of-way width for the particular development is encouraged. The following street cross sections comprise the most typically utilized sections for the City. The details at the end of these design and construction standards include additional cross sections that are utilized when other factors are considered. Note that reduced roadway cross sections may be permitted for streets serving areas for which a master land use plan is approved, with approval of the Technical Review Committee.

In areas where an entrance median is desired, the width of the median shall be in addition to required cross sections as specified.

1. Minor street (and/or Alley)

Typical width: 25 feet of pavement on 50-foot public right-of-way

All alleys are primarily for service access to the back or side of properties.. They are encouraged in neo-traditional and mixed use developments, and adjacent to limited-access facilities. The purpose of an alley is to provide utility and vehicular access along the rear or side of new residential and non-residential structures. All alleys are to be maintained with measures to ensure the travel way is not obstructed in any manner, including by parking or loading. Proof roll inspection shall be required for an alley. A drainage system shall be provided and shall conform to all public street design drainage standards as outlined in this Manual.

The City shall not be responsible for damage occurring to the pavement structure due to use of the private alley for access in providing public services. When alleys are used for the provision of these services, the Homeowner Association covenants for the development shall clearly state this. Alleys shall be constructed on a 50-foot public or private right-of-way with a paved travel lane of 25 feet, and clear shoulders of a minimum width 4.5 feet along each side.

Under unique, site-specific circumstances, including such factors as the absence of utility lines in the alley and/or lack of real property, consideration of a reduction of rights of way and travel lane width may be made.

2. Residential Cul-de-sac (800 feet maximum)

Typical width: Typical width of street determined by residential street. Minimum pavement radius of cul-de-sac 40' from center of cul-de-sac minimum radius of r/w shall be 50'.

A street which serves abutting residential land use and which terminates in a turnaround and originates at the intersection with another street. With the exception of cul-de-sacs, other street types shall not intersect onto this street classification segment. Cul-de-sacs shall only be permitted on a case-by-case basis where extreme topographical or environmental concerns exist, or where future connection to other streets is impossible due to pre-existing development.

3. Residential Street

Typical width: 30 feet face to face on 50-foot right of way

A street where the primary function is to serve the immediately abutting residential land use, i.e., only local traffic generated by the residents in proximity of the street. In this classification, traffic volumes flowing from other intersecting residential streets shall not exceed the traffic volumes generated by the land use abutting the street, and this street classification shall not serve more than 150 dwelling units. Where the design will accommodate double sided on-street parking the Director of Public Utilities shall be consulted for the minimum width. Additional pavement marking and signage may be required where on-street parking is prohibited.

4. Commercial Cul-de-sac

Typical width: Minimum pavement radius is 50' with minimum r/w of 65'.

A street which serves abutting non-residential land uses and which terminates in a turnaround and originates at the intersection with another street. With the exception of cul-de-sacs, other street types shall not intersect onto this street classification segment. This street may require additional turn lanes on either of the intersecting streets at the street intersection.

5. Residential Loop Street

Typical width: 30 feet face to face on 50-foot right of way

A street which serves abutting residential land use and which terminates on the same street from which it originates. Short residential cul-de-sac streets may be considered to intersect onto this street classification segment. Where the design will accommodate on-street parking the Director of Public Utilities shall be consulted for the minimum width of street and right-of-way. Additional pavement marking and signage may be required where on-street parking is prohibited.

6. Sub Collector Street

*Typical width: 34 feet face to face on 55-foot right of way
no on-street parking permitted*

A street, which serves traffic, generated by proximity land, which may include, uses other than residential. Design shall accommodate the vehicle type expected to use the facility which is typically larger than a passenger car. Where the design will accommodate on-street parking the Director of Public Utilities shall be consulted for the minimum width of street and right-of-way.

7. Collector Street

*Typical width: 40 feet face to face on 60 feet of right of way –
no on-street parking*

A street which serves various land use classifications, and whose primary function is traffic service, collecting traffic from streets intersecting it and funneling it to major streets. A collector street shall be provided when the roadway is the sole traffic route for more than 100 dwelling units, collects traffic from a commercial area of 20 acres or more, or contains other land uses which would account for similar traffic volumes. Where the design will accommodate double sided on-street parking the Director of Public Utilities shall be consulted for the minimum width of street and right-of-way. Additional pavement marking and signage may be required where on-street parking is prohibited.

If project frontage is within 500 feet of a major intersection, additional turn lanes and right of way widths may be required as determined by the Director of Public Utilities, NCDOT, and a Transportation Impact Analysis.

8. Major Street

Typical width: 48 feet face to face on 80 feet of right of way. On street parking is prohibited. A Transportation Impact Analysis is required.

A street which serves as a primary traffic artery of the urban area, serving the major centers of activity and carrying traffic between such centers at moderate speeds. Access to abutting property may be permitted by the Director of Public Utilities only on a very limited, controlled basis and in cases of a divided roadway will be limited to right in/right out unless a median and turn lanes are approved. However, the primary function of this street is to carry traffic having origin and destination removed from the street proper. The thoroughfare classifications carry the majority of trips entering and leaving the urban area as well as the through trips. Access is primarily provided by at-grade intersections which may be signal controlled.

A slope easement of 20 feet in width shall be required adjoining each side of the right of way for this type of facility unless the complete facility is being constructed as part of the adjoining property development. The Director of Public Utilities may reduce or increase the slope easement width if necessary due to terrain.

If property owner submits to the Director of Public Utilities (prior to construction drawing or preliminary plan approval) sufficient information to show that improvements to be located in the slope easement do not interfere with the right of the public to construct within adjoining right of way, then the Director of Public Utilities may permit the proposed improvement to occur.

If project frontage is within 1000 feet of a major intersection, additional turn lanes and right of way widths may be required as determined by the Director of Public Utilities, NCDOT, and Transportation Impact Analysis. .

9. Highway

Typical width: 48 feet face to face on 80 feet right of way. A Transportation Impact Analysis is required.

An urban major roadway where sole function is to carry large volumes of traffic safely and expediently through the urban area. Access onto the facility is controlled to occur only at intersections with major streets or in some cases limited to right-in/right-out access subject to approval by the Director of Public Utilities and NCDOT. Such intersections are spaced at intervals which promote traffic progression with the absolute minimal delays incurred. The highest practical level of design shall be incorporated into facilities of this classification.

A slope easement of 20 feet in width shall be required adjoining each side of a street right of way unless the complete facility is being constructed as part of the adjoining property development. The Director of Public Utilities may reduce or increase the slope easement width if necessary due to terrain.

If property owner submits to the Director of Public Utilities (prior to construction drawing or preliminary plan approval) sufficient information to show that improvements to be located in the slope easement do not interfere with the right of the public to construct within adjoining right of way then the Director of Public Utilities may permit the proposed improvement to occur.

If project frontage is within 1000 feet of a major intersection, as determined by NCDOT, then additional turn lanes and right of way widths may be required by NCDOT in accordance with the approved Transportation Analysis.

B. Horizontal Street Design

All streets shall conform to the NCDOT Standards and shall be designed and located in proper relation to existing streets and environment. Collector streets, thoroughfares, and boulevards shall be as directional as possible but consistent with topography and preserving developed properties and community values. Residential streets shall be designed to minimize cuts and fills, and emphasis shall be placed on encouraging slower speeds in order to protect pedestrians using the facility and minimize persistent cut through traffic.

The design of streets shall conform to the horizontal curve controls in Figure 1 at the end of this chapter.

A minimum tangent of 150 feet is required between reverse curves for major streets, highways, boulevards, and collector streets. The tangent shall be extended as necessary to provide the minimum runoff lengths for the superelevated curves per AASHTO guidelines. The minimum tangent length approaching an intersection is 30 feet for residential streets. All intersections of streets classified as collector or greater shall have a tangent section not less than 100 feet approaching the intersection.

Compound horizontal curves with the same direction of curvature shall have the radius of the flatter circular arc no more than 1½ times the radius of the sharper circular arc. Streets shall intersect each other at right angles whenever possible. The minimum desirable intersection angle is 80°. At no time shall a street intersect any other street at less than 75°.

Intersections with thoroughfares, boulevards, or highways shall be at least 800 feet apart. There shall be a minimum of 200 feet between centerlines of street jogs on collectors, boulevards, and major streets. Residential and marginal access streets shall not be offset less than 125 from their centerlines.

Thoroughfares, boulevards, and collectors shall be superelevated. Superelevation shall conform to Figure 1 at the end of this chapter and shall conform to NCDOT and AASHTO standards.

Tapers shall be used as necessary in street design. Approach tapers shall be used to shift lanes laterally. The following equations shall be used as applicable:

Design Speed = Post speed plus 5 mph minimum Design Speed is 30 mph

$L = WS$ for design speeds of greater than 40 mph

$L = WS^2 / 65$ for design speeds of 40 mph or less

L = Length in feet

S = Speed in miles per hour

W = Lateral offsets in feet

Turn bay tapers shall be at least 100 feet for posted speeds of 45 miles per hour and more. The minimum turn bay taper allowed is 8:1. Symmetrical reverse curve tapers are recommended for streets classified as collector or less. Storage lengths for the turn bays shall be calculated using an acceptable method.

Streets with medians shall be designated to allow for proper turning movements for a SU (single unit truck) design vehicle. AASHTO guidelines shall be utilized for the actual median design and median opening dimension.

C. Vertical Design

Street grades shall be established with respect to existing topography to avoid excessive grading and the removal of existing trees and vegetation whenever practical.

The minimum grade allowed on any street shall be ½%.

The maximum grade allowed when approaching an intersection is 5% for the last 100 feet of pavement before the intersection unless otherwise approved by the Director of Public Utilities.

The vertical curve controls found in Figure 1 at the end of this chapter shall also be utilized in street design.

D. Geometrics-Radii

A minimum radius of 25 feet to the face of curb shall be required where residential streets intersect.

A minimum radius of 30 feet measured to the face of curb shall be required where a residential street intersects with a non-residential street. It is recommended that the designer consider larger radii or 3-centered compound curves where needed to provide for turning movements of larger vehicles.

A minimum radius of 40 feet shall be required where collectors intersect thoroughfare or boulevard streets.

E. Cul-de-sacs

The minimum allowable cul-de-sac radius is 40 feet residential and 50 feet for commercial. The maximum allowable length of a cul-de-sac is 800 feet, measured from the last point of alternate access. The variance must be approved by the City Board upon recommendation by the Director of Public Utilities and public safety officials. Additional emergency secondary access may be required in these circumstances.

No median shall be allowed in a 40-foot radius cul-de-sac. A median may be permitted where the cul-de-sac radius is increased and it can be demonstrated that all emergency and service vehicles can be readily accommodated.

F. Driveways/Access

1. General

In the interest of public safety and convenience, the City of Dunn may restrict the placement of a driveway to a particular location along the property owner's frontage. Driveways will not generally be allowed along acceleration or deceleration lanes and associated tapers. No driveway will be allowed within the intersection of radii of intersecting roadways.

2. Non-residential

Standard concrete driveway aprons as shown in the Standard Detail Section of these Standards shall be used when the development has less than 200 parking spaces.

Street type turnouts shall be used when the development has 200 or more parking spaces or when access by larger trucks must be accommodated, as approved by the Technical Review Committee. The minimum radius for street type turnouts shall be determined by the type of vehicles which utilize the driveway on a daily basis. The maximum vertical grade allowable for a distance of 25 feet into the

site from the right of way line shall be 8%. In addition, the designer shall insure that adequate sight distance for all driveways is provided in accordance with AASHTO Standards.

Non-residential driveways that are unpaved shall have a minimum 30-foot paved surface strip measured from the back of the driveway apron.

Driveways without islands shall be a minimum of 22 feet wide, excluding curb and gutter. Driveways with islands shall have a 16-foot entrance lane, excluding curb and gutter. A 14-foot wide exit lane shall be required when only one lane is specified, and a 22-foot wide exit lane shall be used when two exit lanes are specified (all minimum measurements stated exclude curb and gutter). A minimum distance of 80 feet shall be required at all egress and ingress points from major streets and highways.

The number of street and driveway connections permitted serving a single property frontage or commercial development shall be the minimum deemed necessary by the City of Dunn for reasonable service to the property without undue impairment of safety, convenience, and utility of the roadway. Normally, one driveway shall be permitted for any single property frontage. The use of shared driveways and joint access easements may be required for new accesses to "managed access" roadways.

The arrangement of driveways should be related to adjacent driveways and nearby street intersections. Driveways close to street intersections shall be at least 25 feet from the point of tangency of the radius of curvature of the intersecting street. All driveways serving shopping center and other high volume generators shall be located a minimum of 200 feet from the intersection of public roads unless otherwise approved by the Director of Public Utilities.

Where two driveways are proposed and approved along a single property frontage to facilitate operations, the minimum distance between the centerlines of the drives shall be 100 feet. The minimum distance between the centerlines of driveways into shopping centers and other high volume generators shall be 400 feet.

For all median divided roadways, all driveways shall be limited to right in/right out unless located at approved planned median breaks.

3. Residential

Residential driveways shall measure 12 feet wide from the curb cut to the right of way for a single car garage/driveway, shall measure 16 feet wide from the curb cut to the right of way for a double or greater car garage/driveway, and shall conform to the applicable Standard Detail for concrete driveway aprons. A minimum driveway length of 20 feet shall be provided between any building and the right of way line for single-width parking areas and 25 feet shall be required

for double-width parking areas. Triple-width parking areas shall require a site plan review and approval and may require additional length.

All lots shall be served off the more minor classification of roadway, and there shall be only one driveway per residential lot.

Residential driveways shall be located a minimum of 10 feet from the point of tangency of curb radii at street intersections. Additional distance will be required for roadways classified as collectors and higher.

G. Curb and Gutter

Curb and gutter shall be required on all streets and parking lots, unless otherwise approved by the Director of Public Utilities. Exceptions may be granted by the Director of Public Utilities in instances where:

1. The curb and gutter will only be temporary in nature;
2. There are environmental restrictions;
3. Drainage problems will be created;
4. Long term goal of the City's Street Network;
5. There are conflicts with installation

Streets without curb and gutter may also be approved in very low density, wide-frontage lots, and must meet all of the following requirements and be approved by the City of Dunn:

1. Minimum 60-foot rights of way;
2. 5% maximum vertical grade and 0.5% minimum grade;
3. Adequate swale system to carry the 10 year storm in a non-erosive manner – this must be demonstrated by performance during the one-year warranty period or a change in the material of swales will be required;
4. Driveways across swales shall be constructed to provide for the passage of the 10 year storm;
5. All driveway pipes shall have flared end sections or headwalls on inlet and outlet ends of the pipe.

Variances for curb and gutter may not be issued for streets classified as collector or greater. All streets located in multi family developments shall have standard 2'6" curb and gutter. For other streets, 2'6" standard or 2'6" valley curb and gutter may be used. Median curb shall be a minimum width of 2'0" standard mountable curb or 2'0" to 2'6" standard curb and gutter. In parking lots, curb and gutter may be 2'0" or 2'6" standard curb and gutter or granite curb to match existing conditions.

Where 2' 6" standard curb and gutter is used, driveway and utility service locations shall be shown in detail on construction drawings.

A minimum 5-foot section of curb and gutter shall remain when removing any section of curb for the installation of a driveway, street turnout or repair of curb and gutter. When less than 5 feet of the curb remains, the full section of curb shall be removed to the next joint. Full removal of both the curb and gutter is required when installing a driveway.

For parking lots, cut and fill slopes shall not begin immediately at the back of curb, instead a minimum 4 foot shoulder for fill slopes or 2 foot shoulder for cutslopes is required behind the back of curb. For roadways, cut and fill slopes shall begin outside a minimum 10' or 12' shoulder as shown on the details.

On streets a minimum depth of 4 inches of I19.0B shall be placed under the curb and gutter and the sub-base shall have a minimum compaction of 100% Standard Proctor.

H. Parking Lots/Off Street Parking

Parking lots shall be designed to provide safe maneuverability of vehicles. A minimum parking stall dimension of 9' x 20' shall be provided. An aisle width of 24 feet (two-way) is required on all sites. Handicap parking spaces shall reserve a minimum dimension of 8' wide with a 5' wide access aisle adjacent to the space (and must include one (1) 8' wide access aisle for Van Accessibility), properly marked with signage in accordance with the N.C. Building Code. All parking facilities shall have dimensions per Figure 2. All minimum stall depths and module widths shall be measured to the face of curb when curb and gutter is used. Wheel stops, when used, shall be placed 2 feet from the center of the wheel stop to the face of the curb or edge of pavement.

At locations where sidewalk and/or walkway abuts a 20-foot deep parking bay, the sidewalk shall be a minimum of 6 feet wide.

A minimum pavement structure consisting of 8 inches of ABC and 2 inches of I19.0B and 2 inches of S9.5B shall be used along the travel aisle on parking facilities for multi-family (excluding duplex and triplex development) and non-residential developments. Access drives for these facilities shall also meet this minimum pavement standard.

All paved parking facilities shall be striped in accordance with the MUTCD with 4-inch white lines, other than fire lanes, which shall be yellow.

On all parking facilities, cut and fill slopes shall not begin immediately at the back of curb, instead, a minimum 4 foot shoulder for fill slopes and 2 foot shoulder for cut slopes is required behind the back of curb.

I. Sidewalks

Sidewalks shall be constructed within the street right of way or public easement in accordance with these standards at locations as specified in the City of Dunn Pedestrian Plan. Sidewalks shall be installed at the time of roadway construction or widening unless otherwise approved by the City of Dunn. The minimum thickness of a sidewalk shall be 4 inches. At locations where a driveway crosses a sidewalk, a 6-inch depth is required. (Sidewalks shall have a uniform slope toward the roadway of $\frac{1}{4}$ inch per foot.) The utility strip between the sidewalk and the back of curb shall not be less than $\frac{1}{4}$ inch per foot nor greater than $\frac{1}{2}$ inch per foot toward the roadway.

Sidewalks are to be located a minimum distance of 5 feet off the back of curb. In some cases, where street trees are to be located between the curb and the sidewalk, this distance is preferred to be increased to be a minimum of 7 feet. Refer to approved construction drawings for each project to determine this setback. This minimum requirement may not be varied without the approval of the City of Dunn.

Where sidewalks and/or greenways intersect any section of curb and gutter, a handicap ramp shall be installed in accordance with current ADA Code.

J. Pavement Design

A pavement design shall be required for all thoroughfares, boulevards, and collector streets. The pavement design and traffic analysis shall be signed and sealed by a North Carolina Professional Engineer. Pavement design shall be based on subgrade conditions, a 20-year design life and projected traffic loading. Subgrade conditions shall be based upon corrected soaked CBR values at 0.1 inch penetration as per ASTM D1883. Soil samples used for these CBR tests shall be obtained at intervals not greater than 500 feet. Should a Professional Engineer with expertise in geotechnical engineering certify that the soil in question is of the same type with similar engineering properties this spacing may be increased to a 700-foot maximum spacing. Boring logs and scaled drawings designating boring locations with CBR tests and other pertinent data shall accompany the pavement design.

The pavement thickness of any street shall, at a minimum, equal the design shown in the Standard Details section of these standards for the various street widths.

Approved pavement design methods include those as proposed by NCDOT, the 1986 AASHTO Guidelines and the 1981 Asphalt Institute MS 1 document.

The AASHTO method will require use of a terminal serviceability index of 2.0 for collectors and 2.5 for major streets and highways, $S_o = 0.49$ for flexible pavement and $S_o = 0.39$ for rigid pavements, a reliability of 98% for major streets and highways and a reliability of 95% for collectors.

All streets maintained by the NCDOT must receive approval of the pavement design from NCDOT prior to the beginning of construction. Normal crown for

the pavement section shall be ¼"/foot, except as approved for superelevated cross-sections.

K. Pavement Markings

All roadways shall be marked and signed in accordance with the latest revisions of the MUTCD unless otherwise approved by the Director of Public Utilities. Pavement markings and signage shall be shown on roadway and subdivision plans and shall be installed prior to the issuance of Certificates of Occupancy for the development or final acceptance of the roadway. The pavement markings for all collector streets, thoroughfares, and boulevards, shall be thermoplastic.

The pavement markings along thoroughfares or boulevards shall be installed such that the outside lanes are 13 feet in width to accommodate bicycle traffic unless otherwise approved by the Director of Public Utilities.

At any time prior to 1 year warranty additional pavement markings and/or signage may be required by the Director of Public Utilities, at the developer's expense.

L. Bridge Design

All public or private bridges shall be designed to withstand HS-20 highway loading unless otherwise approved by the City of Dunn and shall be properly signed and sealed by a North Carolina Professional Engineer.

M. Shoulder Sections

Shoulders shall be sufficient to permit the adequate installation and maintenance of sidewalks and utilities, as well as provide sufficient clear zone distance as defined by NCDOT.

Shoulder sections without sidewalk shall be 12 feet wide on all streets with a cross section of 35 feet and greater.

Shoulder sections without curb and gutter must be a minimum of 6 feet wide.

N. Roadway Connectivity

A Connectivity Index shall be calculated for each subdivision, and shall be required to exceed 1.2 unless otherwise approved by the Director of Public Utilities due to unusual topographical restraints. This index shall be calculated by dividing the total number of street lengths (street sections between intersections including cul-de-sacs) by the number of street nodes (intersections plus cul-de-sacs). Calculations should not include adjacent streets. In addition, intersections shall be spaced no more than 1200 feet to 1500 feet in each direction.

Developments shall provide at least one vehicular access to each abutting property. This shall be accomplished via a public street and/or by joining

adjacent parking lots and sharing driveways, at the discretion of the Director of Public Utilities. Development plans accomplishing this with parking lots and/or sharing driveways should provide a cross-access easement and complete the connection if an immediate benefit can be derived by completing the link. If no immediate benefit can be derived, development plans should provide cross access and construction easements and arrange the site design so when the adjoining property owner extends the connection to the property line, the link will be completed. If the link is to be completed in the future, the grade of the connection, parking, landscaping and/or other improvements must be designed and installed to allow for extension onto or into the adjacent properties in the supporting engineering design and calculations being provided.

For roadways that stub-out to adjacent properties, sufficient information shall be provided to demonstrate the feasibility of extending the roadway to the adjacent properties. This shall include both plan and profile information for the extensions. In the event that the roadway, when extended, will cross a stream or creek, the vertical and horizontal alignment design for a minimum distance of 100 feet, plus City culvert report shall be completed. Design shall be per City geometric standards. Information on State and Federal regulatory permit ability shall also be provided to further demonstrate feasibility of the extension. In some instances, these permits may be required.

Whenever possible, internal access drives should be located to join together at existing public streets and/or connect to adjacent private drives so that the internal circulation functions as an integral part of the surrounding transportation network.

Where street networks have been approved with master plans of nearby developments, streets shall be designed for interconnection with those plans.

O. Phased Construction

Any development with more than 200 dwelling units must have a secondary means of access during all phases of construction. Roadway construction may not be phased in such a manner to create a dead-end roadway or roadway network exceeding 2000 feet in length, or serving more than 200 dwelling units. Where a development plan or master plan has been approved and a development schedule can be provided that documents completion of future phases to eliminate the dead-end exceeding 2000 feet within a reasonable time frame, the Director of Public Utilities may approve an exception to this requirement if an alternate emergency access is approved and provided in the interim period. The Director of Public Utilities reserves the right to mandate more restrictive requirements after consultation with the other Department Directors or for other extenuating circumstances.

3.03 SIGHT DISTANCE

A. General

Sight distance shall mean the length of roadway visible to the driver traveling along the roadway or waiting to enter or cross the roadway. The sight triangle shall include both the horizontal and vertical plane and shall exist at all street intersections, multi-family, site, and non-residential driveway intersections.

It shall be the responsibility of the designer for all proposed developments, including site, subdivision, landscape, infrastructure, and sign plans to meet these requirements as a part of the plan project design and approval process. Between the latest version of AASHTO and the Standard's stated herein, the more restrictive standard shall apply.

Some objects located within sight distance areas may not significantly obstruct the required visibility of the driver. The driver may be able to see over, under, or around some objects within sight distance areas. Objects that may be required within sight distance areas include fire hydrants, utility poles and traffic control devices, which should be located to minimize visual obstruction. Other objects 12 inches in diameter and smaller, such as tree trunks and sign posts, may be allowed within sight distance areas if located individually or in combination so as to not substantially restrict the driver's view. The determination of what objects, if any, may be located within sight distance areas shall be made by the Director of Public Utilities. Trees greater than 12 inches in diameter and located in the street right of way shall be evaluated in accordance with other applicable City policies and requirements.

It is recognized that in some cases conditions may exist that prevent the attainment of desirable sight distance due to social, economic or environmental consideration. In such cases, the maximum practical sight distance, up to the desirable values, shall be obtained. In addition, where desirable sight distance is not attained, additional measures, such as warning signs, reduced speed zones, and other traffic controls may be imposed. In all cases, unless otherwise provided by Ordinance or granted an exemption, the minimum provision of adequate stopping sight distance shall be required.

The information and tabular data herein are provided as a guideline. The registered engineer shall ultimately be responsible to determine the design criteria and design.

B. Intersection Sight Distance

In order for vehicles to safely maneuver into or through an intersection, sufficient sight distance must be provided so as to avoid collisions. The horizontal line of sight is a visual line connecting the driver's eye and the approaching vehicle, both of which are in the center of the travelway in this section. If this line of sight is impeded by any obstructions, either the obstruction should be moved or the alignment adjusted. The vertical stopping sight distance is measured along the centerline of the major street between the drivers of the two opposing vehicles. The vertical line of sight is a visual line connecting the driver's eye, which is located 3.5 feet above the roadway surface, with the approaching vehicle, which is located 4.25 feet above the roadway surface. If this line of sight is impeded by any obstructions, either the obstruction should be moved or the alignment adjusted.

The amount of sight distance required at an intersection depends on the type of traffic control at the intersection and the speeds of the vehicles.

1. Yield Sign Control

This type of design requires that the side street be posted with yield signs. The sight distance for the driver on the side street must be sufficient for the driver to observe a vehicle on the through street approaching from either the left or the right and bring his/her vehicle to a stop prior to reaching the intersection. The assumed operating speed approaching the yield sign is 10 mph resulting in a stopping sight distance of 45 feet. Where proper sight distance cannot be achieved for the driver on the side street at the design speed of the roadway, it may be necessary to have a posted speed reduction on the approach to the intersection or to replace the yield sign with a stop sign. Due to the possibility that a vehicle must stop at the yield sign, adequate sight distance at the intersection shall be provided for safe departure from a stopped condition as required by the section on stop sign controlled intersections.

2. Stop Sign Control

At approaches to intersections that are controlled by stop signs or at driveways and alleys where the driver is required to stop before entering the street the driver must have an unobstructed view of the entire intersection and adequate sight distance for any of the various vehicular movements allowed upon departure of the intersection. These movements may include crossing the street, turning left or turning right onto the street. Where the through street is either undivided or divided with a median narrower than 20 feet, the crossing or left turn movements are treated as a single operation. Where the median can provide storage for the design vehicle (20 feet wide for a passenger car), the crossing or left turn movement may be considered in two phases of operation. The measurement method for determining the sight line for left, right, and

through movements from the side street is based on values listed in Table 3.1 on the following page.

An obstruction to the driver's view shall not be located within the sight triangles as defined herein to permit adequate view of the intersection. In addition, there shall be no sight obstruction located in the triangular areas to allow for safe departure through the intersection. The measurement of intersection sight distance is along the centerline of the appropriate lane of the roadway and is measured from an eye height of 3.5 feet above the surface of the roadway to an object 4.25 feet above the surface of the roadway. The location of the driver's eye (d1) is dependent on the classification of the intersecting streets. For all intersections where the through street is a thoroughfare, the driver's eye location shall be 18 feet back from the face of curb extended through the intersection or the edge of pavement if there is no curb. At all intersections where the through street is a local or collector street, and for ramp type driveways, the driver's eye shall be located 15 feet behind the face of curb extended, or the edge of pavement if there is no curb. The sight distance for left or right turns onto the through street are dependent on the design speed of the roadway and are presented in Table 3.1 or the most current version of AASHTO guidelines.

3. Traffic Signal Control

At intersections controlled by traffic signals, the minimum sight distance will be stopping sight distance (Tables 3.1) for all side street movements except for the right turn movement. The right turn movement shall have intersection sight distance to allow right turn on red, except where it is economically impractical due to existing major features such as permanent buildings and existing, large, mature trees. The minimum sight distance for the right turn movement limited by existing major features shall be stopping sight distance. Where intersection sight distance cannot be achieved, right turn on red will be restricted.

TABLE 3.1

Vehicle Crossing the Roadway	Sight Distance (ft) per 10 mph of Design Speed for Appropriate Width of Crossing			
	2-Lanes	4-Lanes	6-Lanes	8-Lanes
Passenger	100	120	130	140
Single Unit Truck	130	150	170	190
Large TTST	170	200	210	220

A. Stopping Sight Distance

At minimum, stopping sight distance must be available to the driver at all locations along roadways. Stopping sight distance applies to horizontal as well as vertical alignments. Stopping sight distance on horizontal curves is measured along the centerline of the inside lane around the curve and the line of sight is a straight line between two points on the centerline of the lane. On vertical curves, stopping sight distance is measured on a straight line between the driver's eye and an object on the roadway surface. The height of the driver's eye shall be measured at 3.5 feet above the roadway surface and the object shall be 2.0 feet above the roadway surface. A more detailed explanation of the measurement of stopping sight distance is included in *A Policy on Geometric Design of Highways and Streets*, 2001, by AASHTO (AASHTO Green Book). The minimum stopping sight distance required is based on wet pavements and depends on the design speed and the grade of the roadway. Table 3.2 presents the minimum stopping sight distances for various design speeds on level terrain. Table 3.3 presents adjustment factors for stopping sight distance on grades. Variable situations may require a greater length of stopping sight distance. Lengths in Table 3.2 and 3.3 are a guide and the registered engineer shall ultimately be responsible for the design criteria.

TABLE 3.2

**MINIMUM STOPPING SIGHT DISTANCE
FOR LEVEL AND WET CONDITIONS**

Design speed (MPH)	Stopping sight distance (feet)
10	45
15	80
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570

Source: AASHTO Green Book, 2001.

TABLE 3.3

**ADJUSTMENT FACTORS FOR
STOPPING SIGHT DISTANCE ON GRADES**

Design speed (MPH)	Increase for downgrades correction in stopping sight distance (feet)			Decrease for upgrades* correction in stopping sight distance (feet)		
	3%	6%	9%	3%	6%	9%
20	1	5	11	-6	-8	-11
25	3	10	18	-8	-12	-15
30	5	15	27	0	-16	-21
35	7	21	37	-13	-21	-28
40	10	28	49	-16	-27	-36
45	18	40	67	-16	-29	-40
50	21	49	82	-20	-37	-50
55	25	58	98	-26	-45	-62
60	28	68	116	-32	-55	-75

*Assumed speed is lower than the design speed since vehicles normally travel at a slower speed on an upgrade.

Source: AASHTO Green Book, 2001.

3.04 MATERIALS

1. **Portland Cement Concrete** for curb and gutter, driveways, and sidewalks shall have a minimum 28-day compressive strength of 3000 psi, a non-vibrated slump between 2.5 and 4 inches, a minimum cement content of 564 pounds per cubic yard, an air entrainment of 5 to 7%, and a maximum water-cement ratio of 0.532.
2. **Joint Filler** shall be a non-extruding joint material conforming to ASTM C1751.
3. **Concrete Curing Agents** shall be free from any impurities which may be detrimental to the concrete and shall meet Section 926 of NCDOT Standard Specifications for Roads and Structures.
4. **Aggregate** for portland cement concrete shall meet the requirements for fine and course aggregate of Section 1014 of the NCDOT Standard Specifications for Roads and Structures.
5. **Portland Cement and Admixtures** shall meet the requirements of Section 1000 of the NCDOT Standard Specifications for Roads and Structures.
6. **Water** for mixing or curing the concrete shall be free from injurious amounts of oil, salt acid, or other products injurious to the finished product.
7. **Aggregate Base Course** shall consist of an approved coarse aggregate produced in accordance with the requirements indicated for either Type A, B, or C aggregate as described in Section 910 of the NCDOT Standard Specifications for Roads and Structures.
8. **Bituminous Surface Course**, Type SF9.5 (A,B,C) and I19.0 (B, C) shall consist of a mixture of coarse and fine aggregates, and asphalt cement, and shall meet the requirements of Section 645 of the NCDOT Standard Specifications for Roads and Structures. For NCDOT project the requirements of NCDOT for other types of asphalt (Superpave) shall apply
9. **Bituminous Concrete Base Course**, Type B25.0B, shall conform to the general, material, and construction specifications as specified in Section 610 and Section 640 of the NCDOT Standard Specifications for Roads and Structures. For NCDOT project the requirements of NCDOT for other types of asphalt (Superpave) shall apply.
10. **Tack Coat** shall be asphalt or asphalt cement and shall meet the general, material, and construction specifications as specified in Section 605 of the NCDOT Standard Specifications for Roads and Structures.
11. **Concrete Pavement** shall meet Section 700 of the NCDOT Standard Specifications for Roads and Structures.

12. **Concrete Pavers** may be used on privately maintained streets or as approved by the Director of Public Utilities for pedestrian crossings in urban areas, in accordance with the applicable Standard Detail. The City of Dunn will not maintain decorative type paved street surfaces such as pavers or imprinted designs within public right of way, unless approved by the Director of Public Utilities.
13. **Geotextile Fabric** may be used to stabilize a roadway, subgrades, slopes, and for other uses as necessary. At least one week prior to using this fabric, a sample and its associated engineering data shall be submitted to the Director of Public Utilities for approval. Areas stabilized with fabric shall be indicated on “as-built” drawings with the manufacturer name and type fabric specified.

3.05 CONSTRUCTION AND INSPECTION

No construction shall commence until the following applicable items have been obtained:

- All required permits and approvals
- City of Dunn development plan approval
- City of Dunn Construction Drawing approval
- Land Disturbance Permit

A. Streets

No base material shall be placed on a roadway until the storm sewer, subgrade, utilities, and all appurtenances have been inspected and meet City of Dunn Engineering Design and Construction Standards.

The Construction Inspector may require field density testing of subgrade soils from a certified soils laboratory. The soils laboratory shall perform sufficient Proctors to evaluate the compaction characteristics of various soils used in the roadbed. The Construction Inspector may also require field density testing of the ABC used and an asphalt mix formula before either is inspected or approved. The final course of surface asphalt shall not be placed until the end of the warranty period.

The subgrade shall be compacted as described in Section 2.05 Earthwork. Inspection of the subgrade prior to the placement of base course, and inspection of the base course prior to placement of asphalt, shall be performed by proofrolling and/or field density testing at the direction of the Construction Inspector.

When thoroughfare widening takes place, the existing edge line of the travel lane shall be sawcut. Achieve an overlap of the final inch of new asphalt by at least 6" onto the existing roadway cross-section. The objective is to have the joint between new and old asphalt to be offset from the joint between subgrades (this overlap shall exclude the overlay). In addition, whenever an overlay is required, milling of 1 ½ inch shall occur at both tie-in stations to insure a smooth connection.

B. Curb and Gutter, Driveways, and Sidewalks

No concrete shall be placed until all forms and subgrades have been approved by the Construction Inspector. The surface of sidewalks shall be finished to grade and cross section with a float, troweled smooth, and finished with a broom.

Subgrade shall be excavated to the required depth, and shaped to the proper cross-section. Where tree roots are encountered, they shall be removed to a depth of 1 foot for the full width of the excavation. The subgrade shall be stable and thoroughly compacted.

Forms shall be set and maintained true to the required lines, grades, and dimensions. Forms shall be constructed with material of such strength and rigidity to prevent any appreciable deflection between supports. Straight forms shall be within a tolerance of ½ inch in 10 feet from a true line horizontally or vertically. Forms shall be thoroughly cleaned of all dirt, mortar and foreign material before being used. All inside form surfaces shall be thoroughly coated with commercial quality form oil.

Grooved construction joints shall be cut to a depth equal to at least 1/3 of the total slab thickness. The joint shall be no less than 1/8 inch in width and cut at intervals equal to the width of the sidewalk. A 1/2-inch expansion joint filled with joint filler shall be placed between all rigid objects and placed no farther than 50 feet apart for sidewalks and curb and gutter, extending the full depth of the concrete with top of the filler 1/2 inch below the finished surface.

3.06 FIRE LANES

Fire lanes shall be installed in accordance with Dunn Emergency Services and inspected in accordance with the public street requirements of Section 3.05 A and 3.05 B of these standards. The general requirement designates that any building located more than 150 feet from a public road, or which exceeds 30 feet in height and is set back more than 50 feet from a public road, shall have a fire lane.

Fire lanes shall be a minimum width of 20 feet and shall be properly marked and signed to designate the access as a "fire lane" as specified by the Fire Marshal. The surface of the fire lane shall be paved with a minimum of 8 inches of ABC stone and 2 inches of S9.5B asphalt.

All fire lanes shall be marked in accordance with one of the following requirements:

1. Continuously painted yellow striping along the fire lane with “No Parking - Fire Lane” printed with minimum 8-inch high letters at 40-foot intervals or as directed by the Fire Marshal;
2. Continuously painted yellow curb with “No Parking - Fire Lane” along the fire lane, and with “No Parking - Fire Lane” printed with minimum 8-inch high letters at 40-foot intervals or as directed by the Fire Marshal;
3. The installation of the MUTCD standard sign showing “No Parking - Fire Lane” placed at each end of the fire lane and at 50-foot intervals with arrows on the signs or a continuously painted yellow strip along the designated fire lane.

3.07 TRAFFIC CONTROL AND STREET NAME SIGNS

Traffic control and street name signs within subdivisions which will be maintained by the City of Dunn shall be consistent with the MUTCD. All specialty traffic control and street name signs and posts must be in compliance and approved by the City of Dunn.

3.08 TRAFFIC CALMING DEVICES

The City shall not allow the obstruction of any public street, private street or fire lane unless otherwise stipulated by the City Council. This requirement is in accordance with the current edition of the North Carolina State Fire Prevention Code. The reference to an “obstruction” shall include parking, speed bumps or any other device which may obstruct the free passage of emergency vehicles.

All traffic control devices must be shown and approved as a part of a site plan prior to installation and must be in conformance with the City Standard Specifications. The traffic control devices and all related signs and pavement markings shall be maintained by the Owner as a part of the approval of the plan. Traffic control devices shall include rumble strips, raised pavement markers, pavement undulations (speed humps) or speed bumps.

The following traffic calming devices shall not be installed on public streets except with the approval of the City Council.

1. Rumble Strip

An irregular surface established to draw the attention of motorists and alert them of potential hazards or conflicts. The material used as a part of a rumble strip may be cobblestone, stamped concrete, brick or rough surface asphalt.

A rumble strip may not vary more than 1 inch in height from the pavement elevation of the adjacent travelway. All rumble strips must be located outside any public right of way, unless otherwise approved by the Director of Public Utilities and the Public Safety Director.

2. Raised Pavement Markers

Raised pavement markers may be used to create an irregular surface to draw the attention of motorists and to alert them of potential hazards or conflicts. The markers must be made of a flexible and durable solid material designed to support vehicular traffic. The placement of markers may be staggered in a manner as approved by the Public Utilities and Works Departments.

All raised pavement markers shall have a maximum height of 1 inch above the pavement surface. The minimum size of the marker shall be 4" x 4". The markers must be located outside any public right of way. All raised pavement markers shall have cube-corner microprism reflectors visible from either direction of travel.

3. Pavement Undulation (Speed Hump)

A pavement undulation is a gradual raised pavement surface which extends transversely across the travelway. The surface material for a pavement undulation shall be the same as the adjacent travelway, typically asphalt.

A pavement undulation shall be parabolic with a maximum height of 3 inches. The pavement shall be tapered to the edge of the pavement or gutter line for the last 12 inches along each side. The minimum length of the pavement undulation shall be 12 feet.

All pavement undulations shall be clearly marked with pavement markings or warning signs for each direction of travel. Markings and signage shall be consistent with the MUTCD.

All pavement undulations must be located outside any public right of way and may not be used on any public or private street, access, travelway, etc., designated as a fire lane except as permitted by City Policy. Pavement undulations must be located a minimum distance of 500 feet from a signalized intersection. The City of Dunn and/or the N.C. Department of Transportation may require the removal of any speed undulation which causes traffic to back up onto a public street.

3.09 PEDESTRIAN CROSSINGS

All locations which are designated for pedestrian traffic crossings shall be designated as a crosswalk with pavement marking and signage in accordance with MUTCD.

3.10 STREET TREES

Street trees, landscape, and landscape medians on streets within residential and non-residential developments and other areas shall be maintained by the Homeowners Association or by individual property owners fronting on the street. This shall include but is not limited to maintenance of the trees, landscape, ground cover and removal and replacement of plant materials. The City of Dunn accepts no responsibility for maintenance or replacement of street trees, landscape areas, or landscape medians.

Street tree shields shall be installed wherever street trees are required. A one-year warranty period following installation shall be provided on all street trees. After the one year warranty period, the Homeowner's Association and/or the property owner shall be responsible for the care, removal, replacement and maintenance of street trees.

3.11 THOROUGHFARE/MEDIAN PLANTINGS

With the construction of streets in the Thoroughfare/Boulevard/Parking classification and above, landscaping of medians and shoulders shall be per the City of Dunn Thoroughfare Planting Guidelines. Thoroughfare median plantings shall be maintained by the City of Dunn, unless otherwise specified.

3.12 GREENWAY SPECIFICATIONS

Greenway locations and alignments shall be as directed and approved by the Director of Parks and Recreation and shall be in accordance with the City of Dunn Pedestrian Plan. Greenways alignment shall be finalized with the Director of Parks and Recreation prior to preliminary plan approval, with full construction plans and all permits provided prior to construction drawings approval for any project on which greenways are required.

Where greenway trails are required, the following guidelines shall be followed.

- Maximum cross slope grade shall be 2 %.
- Maximum grade shall be 8%, unless approved by the Director of Parks and Recreation.
- Positive drainage shall be established.
- At all drainage crossings a Professional Engineer shall provide properly sized drainage pipe with supporting calculations.

- Bridge crossings may be required in some locations. If a bridge is required, it must carry a 10,000 lb load and shall be designed by a registered engineer and approved by the City of Dunn and appropriate agencies.
- Greenways shall be 8 feet wide. However, in the following cases, greenways shall be 10 feet in width when located on a sewer easement, when approaching an underpass, and at other times if determined necessary by Director Parks and Recreation.
- When the greenway intersects with a roadway, a 10' wide, 6" thick concrete pad will be required extending from the back of curb to the right of way line, or 18', whichever is less. There shall be a handicap curb cut as shown in City of Dunn details. At the end of the pad, removable steel bollards will be required per City of Dunn detail.
- Where the greenway trail intersects roadway in which sidewalk is on opposite side of road a handicap ramp will be required on sidewalk side of street to allow travel onto sidewalk from greenway.
- Greenways shall be located and constructed so as to minimize damage from floodwaters.
- The minimum material must be 3" of approved asphalt base material and 2" SF9.5B.
- Documentation of required permits, approvals, etc. shall be provided for greenways prior to construction drawing approval of the project on which the greenway is required.
- Greenways shall be subject to the same construction inspections, performance, and warranty requirements as roadway infrastructures.

**Figure 1
CURVE CONTROLS**

	Horizontal Curve Controls			Vertical Curve Controls			
	Minimum Design speed (mph) ¹	Maximum Super-elevation (ft./ft.) ²	Minimum Radii (ft.)	Maximum Grade ³ (percent)	Length Crest	Length Sag	Minimum Length (ft.)
Limited Access Thoroughfare	Design standards to be determined for each case individually by the Director of Public Utilities						
Thoroughfare, Boulevard, Parkway	Design standards to be determined for each case individually by the Director of Public Utilities						
Non-Residential Collector	40	0.04	565	9%	44A	64A	120
Residential Collector Streets & No Load Residential Collector	25	0.04	345 (300)	9%	29A	49A	120
Residential streets	30	Normal crown	205 230	10%	12A	26A	75
Cul-de-sacs 1000' or less	30	Normal crown	150	10%	12A	26A	75
Loop road 1500' or less	30	Normal crown	150	10%	12A	26A	75

¹ Design speed shall be at least 5 mph greater than posted speed.

² The superelevation tables found in *A Policy on Design of Urban Highways and Arterial Streets - 2001* published by the American Association of State Highway Officials will be used for determining the actual "e" for various radii.

³ Design criteria can vary on a case-by-case basis if approved by the Director of Public Utilities or Public Works.

⁴ Note: At the discretion of the Departments of Public Utilities or Public Works, the values in sags may be adjusted with additional street lighting

A - Algebraic difference in grades.

END OF SECTION 3.00

**SECTION 4.00
SOIL EROSION AND SEDIMENTATION CONTROL**

SUB-INDEX

4.01 GENERAL

4.02 APPLICABILITY

4.03 TEMPORARY MEASURES

- A. Standard Temporary Silt Fence**
- B. Silt Fence Outlet**
- C. Gravel & Rip Rap Filter Basin (Sediment Trap)**
- D. Skimmer Sediment Basin**
- E. Gravel & Rip Rap Horseshoe Inlet Basin**
- F. Standard Riser-Barrel Sediment Basin (Sediment Pond)**
- G. Catch Basin Riser/Filter**
- H. Check Dam**
- I. Construction Entrance**
- J. Diversion Ditch**
- K. Temporary Stream Crossing**
- L. Storm Drain Inlet Protection**
- M. Temporary Silt Ditch**
- N. Slope Drains**

4.04 PERMANENT MEASURES

- A. Lined Stormwater Channels**
- B. Storm Drain Outlet Protection**

4.05 STABILIZATION MEASURES

- A. Temporary Stabilization**
- B. Permanent Stabilization**
- C. Use of Drought Tolerant Plants**

4.06 SLOPES

4.07 CALCULATIONS

4.08 CONSTRUCTION SEQUENCE

4.09 MINIMUM STANDARDS FOR RESIDENTIAL LOTS

4.01 GENERAL

This chapter contains standards and specifications for various techniques and devices used in temporary and permanent erosion control, for the purpose of insuring compliance with the City's Sedimentation & Erosion Control Ordinance (i.e. to prevent soil erosion and sedimentation to offsite property or protected areas). These techniques and devices are the minimal acceptable for use in the City of Dunn. The use of other techniques and devices is acceptable if adequate control is provided by the alternative and prior approval is given based on a review of specifications for the measure.

The techniques and devices in this chapter should generally be used in the locations and under the conditions specified in the standards for the particular measure. No temporary or permanent erosion control devices are allowed to be placed in riparian buffers, unless approved by the Director of Public Utilities (or designee).

4.02 APPLICABILITY

Temporary and permanent erosion control measures shall be provided for all land disturbing work in accordance with the City's Sedimentation and Erosion Control Ordinance. While all land disturbing work, regardless of the amount of disturbed area, shall require the installation of temporary and permanent measures to prevent erosion and sedimentation to offsite properties or protected areas, certain categories of land-disturbing work shall be required by the City to meet additional requirements:

1. Land disturbance exceeding 20,000 sq. ft. - requires erosion control plan approval, a Land Disturbance Permit, payment of related fees, and a preconstruction meeting before clearing & grubbing and construction may begin.
2. Land disturbance exceeding one acre for a publicly funded project (i.e. a public agency as financially responsible party) – requires plan approval by the North Carolina Department of Environment and Natural Resources, Division of Land Resources, Land Quality Section, Fayetteville Regional Office. Office copies of approved plans & permits should also be submitted to the City for record.
3. Land disturbance for the construction of individual residential buildings – requires installation of certain site-specific erosion control measures prior to specific building inspections.

For most development-related land disturbance activities, the following shall apply. An erosion control plan must be submitted to and approved by the City or NCDENR Land Quality Section. A land disturbance (grading) permit shall be obtained from the City with erosion control plan approval, a preconstruction meeting, and all applicable fees paid prior to issuance of a Land Disturbance permit. Temporary measures shall be installed and inspected by the NCDENR Land Quality Section or the City for compliance and issuance of a Certificate of Compliance prior to initiation of any land disturbing activity (Certificate of Compliance). All permanent erosion control measures shall be incorporated into the work at the earliest practical time. All temporary measures shall be maintained until the permanent measures have taken effect or approval to remove such measures has been granted by the Director of Public Utilities or NCDEQ. Temporary and permanent measures shall be coordinated to provide effective and continuous erosion control throughout the construction and post-construction period to minimize siltation of streams, lakes, reservoirs, and other impoundments, ground surfaces and other property. These measures shall remain in effect until the City gives final approval in the form of a Certificate of Completion.

4.03 TEMPORARY MEASURES

A. Standard Temporary Silt Fence

Silt fence is a temporary sediment filter of geotextile fabric stretched between and attached to supporting posts (at maximum 8 feet spacing) and a wire fence, with the bottom of the fabric and wire buried in the ground. Silt fence shall be used below small disturbed areas less than ¼ acre per 100 feet of fence, where runoff can be stored behind the silt fence without damaging the fence or submerged area behind the fence. Silt fence is not intended for installation across areas of concentrated flow (i.e. streams, ditches, or waterways).

Silt fence shall consist of metal fence posts, wire fence, filter fabric, staples and wire. The wire fence shall be “hog wire”, minimum 14 gauge, with maximum mesh of 6 inches. The wire is used to attach the wire fence to the posts. The filter fabric shall be a synthetic geotextile stapled to the top of the wire fence.

Use/Design: Silt fence must be stable for the 10-year peak storm runoff. Silt fence shall be used where the drainage area is no greater than ¼ acre per 100 ft of fence. The depth of impounded water adjacent to silt fence in the design storm shall not exceed 1.5 ft at any point along the fence. The design life of a synthetic silt fence should be 6 months.

Installation: Refer to the approved erosion control plan for location, extent, and specifications. If silt fence is not installed correctly the first time, it will have to be re-installed.

1. Determine the location on the ground taking into consideration:
 - a) Sufficient spacing between the silt fence and the construction site for maintenance, grading, filling, and other construction activity.
 - b) Installation of the silt fence on the contour so that runoff goes through the silt fence and does not flow along the silt fence to pond at the lowest point. Where ponding does occur, silt fence outlets may be necessary so that the fence does not collapse.
2. Clear the location of the silt fence, clearing only what is needed to provide access by personnel and equipment for installation.
3. Excavate an 8-inch down and 4-inch forward along the location of the fence. Using a “ditch witch” is helpful.
4. Along the lower side of the trench, place steel fence posts no more than 8 feet apart and drive them 24 inches into the ground.
5. Attach wire fence (“hog wire” or min. 14 gauge with max. mesh of 6 inches) to the uphill side of the posts, placing 12 inches of the bottom of the fence into the trench. Use wire to fasten fence to the posts. Completed fence must be at least 1.5 feet high and not more than 2 feet high.
6. Attach synthetic filter fabric to the uphill side of the wire fence with staples a maximum of 12 inches apart, placing 12 inches of the fabric into the trench with the wire fence. Use rolls of fabric and cut to necessary length in order to minimize the number of joints.
7. Backfill the trench and tamp the fill to firmly anchor the bottom of the filter fabric and wire fence.
8. Where it is impossible to install the silt fence on the contour, runoff will flow along the fence and pond at the lowest point. Where the total drainage area to the point is greater than 5,000 ft² a silt fence outlet is required. Where the drainage area is greater than 10,000 ft², a sediment trap shall be used in lieu of a silt fence outlet. The location of silt fence outlets should be shown on the

plan, with installation checked in the field to determine if additional outlets are needed.

9. Silt fence shall be installed in accordance with the standard detail, this specification, and the approved erosion control plan.
10. Access to silt fence must be provided in all phases of construction for maintenance and removal purposes. Following are some guidelines for minimum clearance required for silt fence:
 - a. Allow 15 to 25 feet of space between the fence and any structure for equipment to maneuver for site construction and silt fence maintenance.
 - b. Allow 15 feet at the bottom of fill slopes over 5 feet high for sediment storage and silt fence maintenance.

B. Silt Fence Outlet

A silt fence outlet is a low point placed (where necessary) along the length of a silt fence to allow water trapped behind the silt fence to drain out, thus minimizing failure of the silt fence. A silt fence outlet consists of a segment of hardware cloth and washed stone placed in the low point of a length of silt fence. The outlet may not be used in place of a sediment trap or basin. Provisions shall be made to provide such outlets where necessary to prevent damage and to ensure the maximum filtering efficiency of silt fence.

Use/Design: Obvious points of ponding shall be identified on the erosion control plan and silt fence outlets designated where the drainage area to the point of ponding exceeds 5,000 ft². Because it is difficult to predict these locations using a topographic map, contractor shall adjust outlet locations as necessary to the ponding location during silt fence installation. Silt fence outlets should NOT be located where the outflow will erode the soil below. A location should be selected that is protected with adequate vegetation, or protection should be provided via stone or layers of filter fabric. Silt fence outlets have the same requirements for access as silt fence, outlined above.

Installation: Refer to the approved erosion control plan for location, extent, and specifications. If silt fence is not installed correctly the first time, it will have to be reconstructed. Determine the exact location of the outlet before completing installation of the silt fence, taking into consideration:

1. Installation at the lowest point(s) in the fence where water will pond.
2. Maximum allowable drainage area restriction for silt fence.
3. Installation where the outlet is accessible for installation, maintenance and removal.
4. Placement of the outlet so that water flowing through it will not create an erosion hazard below – avoid steep slopes below the outlet and areas without protective vegetation. Use slope drains if necessary.

The silt fence outlet shall be installed in accordance with the standard detail, and the approved erosion control plan.

C. Gravel & Rip Rap Filter Basin (Sediment Trap)

A sediment trap is a small, temporary ponding area formed by an embankment or excavation to detain sediment-laden runoff and trap the sediment. The erosion control plan should show the sediment trap drawn to scale with adequate room around it for machinery to construct and maintain it during all phases of construction.

Use/Design: Use the following criteria to evaluate the location and to design all types of sediment traps. Sediment traps may be used for *maximum drainage areas that are 5 acres or less* and where access can be maintained for sediment removal and proper disposal. Investigate and evaluate the specific conditions on the site, determine if the location is suitable, and design the trap to fit the conditions.

1. **Storage Capacity** – The minimum volume of the sediment trap shall be 3600 ft³/acre based on area draining into the basin. Measure volume below the crest elevation of the outlet.
2. **Surface Area** – To solve for the surface area use 435 sf/cfs of Q10. Then, convert the answer into a minimum 2:1 ratio.
3. **Weir Length and Depth** – The spillway weir must be designed at least 10 feet long and sized to pass the peak discharge of the 10-yr storm or may be selected from Table 4.1. A maximum flow depth of 1 foot, a minimum freeboard of 1.0 feet, and maximum side slopes of 2:1 are recommended. Weir length is to be designed based on the following criteria by using the weir equation $Q=CLH^{3/2}$; H, not to exceed .5' and C=3

4. **Total Depth** – The minimum depth below the crest of the outlet is 3.5 feet. The maximum depth is 6 feet. Depth may vary in different parts of a trap due to topography.

Installation:

1. **Embankment** – Ensure that embankments for temporary sediment traps do not exceed 5 feet in height measured at the center line from the original ground surface to the top of the embankment. Additional freeboard may be added to the embankment height to allow flow through a designated bypass location. Construct embankments with a minimum top width of 5 feet and side slopes of 2:1 or flatter. Machine compact embankments.
2. **Outlet** – The outlet area of a sediment trap consists of an earthen embankment with filter fabric separating the rip rap and wash stone weir. Baffles to lengthen the distance water travels through the sediment trap should be incorporated in the sediment basin. Installation of baffles shall be as described in the silt fence specifications outlined in Section 4.03C.9. Construct the sediment trap outlet with a minimum of 10 feet in length of the embankment made of stone (located at the low point). The stone section serves two purposes: 1) the top section serves as a non-erosive spillway outlet for flood flows, and 2) the bottom section provides a means of dewatering the basin between runoff events.
3. **Stone Size** – Construct the outlet using well-graded stones with a d50 size of 9 inches (class B erosion control stone is recommended) and a maximum stone size of 14 inches. A 1-ft thick layer of ½ - ¾ inch aggregate (NCDOT #57 washed stone is recommended) should be placed on the inside face to reduce drainage flow rate.
4. **Side Slopes** – Keep the side slopes of the spillway section at 2:1 or flatter. To protect the embankment, keep the sides of the spillway at least 21 inches thick.
5. **Depth of Spillway** – Keep the crest of the spillway outlet a minimum of 1.5 feet below the settled top of the embankment.
6. **Protection from Piping** – Place filter cloth on the foundation below the riprap to prevent piping. An alternative would be to excavate a keyway trench across the riprap foundation and up the sides to the height of the dam.

7. **Weir Length and Depth** – Keep the spillway weir at least 10 feet long and sized to pass the peak discharge of the 10-yr storm. A maximum flow depth of 6 inches, a minimum freeboard of 1 foot, and maximum side slopes of 2:1 are recommended. Weir length may be selected from Table 4.1 for most site locations in North Carolina.
8. **Stabilization** – Within 10 working days after completion, all areas disturbed for the trap construction must be provided with ground cover sufficient to restrain erosion. Vegetation (either temporary or permanent) should be used on the top, slopes, and perimeter when the season allows it. When the season is not suitable for establishing vegetation, use a heavy layer of mulch.
9. **Baffles** - Shall be required in all sediment traps. Baffles normally split the sediment traps into four cells (please refer to the approved plan for the amount and spacing of the baffles). Normally you will need to install three rows of silt fence with hog wire as per Section 4.03A and make sure that the end of each section is keyed into the side wall of the trap to prevent water from washing out the silt fence. The silt fence should be installed where the inlet cone (area furthest from weir) is approximately 35% of the basin area. The first and second cell is approximately 25% of the basin area with the outlet zone consisting of the remaining 15%. The spacing between the metal posts shall be a maximum of 4' apart. Slits are to be provided in the silt fence fabric in alternating spaces.
10. **Trap Cleanout** – Remove sediment from the trap and restore the capacity to original trap dimensions when sediment has accumulated to one-half the design depth.

Sediment traps shall be installed according to the preceding criteria, the standard details and the approved erosion control plan.

D. Skimmer Sediment Basin

A Skimmer Sediment Basin is a small sediment basin that can be used in place of sediment traps. The erosion control plan must show the skimmer sediment basin drawn to scale with adequate room around it for machinery to construct and maintain it during all phases of construction. The Skimmer Sediment Basin outlet consists of an earthen embankment and stone weir spillway. The principal dewatering of the skimmer sediment basin comes through a skimmer adequately sized for the drainage area. The skimmer shall be attached to a minimum 8" Sch 40 PVC pipe on a smooth firm foundation of impervious soil. Do not use material such as sand, gravel or any other pervious material as backfill over the pipe.

Baffles should be included in the basin to lengthen the traveling distance of the water through the Basin. Baffles shall be used in all sediment traps and be designed in accordance with the Baffle specifications outlined in Section 4.03C.9.

Use/Design: Use the following criteria to evaluate the location and to design all types of Skimmer Basins. Skimmer Basins shall be used in areas with a *maximum drainage area of 10 acres*, and located where access can be maintained for sediment removal and proper disposal. Skimmer Sediment Basins shall be placed in a suitable location which is the result of investigating and evaluating the specific conditions on the site and designing the basin to fit the conditions.

1. **Storage Capacity** – The minimum volume of the sediment trap shall be 1800 ft³/acre based on the area draining into the basin. The volume shall be measured below the crest elevation of the outlet. The City of Dunn has a *minimum* depth of 2.5 feet.
2. **Surface Area** – To solve for the surface area use 325 SF/Cts. Then, convert the answer into a minimum 2:1 ratio.
3. **Weir Length and Depth** – The spillway weir must be designed at least 10 feet long and sized to pass the peak discharge of the 10-yr storm or may be selected from Table 4.1. A maximum flow depth of 6 inches, a minimum freeboard of 1 foot, and maximum side slopes of 2:1 are recommended. Weir length is to be designed based on the following criteria by using the weir equation $Q=CLH^{3/2}$; H, not to exceed .5' and C=3

Table 4.1 Minimum Weir Length for Skimmer Sediment Basins

Drainage (Acres)	Minimum Length of Weir (Feet)
1-4	10
5	12
6	14
7	16
8	18
9	20
10	22

4. **Total Depth** – The minimum depth below the crest of the outlet is 2 feet. The maximum depth is 6 feet. Depth may vary in different parts of a trap due to topography.

Installation:

1. **Embankment** – Ensure that embankments for temporary Skimmer Sediment Basins do not exceed 5 feet in height measured at the center line from the original ground surface to the top of the embankment. Additional freeboard may be added to the embankment height to allow flow through a designated bypass location. Construct embankments with a minimum top width of 5 feet and side slopes of 2:1 or flatter. Machine compact embankments.
2. **Outlet Section** – The primary outlet shall consist of a skimmer with a minimum 8” Sch 40 PVC through the embankment on a smooth firm foundation of impervious soil. Do not use material such as sand, gravel or any other pervious material as backfill over the pipe. The emergency overflow shall consist of an earthen embankment with filter fabric separating the rip rap and wash stone weir. Baffles to lengthen the distance water travels through the sediment trap should be incorporated in the sediment basin. Installation of baffles shall be as described in the silt fence specifications outlined in Section 4.03C.9. Construct the sediment trap outlet with a minimum of 10 feet in length of the embankment made of stone (located at the low point).
3. **Protection From Piping** – The embankment around the skimmer drain pipe shall not be constructed with material such as gravel, sand or any other pervious backfill
4. **Side Slopes** – Keep the side slopes of the spillway section at 2:1 or flatter. To protect the embankment, keep top of the spill way at least 5 feet thick.
5. **Depth of Spillway** – Keep the crest of the spillway outlet a minimum of 1’ 6” below the settled top of the embankment.
6. **Stabilization** – Within 10 working days after completion, all areas disturbed for the skimmer sediment basin construction must be provided with ground cover sufficient to restrain erosion. Vegetation (either temporary or permanent) should be used on the top, slopes, and perimeter when the season allows it. When the season is not suitable for establishing vegetation, use a heavy layer of mulch.
7. **Baffles** – Baffles shall be used in all sediment basins and be designed in accordance with the baffle specifications outlined in Section 4.03C.9.

8. **Trap Cleanout** – Remove sediment from the trap and restore the capacity to original trap dimensions when sediment has accumulated to one-half the design depth.

Skimmer Sediment Basins shall be installed according to the preceding criteria, the standard details and the approved erosion control plan.

E. Gravel and Rip Rap Horseshoe Inlet Basin

A Gravel and Rip Rap Horseshoe Inlet Protection Basin is one variation of a sediment trap. It is a “horse-shoe shaped” temporary impoundment used on an existing pipe invert. It may be used for drainage areas that are 5 acres or less. Design criteria shall be consistent with the sediment trap design specified in section 4.03 C of this design manual. These devices shall be installed according to standard detail and the approved erosion control plan.

F. Standard Riser-Barrel Sediment Basin (Sediment Pond)

A sediment basin is a temporary impoundment for use below larger areas of land disturbance with a stormwater release structure, formed by constructing an earthen embankment to create a natural or excavated basin across a drainage way.

Materials: Sediment ponds shall be used for *drainage areas less than or equal to 100 acres*. In addition, the basin life should be limited to 3 years unless it is designed as a permanent structure.

Use/Design:

Special limitation – This specification applies only to the design and installation of sediment basins where failure of the structure would not result in loss of life, damage to homes or buildings, or interruption of use of public roads or utilities. Regardless of classification, structures 11 -15 feet or higher, and having a maximum storage capacity of 10 acre-ft or more are subject to the NC Dam Safety Act.

Planning Considerations – Basin sites should be selected to capture sediment from all areas that are not treated adequately by other sediment traps, considering access for cleanout and disposal of trapped sediment. Locations where a pond can be formed by constructing a low dam across a natural swale are generally preferred to sites that require excavation (unless the structure will be permanent). If practical, divert sediment-free runoff away from the basin.

Design Criteria – The design and construction of a sediment pond involves much more thought and planning than most other sediment-trapping devices. A more precise design is required because of the volume of the sediment to be trapped, the large flow of runoff through the pond, and the hazard created. Adequate precautions should be taken to design the sediment basin properly and to prevent its failure.

1. **Drainage Area** – Limit drainage areas to 100 acres.
2. **Design Basin Life** – Ensure a design basin life of 3 years or less.
3. **Dam Height** – Limit dam height to 15 feet (see Special Limitation statement above). Height of a dam is measured from the top of the dam to the lowest point at the downstream toe.
4. **Storage Capacity** – Ensure that the sediment storage volume of the basin, as measured to the elevation of the crest of the principal spillway, is at least 1800 ft³/acre volume for the disturbed area draining into the basin (1800 ft³/acre volume is equivalent to ½ inch of sediment per acre of basin drainage area). Where possible, the entire drainage area is used for this computation, rather than the disturbed area alone, to help ensure adequate trapping efficiency. For purposes of measuring volume to determine whether or not the special limitation statement above applies, measure volume to the top of the dam.
5. **Minimum Surface Area** – 435 S.F. per CFS of Q10 peak inflow.
6. **Design Runoff Rate** – When calculating the runoff rate to determine the minimum surface area of the trap, do not use the peak rate of runoff used to size the outlets; doing so will result in an oversized basin. Use an average runoff rate (which is not related to time of concentration) that anticipates the most common storms that will occur. Determine the average runoff rate using the Rational formula ($Q = CIA$): use a value of “C” for the most severe runoff conditions expected during development of the site; use 0.65 inches/hour as the value of intensity, “I” (0.65 in/hr is the intensity for a 10-year, 6-hour storm in Raleigh-Durham); and for “A” use the drainage area of the total watershed to the sediment trap.
7. **Basin Shape** – Ensure that the flow length to basin width ratio is greater than 2:1 to improve trapping efficiency – attempt to maximize the length-to-width ratio of the basin as much as possible. This basin shape may be attained by site selection,

excavation, or installing baffles. Length is measured at the elevation of the principal spillway.

8. **Spillway Capacity** – The spillway system must carry the peak runoff from the 10-yr storm with a minimum of 1 foot freeboard in the emergency spillway. Runoff computations should be based on the disturbed soil cover conditions expected during the effective life of the structure.
9. **Principal Spillway** – Construct the principal spillway with a vertical riser connected to a horizontal barrel that extends through the embankment and outlets beyond the downstream toe of the dam, or an equivalent design.
 - *Capacity* – Ensure a minimum capacity of 0.2 cfs/acre of drainage area, with the water surface at the emergency spillway crest elevation.
 - *Sediment cleanout elevation* – Show the distance from the top of the riser to the pool level when the basin is 50% full. This elevation should also be marked in the field with a permanent stake set at this ground elevation or some other acceptable means of marking.
 - *Crest elevation* – Keep the crest elevation of the riser a minimum of 1 foot below the crest elevation of the emergency spillway.
 - *Riser and barrel* – Keep the minimum barrel size at 15 inches for corrugated metal pipe or 12 inches for smooth wall pipe to facilitate installation and reduce potential for failure from blockage. Ensure that the pipe is capable of withstanding the maximum external loading without yielding, buckling, or cracking. To improve the efficiency of the principal spillway system, make the cross-sectional area of the riser at least 1.5 times that of the barrel. The riser and barrel must be assembled with watertight connections.
 - *Anchoring the Riser* – The base of the riser must be firmly anchored to prevent floating or dislocation, which could result in breaking of the watertight connections and failure of the structure when the water level rises. Secure the riser by an anchor with a buoyant weight greater than 1.1 times the water displaced by the riser.
 - *Draining the Basin* – The riser shall have a skimmer attached to the drain plug at the riser so that it will fill the pond (to create conditions for sedimentation) and then slowly drain between rainfalls (so accumulated sediment will dry out for removal and standing water cannot breed mosquitoes). There are many techniques to accomplish this with either a single hole or multiple small holes.

- *Anti-seep Collars* – These are used to prevent water from seeping between the outside of the barrel and the fill material. Install at least one watertight anti-seep collar with a minimum projection of 1.5 feet around the barrel of the principal spillway conduits, 12 inches or larger in diameter. Locate the anti-seep collar slightly downstream from the dam centerline.
 - *Anti-vortex Device & Trash Guard* – An anti-vortex device and trash guard must be provided for the inlet of the principal spillway. The anti-vortex device prevents the formation of a whirlpool within the riser inlet, which would restrict flow into the riser and reduce its capacity. The trash guard traps floating debris, preventing it from entering the riser and possible blocking the pipe. Trash guards are required on all risers. Anti-vortex devices are required on risers with diameters of 10 inches or more.
 - *Outlet Protection* – Protect the outlet of the barrel against erosion.
10. **Emergency Spillway** – Construct the entire flow area of the emergency spillway in undisturbed soil (not fill). Make the cross section trapezoidal with side slopes of 3:1 or flatter. Make the control section of the spillway straight and at least 20 feet long. The inlet portion of the spillway may be curved to improve alignment, but ensure that the outlet section is straight due to supercritical flow in this portion.
- *Capacity* – The minimum design capacity of the emergency spillway must be the peak rate of runoff from the 10-yr storm, less any reduction due to flow in the principal spillway. In no case should freeboard of the emergency spillway be less than 1 foot above the design depth of flow.
 - *Velocity* – Ensure that the velocity of flow discharged from the basin is non-erosive for the existing conditions. When velocities exceed that allowable for the receiving areas, provide outlet protection.
11. **Embankment** –
- *Cut-off Trench* – Excavate a trench at the centerline of the embankment. Ensure that the trench is in undisturbed soil and extends the length of the embankment to the elevation of the riser crest at each end. A minimum of 2 feet depth is recommended.
 - *Top Width* – The minimum top width of the dam shall be 8 feet for dams less than 10 feet in height and 10 feet wide for dams between 10 and 15 feet in height.

- *Freeboard* – Ensure that the minimum difference between the design water elevation in the emergency spillway and the top of the settled embankment is 1 foot.
 - *Side Slopes* – Make the side slopes of the impoundment structure 3:1 or flatter.
 - *Allowance for Settlement* – Increase the constructed height of the fill at least 10% above the design height to allow for settlement.
12. **Basin Efficiency** – Locate the sediment inlets to the basin the greatest distance from the principal spillway. Allow the maximum reasonable detention period before the basin is completely dewatered – at least 10 hours. Reduce the inflow velocity and divert sediment-free runoff.
13. **Stabilization** – Within 10 working days after completion, all areas disturbed for the basin construction must be provided with ground cover sufficient to restrain erosion. Vegetation (either temporary or permanent) should be used on the top, slopes, and perimeter when the season allows it – when the season is not suitable for establishing vegetation, use a heavy layer of mulch.

Sediment basins shall be installed according to the preceding criteria, the standard detail and the approved erosion control plan.

G. Check Dam

Check dams are small, temporary stone dams constructed across a drainage way to reduce erosion by restricting the velocity of flow in the channel. Limit drainage areas to 2 acres or less. Do not use check dams in live streams.

Use/Design: Keep the maximum height to 2 feet at the center of the dam. Keep the center of the check dam at least 9 inches lower than the outer edges at natural ground elevation. Keep the side slopes at 2:1 or flatter. Ensure that the maximum spacing between dams places the toe of the upstream dam at the same elevation as the top of the downstream dam. Stabilize overflow areas along the channel to resist erosion caused by check dams.

Stone Size – Construct the check dam using well-graded stones with a d50 size of 9 inches (class B erosion control stone is recommended) and a maximum stone size of 14 inches. A 1-ft thick layer of ½ - ¾ inch aggregate (NCDOT #57 washed stone is recommended) should be placed on the upstream face to reduce drainage flow rate.

Installation: Check dams shall be installed according to the standard detail and the approved erosion control plan.

I. Construction Entrance

Construction entrances shall be installed at all points of access to construction sites (both residential and nonresidential) in accordance with the standard details and the approved erosion control plan. Any access point that does not have a construction entrance shall be barricaded to prevent its use.

Nonresidential Construction Entrance – Place fabric from the roadway into the site a minimum of 50 feet and allow for a minimum of 25 foot width along the roadway. Once the fabric is down place 2 inch to 3 inch railroad ballast or surge stone on the fabric. The first 35 feet of the stone shall be at a minimum depth of 6 inches and the remaining 15 feet of the entrance shall be a minimum depth of 12 inches.

Residential Construction Entrance – Install stone from the roadway into the site a minimum of 20 feet and allow for a minimum of 12 foot width along the roadway. Stone shall be clean #57 washed stone and be at a minimum of 6 inches in depth. It is recommended to use fabric under the stone to add to the total life of the construction entrance.

Washing – If conditions at the site are such that most of the mud and sediment are not removed by vehicles traveling over the gravel, tires of vehicles exiting the site should be washed. Washing should be done on an area stabilized with crushed stone that drains into a sediment trap or other suitable disposal area. A wash rack may also be used to make washing more convenient and effective.

Street Cleaning – The City may require the Financially Responsible Party of any project regardless of the size to clean any sediment (mud) that has been tracked or has left the site and is left on a roadway, sidewalk, or right-of-way. Failure to respond to directives by the City to complete the street or sidewalk cleaning and/or any other measures to remove sediment from the street, the City may have such work performed and charged to the Financially Responsible Party in an amount to cover all manual and administrative costs of such work. This shall not create an obligation of the City to undertake such work or to be liable in any way for failure to undertake such work.

J. Diversion Ditch

A diversion ditch is a temporary ridge or excavated channel or combination ridge and channel constructed across sloping land on a

predetermined grade. The purpose is to protect work areas from up-slope runoff and to divert sediment-laden water to appropriate traps or stable outlets. *Diversion ditches shall be used for drainage areas less than or equal to 5 acres.*

Diversion ditches shall be sized to handle the peak runoff from the 10-year storm. Where design velocities exceed 2 ft/second, a channel liner is usually necessary to prevent erosion. Diversions that are to serve longer than 30 working days should be seeded and mulched as soon as they are constructed to preserve dike height and reduce maintenance. Wherever feasible, build and stabilize diversions and outlets before initiating other land-disturbing activities.

Diversion ditches shall be installed in accordance with the standard detail and the approved erosion control plan.

K. Temporary Stream Crossing

A temporary stream crossing is a bridge, ford, or temporary structure installed across a stream or watercourse for short-term use by construction vehicles or heavy equipment. Stream crossings are of three general types: bridges, culverts and fords. Temporary stream crossings shall be installed in accordance with the standard detail, and Practice 6.70 in the *North Carolina Erosion and Sedimentation Control Planning*

L. Storm Drain Inlet Protection

Storm drain inlet protection is a sediment filter or trap around or across the inlet to a storm drain. The different types of storm drain inlet protection consist of 1) block and gravel filter, 2) hardware cloth and gravel filter, 3) excavated pit, and 4) plywood and stone, pipe inlet protection, 5) gravel and rip rap horseshoe inlet. The purpose of inlet protection is to detain and filter sediment-laden runoff before it enters a storm drain.

Erosion control plans that propose to use inlet protection must include detailed instructions and illustrations of how inlet protection will be implemented around each inlet. The plan must also include details of how diversions will be used to capture and direct runoff to the inlet and how berms will be built below the inlet to force runoff through the filter and into the inlet.

1. **Block and Gravel Filters** are particularly useful at storm drain inlets. By varying the number of courses of block, the height of the filter can be varied to fit the particular location. The drainage area to the inlet must be 1 acre or less. Where the drainage area is greater, an excavated pit or other device must be used at the inlet. The filter is built of washed stone, hardware cloth, concrete blocks,

and 2x4's. For yard inlets and junction boxes, the concrete blocks are placed around the perimeter of the inlet with the holes parallel to the ground to allow water to flow through them. The 2x4's are placed behind the blocks as reinforcement. Hardware cloth is placed on the ground around the outside of the blocks and up over the holes in the block to prevent the stone from washing through. The washed stone is then placed on top of the hardware cloth up to the top of the blocks to form the filter. For curb inlets, the block and gravel filter is ½ of the filter for yard inlets and junction boxes. The end of the line of blocks is placed up against the curb to form a C-shaped filter around the opening. Block and gravel filter inlet protection shall be installed according to the standard detail and the approved erosion control plan.

2. **Hardware Cloth and Gravel Filters** are useful at yard inlets and inlets to junction boxes. The height of the filter can be varied to fit the particular location. The short height of the filter and open top allows runoff to overflow into the inlet instead of bypassing it when runoff ponds at the filter. The drainage area to the inlet must be 1 acre or less. Where the drainage area is greater, an excavated pit or other device must be used at the inlet. The filter is built of steel fence posts, hardware cloth, wire, and washed stone. Hardware cloth and gravel filter inlet protection shall be installed according to the standard detail and the approved erosion control plan.
3. An **Excavated Pit** around a storm drain inlet is essentially a sediment trap with the inlet structure serving as the outlet for the sediment trap. For small drainage areas (less than 1 acre), other types of inlet protection are recommended. Where the drainage area exceeds that for inlet protection devices and an excavated pit is desirable, use the sediment trap design criteria. An excavated pit inlet protection shall be installed according to the standard detail and the approved erosion control plan.
4. **Plywood and Stone Pipe Inlet Protection** Storm drain inlets must be protected during all phases of construction, even while the pipe is being laid and before the junction boxes and inlet structures are in place. These devices shall be installed across the upstream pipe opening at the end of each work session and removed at the beginning of the next. If the pipe will not be extended for a prolonged time period gravel and rip rap horseshoe inlet protection with appropriate storage shall be installed to replace the plywood and stone structure. These devices are to be used on the pipe in small storm drain systems that are not located in live streams with large watersheds or watercourses where their use could cause

upstream flooding. These devices are made of plywood or steel fence posts, hardware cloth, and washed stone. Protection for the open end of storm drains shall be installed according to the standard detail and the approved erosion control plan.

M. Slope Drains

Slope drains consist of flexible tubing or conduit extending temporarily from the top to the bottom of a cut or fill slope. The slope drains convey concentrated runoff down the face of the slope without causing erosion. Slope drains are needed where grading or placement of a sediment-trapping device will result in concentrated runoff flowing over an erodible slope. Slope drains are usually used in conjunction with diversions at the top of the slope and some type of sediment-trapping device at the outlet. However, in some instances they may be used below a sediment-trapping device to carry outflow over a steep undisturbed slope.

Slope drains must be designed to carry the peak runoff from a 10-year storm. The drainage area to any single slope drain must not exceed one acre. Larger drainage areas should be divided into several smaller ones to limit the damage if the slope drain should fail. Size the slope drain according to Table 4.2 to size the slope drains.

Table 4.2 Size of Slope Drain

Maximum Drainage Area per Pipe (acres)	Pipe Diameter (Inches)
Less than 0.5	12
0.75	15
1.0	18

Where the drainage area exceeds those in the table, use multiple pipes or, preferably, divide the area into two or more parts. In no instance can the watershed exceed one acre to any point where one or more slope drain is located.

Slope drains shall be installed in accordance with the details (HS23EC) and the approved erosion control plan.

Maintenance: Slope drains must be inspected and maintained so that they continue to perform properly and contribute to erosion control rather than becoming a liability. Failure usually results from improper installation or maintenance of the inlet; runoff flowing between the pipe and the fill creates a weak point, and runoff flows on the slope instead of

in the pipe. Other failures result from faulty pipe connections or an improperly constructed diversion directing runoff to the inlet.

4.04 PERMANENT MEASURES

A. Lined Stormwater Channels

Lined Stormwater channels are open constructed or improved drainage ways to convey runoff through and away from developed areas. The stormwater channel must carry the expected volume and velocity of runoff without damage to the channel lining or erosion of the soil beneath. Stormwater channels may be grass-lined channels, riprap channels or paved channels. Riprap and paved linings are used where velocities are too high for grass-lined channels. Permanent erosion control matting can be used in conjunction with grass-lined swales to increase the velocity of water in the channel. In addition, there are several acceptable shapes for stormwater channels: V-shaped channels, parabolic channels, and trapezoidal channels. V-shaped channels generally apply where the quantity of water is small such as in short reaches along roadsides. The V-shaped channel is least desirable because it is difficult to stabilize the bottom where velocities may be high. Parabolic channels are often used where larger flows are expected and space is available. The swale-like shape is pleasing and may best fit site conditions. Trapezoidal channels are used where runoff volumes are large.

Use/Design: Channels must be designed to carry peak runoff from at least a 10-year storm without eroding. Where flood hazard exists, increase the capacity according to the potential damage. Channel dimensions may be determined by using design table with appropriate retardance factors or by Manning's formula using an appropriate "n" value. The design velocity in the channels determines what type of lining will be required. Stormwater channels shall be designed in accordance with this section, the standard detail, Practices 6.30 and 6.31 in the *North Carolina Erosion and Sedimentation Control Planning and Design Manual*. In addition, Appendix 8.05 in the *North Carolina Erosion and Sedimentation Control Planning and Design Manual*, Design of Stable Channels and Diversions, shall be used to design stormwater channels.

B. Storm Drain Outlet Protection

All stormwater release points shall be protected by riprap dissipation pads designed to reduce discharge velocities to non-erosive levels. Alternate measures will be evaluated on a case by case basis by the Director of

Public Utilities. Dissipation pads shall be designed and constructed with either an engineering fabric or washed stone barrier between the pad and the natural ground. Calculations shall be provided to indicate the sufficiency of the dissipation pads specified. Riprap pad design shall be in accordance with NYDOT or NRCS methods. Storm drain outlet protection shall be installed in accordance with the standard detail and the approved erosion control plan.

4.05 STABILIZATION MEASURES

A. Temporary Stabilization

Temporary seeding is the use of rapid growing annual grasses, small grains or legumes to provide initial, temporary cover for erosion control on disturbed areas for less than 12 months. Mulch is used to provide an immediate ground cover to protect disturbed soil from erosion during the completion of construction until the disturbance is permanently stabilized. Seeding and mulching shall be done immediately following construction. All disturbed areas shall be dressed to a depth of 8 inches (soil loosened using a ripper, harrow, or chisel plow). The top 3 inches shall be pulverized to provide a uniform seedbed.

Agricultural Lime – Shall be applied at the rate of 95-lbs/1000 ft² or 2-tons/ ac. immediately before plowing (soils with a pH of 7 or higher need not be limed).

Grass Seed – Shall be applied at the rates outlined in Table 4.3. Fertilizer application rates are based upon soil tests. When soil testing is not possible, apply a 10-10-10 grade fertilizer at 700-1000 lbs/acre.

Surface Roughening – If recent tillage operations have resulted in a loose surface, additional roughening may not be required except to break up large clods. If rainfall causes the surface to become sealed or crusted, loosen it just prior to seeding by disking, raking, harrowing, or other suitable methods. Groove or furrow slopes steeper than 3:1 on the contour before seeding.

Mulching – The use of appropriate mulch will help ensure establishment under normal conditions and is essential to the success under harsh site conditions. Mulching shall consist of small grain straw applied at a rate of 95-lbs/1000ft² or 2-tons/acre. Mulched areas shall be tacked with asphalt at a rate of 200 to 400 gallons per acre, or other approved method sufficient to hold the straw in place.

If active construction ceases, meaning no substantial or significant progress is made in any area for more than 30 days, all disturbed areas

must be seeded, mulched, and tacked unless written approval is granted by the Environmental Engineer. *Incidental grading shall not constitute substantial or significant progress in construction activity.*

Table 4.3 – Temporary Seeding Recommendations

Date	Type	Planting Rate
Jan. 1 – May 1	Rye <i>and</i>	120 lb/acre
	Annual lespedeza (Kobe) ¹	50 lb/acre
May 1 – Aug. 15	German millet	40 lb/acre
Aug. 15 – Dec. 31	Rye (grain)	120 lb/acre

¹ Omit annual lespedeza when duration of temporary cover is not to extend beyond June. Note on maintenance: refertilize if growth is not fully adequate. Reseed, refertilize and mulch immediately following erosion or other damage.

B. Permanent Stabilization

Permanent stabilization consists of a permanent ground cover to protect the disturbed soil and prevent erosion after completion of the disturbance. The different types of permanent stabilization are: 1) vegetation, 2) mulch, 3) stone, and 4) sod. The City of Dunn Erosion Control Ordinance requires that a permanent ground cover sufficient to restrain erosion be provided within 15 working days or 90 calendar days, whichever period is shorter, after completion of construction or development. Provision must be made in the erosion control plan to stabilize **all** disturbed areas.

Vegetation – Seedbed preparation is very important in establishing good vegetative cover. All disturbed areas shall be dressed to a depth of 8 inches (soil loosened using a ripper, harrow, or chisel plow). The top 3 inches shall be pulverized to provide a uniform seedbed.

Agricultural Lime – Shall be applied at the rate of 95-lbs/1000 ft² or 2-tons/ ac. immediately before plowing (soils with a pH of 7 or higher need not be limed).

Grass Seed – Shall be applied at the rates outlined in Tables 4.4 and 4.5. Fertilizer application rates are based upon soil testing. When soil testing is not possible, apply a 10-10-10 grade fertilizer at 700-1000 160/acre.

Surface Roughening – If recent tillage operations have resulted in a loose surface, additional roughening may not be required except to break up large clods. If rainfall causes the surface to be come sealed or crusted, loosen it just prior to seeding by disking, raking, harrowing, or other

suitable methods. Groove or furrow slopes steeper than 3:1 on the contour before seeding.

**Table 4.4 – Permanent Seeding Recommendations
Shoulders, Side Ditches, Slopes (Maximum slope 3:1)**

Date²	Type	Planting Rate
Aug. 15 – Nov. 1	Tall Fescue or Hard Fescue	300 lb/acre
Nov. 1 – Mar. 1	Tall Fescue & Abruzzi Rye or Annual Rye	300 lb/acre
Mar. 1 – Apr. 15	Tall Fescue or Hard Fescue	300 lb/acre
Mar. 1 – Jul. 15	Hulled Common Bermuda grass OR Hybrid Bermuda grass OR Centipede grass OR Zoysia grass OR St. Augustine grass	200 lb/acre
Apr. 15 – Jun. 30	Weeping Love Grass OR Bahia grass	25 lb/acre
Jul. 15 – Aug. 15	Tall Fescue <u>and</u> Browntop Millet or Sorghum-Sudan Hybrid ¹	35 lb/acre

¹ Temporary – Reseed according to optimum season for desired vegetation. Do not allow temporary cover to grow over 12 inches in height before mowing to keep fescue from being shaded out.

² Seeding dates will vary depending on weather conditions (e.g. temperature, rainfall, etc.)

Note on maintenance: refertilize if growth is not fully adequate. Reseed, refertilize and mulch immediately following erosion or other damage.

Table 4.5 – Permanent Seeding Recommendations
Shoulders, Side Ditches, Slopes (Slopes 3:1 and 2:1 – not mowed)

Date	Type	Planting Rate
Mar. 1 – Jun. 1	Sericea Lespedeza (scarified), AND	50 lb/acre
Mar. 1 – Apr. 15	Add Tall Fescue, OR	120 lb/acre
Mar. 1 – Jun. 30	Add Weeping Love grass, OR	10 lb/acre
Mar. 1 – Jun. 30	Add Hulled Common Bermuda Grass	25 lb/acre
Jun. 1 – Sep. 1	Tall Fescue, AND	120 lb/acre
	Add Browntop Millet ¹ , OR	35 lb/acre
	Add Sorghum-Sudan Hybrids ¹	30 lb/acre
Sep. 1 – Mar. 1	Sericea Lespedeza (unhulled/unscarified),	70 lb/acre
	AND Add Tall Fescue,	120 lb/acre
	AND Add Abruzzi Rye and Annual Rye	25 lb/acre

¹ For temporary seeding purposes.

Note on maintenance: refertilize if growth is not fully adequate. Reseed, refertilize and mulch immediately following erosion or other damage.

When seeding is finished, apply a layer of mulch, usually small grain straw, to encourage seed germination and to protect bare soil until the vegetation is established. It is advisable to anchor the mulch with either asphalt or netting to prevent the mulch being blown away. Where possible, irrigate the seeded areas to promote germination and growth.

As a part of permanent vegetation, maintenance may be required to maintain vegetation for 12 months. This maintenance shall be considered a part of establishing permanent ground cover.

Permanent vegetation shall be installed according to this section and the approved erosion control plan.

Mulch – Mulching is defined as the application of a protective blanket of straw or other plant residue, or synthetic material to the soil surface. Mulching is an acceptable alternative to vegetation, except in locations where slopes are too great for the mulch to remain in place for long periods of time or and where concentrations of runoff require a more durable type of stabilization. Table 4.6 is a list of recommended mulches – this list is not exhaustive and other types of mulch are acceptable when used in the appropriate location, at a rate that will restrain erosion, and in a manner that will keep the material in place.

Table 4.6 – Mulching Materials and Application Rates

Material	Rate per 1000 ft²	Notes
Wood Chips	250 lbs.	Require the addition of nitrogen while decaying
Bark Chips	2 cubic yards	Apply w/ chip handler by hand. Do not use asphalt tack.
Shredded Bark	2 cubic yards	Apply w/ mulch blower
Pine Straw	90 lbs.	Avoid weeds
Compost or Manure	400 lbs.	May contain objectionable weeds

C. Use of Drought Tolerant Plants

All sedimentation and erosion control plans shall be designed to incorporate water conservation materials and techniques through application of landscaping principals, including but not limited to: (1.) use of low water demanding plants and turf; (2.) use of re-use water supplies for irrigation; (3.) minimizing the use of high irrigation turf; (4.) use of mulches to reduce the evaporation rates.

4.06 SLOPES

Cuts, fills and graded areas shall not exceed 2:1 in slope. Slopes which are designed to be stabilized with vegetation which requires mowing shall not exceed 3:1. Slope breaks shall be implemented on long and steep slopes to prevent erosion and gulying consistent with Practice 6.02 in the *North Carolina Erosion and Sedimentation Control Planning and Design Manual*. The Director of Public Utilities may require more restrictive measures for site specific slope and stabilization. Cut and fill slopes adjacent to buffers or tree save areas shall be in accordance with Section 10 of this manual.

4.07 CALCULATIONS

The City shall review all calculations and assumptions used to formulate an erosion control plan. Erosion and sedimentation control measures, structures, and devices shall be planned, designed, and constructed to control the calculated peak runoff from a 10-year frequency storm. Runoff rates shall be calculated using the Rational Method, the Natural Resources Conservation Service (formerly Soil Conservation Service) Method, or other acceptable calculation procedures.

Runoff computations shall be based on rainfall data published by the National Weather Service for this area.

4.08 CONSTRUCTION SEQUENCE

The basic construction sequence on projects shall be as follows:

1. Attend pre-construction conference.
2. Obtain Land Disturbance (grading) Permit.
3. Install tree protection on site.
4. Install all erosion control measures as shown on the approved plan.
5. Call for on-site inspection by Public Utilities Department personnel (919-557-3938) to obtain Certificate of Compliance.
6. Proceed with grading.
7. Clean sediment traps and basins when one-half full.
8. Seed and mulch denuded area within 15 working days or 90 calendar days, whichever period is shorter, after finished grades are established and denuded slopes within 15 working days or 30 calendar days, whichever period is shorter, after finished grades are established.
9. Maintain soil erosion and sedimentation control measures until permanent ground cover is established.
10. Call for on-site meeting to obtain approval for removal temporary erosion control measures, stabilize these areas and install applicable permanent measures and stormwater BMP's.
11. Request final approval by Public Utilities Department – Certificate of Completion

On complex projects, this basic construction sequence shall be expanded to show the order of devices installed, necessary phasing, special circumstances, etc.

4.09 MINIMUM STANDARDS FOR RESIDENTIAL LOTS

Erosion and Sedimentation Control measures shall be installed on all lots under construction regardless of the amount of disturbed area and must meet the following minimum criteria for erosion and sedimentation control measures: residential construction entrance and silt fence on the low side of the lot. Additional erosion control may be required for site specific areas of concern which will be identified by the Director of Public Utilities prior to issuance of a building permit or throughout the construction process.

END OF SECTION 4.00

**SECTION 5.00
PIPE TRENCHES**

SUB-INDEX

- 5.01 EXCAVATION AND PREPARATION OF PIPE TRENCHES**
- 5.02 PIPE LAYING AND BACKFILLING**
- 5.03 BORING AND JACKING**
- 5.04 HORIZONTAL DIRECTIONAL DRILLING**

SECTION 5.00

PIPE TRENCHES

5.01 EXCAVATION AND PREPARATION OF PIPE TRENCHES

Trenches for water distribution lines, sanitary sewer lines, force mains, and storm sewer lines shall be excavated to the required depth to permit installation of the pipe along the lines and grades shown on the construction drawings. The minimum trench width at the top of the pipe shall be at least 18 inches greater than the outside diameter of the pipe. Where excavation is in rock, the rock shall be removed to a depth of at least 6 inches below grade and shall be backfilled with materials in accordance with these specifications. Wet trenches shall be stabilized with #78 M stone or with a base layer of #57 stone.

5.02 PIPE LAYING AND BACKFILLING

All pipe shall be laid in accordance with the manufacturer's recommendations. The subgrade at the bottom of the trench shall be shaped to secure uniform support throughout the length of the pipe. A space shall be excavated under the bell of each pipe to provide space to relieve bearing pressure on the bell and to provide room to adequately make the joint. Open ends of pipe shall be plugged with a standard plug or cap at all times when pipe laying is not in progress. Trench water shall not be allowed to enter the pipe. Backfill material shall be free from construction material, debris, frozen material, organic material, or unstable material. The top 2 feet of backfill material shall be free from stones greater than 4 inches in diameter.

Under roadways and extending at a slope of 1 to 1 beyond the back of curb, measured perpendicular from centerline, backfill shall be compacted to a density of no less than 100% standard Proctor maximum dry density as measured by AASHTO method T99. Backfill shall be placed in lifts of 8 inches or less of the uncompacted soil. Other fill material shall be compacted to a density of no less than 95% of the maximum dry density as measured by AASHTO method T99. Suitable backfill material shall be utilized and compacted. Pavement repair shall be in accordance with the Standard Detail section of these standards.

All trenches shall be properly backfilled at the end of each working day. All pavement cuts shall be repaired within a maximum of 3 days from the date the cut is made. Trench repairs in roadways shall be backfilled with stone and binder or flowable fill as directed by the Inspector. If conditions do not permit a permanent repair within the given time limit, permission to make a temporary repair must be obtained from the Director of Public Utilities. If roadway repairs are not accomplished in accordance with these specifications, City forces may make such

repairs and back charge the project owner in an amount equal to triple for all associated costs (See Section 2.16 of these specifications).

In locations where backfill material is temporarily stockpiled on the roadway surface, a layer of 1½ inches of screenings shall be used between the pavement surface and the backfill material.

5.03 BORING AND JACKING

All crossings of State maintained streets within the City corporate limits shall be by the dry bore and jack method. In cases where circumstances such as utility conflicts will not allow crossing by bore and jack method, the City may consider approving other methods of crossing with additional requirements to minimize pavement failure and maintenance problems. Any crossing requiring an open cut must be approved by the City and NCDOT.

In locations where open pipe trenches are not allowed, dry bore and jack operations may be allowed.

Smooth wall or spiral welded steel pipe may be jacked through dry bores slightly larger than the pipe bored progressively ahead of the leading edge of the advancing pipe. The spoil material shall be mucked by the auger back through the pipe during the boring operation. As dry boring progresses, each new section of the encasement pipe shall be butt-welded to the section previously jacked into place.

In the event that an obstruction is encountered during the boring and jacking operation, and the operation is relocating the auger is to be withdrawn and the excess pipe is to be cut off, capped, and filled with 1:3 portland cement grout at a sufficient pressure to fill all voids before moving to another boring site.

If voids are encountered while installing encasement pipe 30 inches and larger, grout holes shall be installed at 10 foot centers and filled with 1:3 Portland cement grout at sufficient pressure to prevent settlement of the roadway, unless NCDOT approval stipulates otherwise. Other grout mixtures may be submitted for approval.

Steel pipe shall be manufactured of grade 'B' steel with a minimum yield strength of 35,000 psi in accordance with ASTM A139 and A283. When used along or under a roadway maintained by NCDOT, the encasement pipe shall be coated to meet NCDOT requirements.

Size and wall thickness of smooth wall or spiral welded encasement pipe shall be as follows:

Pipe Size (O.D.) (inches)	Wall Thickness (inches)
12 ³ / ₄	0.188
16	0.250
18	0.250
20	0.250
24	0.250
30	0.312
36	0.375

Casing pipe shall be installed with a minimum cover of 3 feet under pavement.

All carrier pipe shall be ductile iron pipe resting on metal spiders as shown in the Standard Details section of these standards so as to prevent damage to the pipe bell. Pipe bells shall not contact the interior of the casing pipe. No blocks or spacers shall be wedged between the pipe and the top of the casing. Casing pipe shall have the following minimum sizes:

Carrier Pipe Size (inches)	Casing Pipe Size (inches)
4	12 ³ / ₄
6	12 ³ / ₄
8	18
10	20
12	24
14	26
16	28

5.04 HORIZONTAL DIRECTIONAL DRILLING

Water and sewer forcemain may be installed by horizontal directional drilling in areas where disturbance must be minimized. This does not include installation under city streets unless approved by the Director of Public Utilities.

Piping shall be polyethylene pipe (See Section 6.01 of these specifications).

Guided Boring Contractors will have actively engaged in the installation of pipe using guided boring for a minimum of three years. Field supervisory personnel employed by the Guided Boring Contractor will have at least three years experience in the performance of the work and tasks as stated in the contract document.

Submit the following drawings and documents:

1. Working drawings and written procedure describing in detail the proposed method of installation. This will include, but not be limited to: size, capacity and setup requirements of equipment; location and siting of drilling and receiving pits, dewatering if applicable, method of fusion and type of equipment for joining pipe, type of cutting tool head, and method of monitoring and controlling line and depth.
2. If the Contractor determines that modifications to the method and equipment as stated in the submittal is necessary during construction, the Contractor will submit a plan describing such modifications, including the reasons for the modification.
3. Bentonite drilling mud products information (MSDS); special precautions necessary; method of mixing and application; and method of removing spoils.

Drilling operations must not interfere with, interrupt or endanger surface and activity upon the surface. The Contractor shall conduct pre-bid and pre-drill investigations of each individual site and make a determination as to the existing conditions. When rock stratum, boulders, underground obstructions, or other soil conditions that impede the progress of drilling operations are encountered, the Contractor shall change from a conventional drilling bit to one suitable for drilling in rock formations. This change in equipment shall be at no additional cost to the City of Dunn.

Drilling fluid will be a mixture of water and bentonite clay. The Contractor will be responsible for making provisions for a clean water supply for the mixing of drilling fluid. The fluid will be inert. The fluid should remain in the tunnel to ensure the stability of the tunnel, reduce drag on the pulled pipe, and provide backfill with the annulus of the pipe and tunnel. Excess drilling fluid must be disposed of at an approved site. The contractor shall describe in writing the disposal location to the engineer. Disposal of drilling fluids must meet all federal and state standards. Contractor is responsible for transporting all excess fluids to the disposal site and paying any disposal costs. Contractor shall immediately clean up all locations where drilling fluid inadvertently surfaces.

The contractor shall verify the location of all adjacent underground utilities before beginning work.

The Public Utilities Director and the Design Engineer shall be notified immediately if any obstruction is encountered that stops the forward progress of drilling operations. Dewatering of pits and excavations must meet the general provisions and specifications for new forcemain construction. The type of dewatering method will be at the option of the Contractor. When water is encountered, the Contractor must provide a dewatering system of sufficient capacity to remove water, keeping any excavations free of water until the backfill

operation is in progress. Dewatering shall be performed in a manner that soil particle removal is held to a minimum. The Contractor and any of his subcontractors performing work in the state right-of-way in connection with boring operations shall furnish to the City necessary bonds and/or insurance certificates as noted in the permit(s).

Excavate required pits in accordance with the working drawings. The drilling procedures and equipment shall provide protection of workers, particularly against electrical shock. As a minimum, grounding mats, grounded equipment, hot boots, hot gloves, safety glasses, and hard hats shall be used by crewmembers. The drilling equipment shall have an audible alarm system capable of detecting electrical current.

The entry angle of the pilot hole and the boring process will maintain a curvature that does not exceed the allowable bending radii of the product pipe. The Contractor shall follow the pipeline alignment as shown on the Drawings, within the specifications stated. If adjustments are required, the Contractor shall notify the Engineer for approval prior to making the adjustments.

After the pilot hole is completed, the Contractor shall install a swivel to the reamer and commence pullback operations. Pre-reaming of the tunnel may be necessary and is at the option of the Contractor. Reaming diameter will not exceed 1.5 times the diameter of the product pipe being installed. The product pipe being pulled into the tunnel will be protected and supported so that it moves freely and is not damaged by stones and debris on the ground during installation. Pullback forces will not exceed the allowable pulling forces for the product pipe. The Contractor shall allow sufficient lengths of product pipe to extend past the termination point to allow connections to the diffuser assembly. Pulled pipe will be allowed 24 hours of stabilization prior to making tie-ins. The length of extra product pipe will be at the Contractor's discretion. Drilling fluid returns (caused by fracturing of formations) at locations other than the entry and exit points will be minimized. The Contractor will immediately clean up any drilling fluids that surface through fracturing.

END OF SECTION 5.00

**SECTION 6.00
WATER DISTRIBUTION**

SUB-INDEX

6.01 WATER DISTRIBUTION PIPE

- A. Design**
- B. Material**
- C. Installation**

6.02 FIRE HYDRANTS

- A. Location**
- B. Specifications**
- C. Installation**

6.03 VALVES AND APPURTENANCES

- A. Location**
- B. Specifications**
- C. Installation**

6.04 WATER SERVICE TAPS

- A. Materials**
- B. Individual Water Services**

6.05 CLEARANCE BETWEEN WATER MAINS, SANITARY AND STORM SEWERS

6.06 BACKFLOW PREVENTION AND CROSS CONNECTION

- A. General**

6.07 AUTOMATIC FIRE SPRINKLER SYSTEMS

- A. General**
- B. Design**
- C. Post Indicator Valve**
- D. Backflow Prevention**
- E. Fire Department Connection**
- F. Dedicated Riser Room**
- G. Access**
- H. Identification**

I. Installation

6.08 TESTING AND INSPECTION

- A. Hydrostatic Testing**
- B. Chlorination**
- C. Bacteriological Sampling**

6.09 FIRE PROTECTION DURING CONSTRUCTION

6.10 IRRIGATION SYSTEMS

6.11 REPAIR OF WATER LINES

SECTION 6.00

WATER DISTRIBUTION

6.01 WATER DISTRIBUTION PIPE

A. Design

Location: Water lines shall be extended along the entire roadway frontage length of any proposed project. All public water mains shall be located within dedicated right of way or dedicated easements with a minimum width of 20 feet. Landscape plantings, fences, or structures shall not be allowed within water line easements.

Sizing: Water lines shall be sized as directed by the Director of Public Utilities. In residential areas, mains shall be 6-inch and 8-inch diameters. Six-inch mains shall be used only when a good grid exists. The total maximum length of 6-inch and 8-inch line, without connection to a larger main, is 1200 feet and 2000 feet, respectively. Where a sufficient grid network does not exist, lines shall be upsized additionally to provide adequate fire flow as directed by the Director of Public Utilities. If there is adjacent developable property, an adequate size line to properly serve future development shall be provided sufficient for any future project to meet City standards.

B. Material

All water mains shall be either ductile iron or PVC. The Public Utilities Department will maintain a list of approved manufacturers of other water distribution products. New manufacturers must submit requests for approval to the Public Utilities Department. Additional information such as catalogs, list of installations in the area, or material samples may be required. A written response will be mailed to the applicant accepting or rejecting the product within 90 days of the receipt of all necessary information.

Ductile Iron Pipe shall be designed and manufactured in accordance with AWWA C150 and C151 for a laying condition Type 2 and a working pressure as follows:

3-12 inches	350 psi
14-20 inches	250 psi
24 inches	200 psi

Pipe Joints shall be of the push-on type as per AWWA C111. Pipe lining shall be cement mortar with a seal coat of bituminous material in accordance with AWWA C104. Galvanized steel pipe will not be allowed as a material for water mains or water services lines.

Polyethylene Pipe shall be designed and manufactured in accordance with the following standards, unless otherwise specified:

1. ASTM D-3350 Polyethylene Plastics (PE) Pipe and Fittings Materials
2. ASTM D-2321-74 Underground Installation of Flexible Thermoplastic Sewer Pipe
3. ASTM F-714 Polyethylene Plastic Pipe (SDR-PR) Based on Outside Diameter
4. AWWA C 900 Polyethylene (PE) Pressure Pipe and Fittings 4" through 12" for Water Distribution, C905 for 14"-36".

All pipe shall be DIP (Ductile Iron Pipe Size) unless otherwise noted on the plans.

C. Installation

All cross country waterline mains shall be a minimum of 4 feet deep from existing grade. All water mains shall be installed with a minimum cover of 3 feet measured from the top of the pipe to the finished subgrade of the roadway. When water lines are installed along a roadway which does not have curb and gutter or which are planned to be widened in the future, the water line shall be installed at 4.5' minimum depth below edge of existing pavement. In addition, all waterline installation shall be placed to prevent conflict with future road improvements or foreseeable vertical alignment changes. Where air release valves are located on water mains the lines should be a minimum of 6 feet below the existing edge of pavement in this area.

Locator devices as manufactured by 3M Corporation shall be placed directly on top of distribution water mains along major thoroughfares and cross-country installations (and as otherwise directed by the Director of Public Utilities) at 100' intervals and turns/bends. Locator tape shall also be required to be installed at 2' above the pipe.

All construction relating to the utility improvements which will be maintained by the City of Dunn must be performed by a contractor licensed in North Carolina. Proof of licensure will be required at the Project Preconstruction Meeting. Operation of existing valves and fire hydrants shall be by City staff only.

6.02 FIRE HYDRANTS

A. Location

All fire hydrants shall be installed on a minimum 6-inch waterline. Only 1 fire hydrant may be installed on a dead end 6-inch line. There shall be at least 1 fire hydrant at each street intersection located in accordance with the Standard Detail section of these Standards. Each fire hydrant shall have a valve on the hydrant service leg, located within 15 feet of the fire hydrant.

In residential areas, the maximum distance between fire hydrants, measured along street centerlines, shall be 500 feet. When residential intersections are not more than 700 feet apart, no hydrant is required between the intersections. In residential areas, the minimum fire flow shall be 1000 gpm with a minimum system pressure of 25 psi.

In business, office and institutional, and industrial districts, the maximum distance between hydrants, measured along street centerline, shall be 300 feet. When business, office and institutional, and industrial intersections are not more than 450 feet apart, no hydrant is required between intersections. The minimum fire flow in these areas shall be 1500 gpm with a minimum system pressure of 25 psi.

On major thoroughfares with access points only at street intersections, hydrants shall be located at each street intersection and staggered at 1000 foot intervals along the street. Where these intersections are less than 1200 feet apart, no hydrant is required between the intersections.

When new buildings are constructed, or existing buildings expanded, and they contain 10,000 total square feet of floor space (all floors of all buildings, new and existing, added together) hydrants shall be installed at 300-foot intervals along all sides of the building that are accessible to fire pumpers. These hydrants shall be at least 40 feet from the building. The total number of hydrants required shall not exceed 1 hydrant per separation of buildings, plus 1 hydrant per 10,000 square feet of floor space.

See Section 6.07E for fire hydrants required for automatic fire sprinkler systems.

Where sprinkler systems are used, the fire department connections shall be located within 50 feet of a fire hydrant and at fall zone line or as specified by the Fire Department, and shall be located so that nothing obstructs direct access. Where a sprinkler system or a riser room are required, outside access in accordance with the N.C. Building Code shall be provided. Backflow prevention for sprinkler systems shall be as specified in Section 6.06 of these Standards. Flow data for system design shall be field-verified by the designer. The City will provide assistance with opening valves and hydrants for the collection of data.

B. Specifications

Hydrants shall be furnished by Mueller, model shall be Centurian 250. Hydrants shall be equipped as follows: 4½-inch Storz Nozzle and double 2½-inch hose connections with caps and chains, National Standard Threads, mechanical joint, 1½-inch pentagon operating nut, open left, painted fire hydrant Safety Yellow, bronze to bronze seating, a minimum 3½-foot bury depth with break away ground line flange and break away rod coupling. The hydrant bonnet will be designed with a sealed oil or grease reservoir with O-ring seals and a Teflon thrust bearing, furnished by Mueller "Centurion" (A-421). Fire hydrant caps shall be attached to the body of the hydrant with a minimum 2/0 twist link, heavy duty, non-kinking, machine chain.

C. Installation

Hydrants shall be set plumb, properly located with the pumper nozzle facing the closest curb. The back of the hydrant opposite the pipe connection shall be firmly blocked against the vertical face of the trench with 1/3 cubic yard of concrete. Double bridle rods and collars shall not be less than 5/8 inch diameter stock and coated with bituminous paint. All fire hydrants shall be newly painted in accordance with NFPA standards. A minimum of 8 cubic feet of stone shall be placed around the drains. The backfill around the hydrants shall be thoroughly compacted. Hydrant installation shall be in accordance with the Standard Details section of these Standards. Fire hydrant shall be installed with a minimum of 18"-24" from center of 6" cap to grade and shall be installed with positive drainage.

6.03 VALVES AND APPURTENANCES

A. Location

Valves shall be installed on all branches from feeder mains and hydrants according to the following schedule: 3 valves at crosses; 2 valves at tees; and 1 valve on each hydrant branch. When a loop section of waterline is connected back into the feeder main within a distance of 200 feet or less, only 1 valve will be required in the feeder main.

Where no waterline intersections are existing, a main line valve shall be installed at every 100 feet per 1-inch diameter main up to a distance of 2000 feet between valves.

Blowoff assemblies shall be a minimum of 2 inches and installed at the end of all dead-end waterlines. Where there is not sufficient pressure or fire hydrants located to thoroughly flush the system, a larger blowoff may be required. On

large diameter mains or other circumstances, larger blowoffs may be required by the Director of Public Utilities.

Combination air valves shall be installed at high points of waterlines 12 inches in diameter or larger, as directed by the Director of Public Utilities. Water lines shall be installed at a grade which will allow the air to migrate to a high point where the air can be released through an air valve. A minimum pipe slope of 1 foot in 500 feet should be maintained. The size of air valve shall be designed by a Professional Engineer registered in North Carolina. Combination air valves or other types of air release valves may be required at other locations as directed by the Director of Public Utilities.

B. Specifications

Gate Valves greater than 2 inches shall meet all requirements of AWWA C500 for a working pressure of 150 psi. All shall be mechanical joint with iron body, resilient wedge seat type in accordance with AWWA C509 with a non-rising stem and open left with a double O-ring seal. Gate valves shall be installed in a vertical position. Acceptable brands CLOW, Kennedy, Mueller or equal.

Valve Boxes shall be cast iron of the screw or telescopic type with a 5-inch opening with "water" stamped on the cover. Valve box ring adjustments will not be allowed. Locking valve boxes may be required as determined by the Director of Public Utilities. All castings shall be made in the United States.

Butterfly Valves shall be installed in waterlines 16 inches or greater. All shall meet the requirements of AWWA C504 with mechanical joints, 2-inch operating nut and open left. Acceptable brands, Pratt, CLOW, K-Flo, Milliken or equal.

Blowoff Assemblies shall be constructed as shown in the Standard Details Section of these Standards. The valves shall be an AWWA iron body gate valve with a non-rising stem and a 2-inch operating nut.

Pipe Fittings shall be compact D.I. fittings in accordance with AWWA C153. Joints for fittings shall be mechanical joint and lined with cement mortar with a seal coat of bituminous material, all in accordance with AWWA C104.

Reaction Blocking for all fittings or components subject to hydrostatic thrust shall be securely anchored by the use of concrete thrust blocks poured in place. The required reaction areas are shown in the Standard Details Section of these Standards. Concrete shall be installed so that it does not interfere with the removal of fittings. Material for reaction blocking shall be 3000 psi concrete. Alternative restraining methods may be considered only in unusual circumstances and must be designed by a Professional Engineer registered in North Carolina and approved by the Director of Public Utilities.

Tapping Sleeves shall be stainless steel sleeves with stainless steel flanges. The sleeves shall be mechanical joint to the main line and flanged to the tapping valve. Acceptable material Mueller, Rockwell, CLOW, Romac or equal.

Tapping Saddles shall be used on mains. Saddles shall be made of ductile iron providing a factor of safety of 2.5 with a working pressure of 250 psi. Saddles shall be equipped with an AWWA C110 flange connection on the branch. Sealing gaskets shall be O-ring type, high quality molded rubber having an approximate 70 durometer hardness, placed into a groove on the curved surface of the saddles. Straps shall be alloy steel.

The maximum size saddle outlet for each size of pipe to be tapped shall be as follows:

Size pipe to be tapped	Maximum size saddle outlet
16"	12"
20"	16"
24" and 30"	20"
36"	24"

Acceptable brands Mueller, Rockwell, Ford, Romac.

Combination Air Valves shall be of the single housing style that combines the operation of both an air/vacuum and air release valve. The valve shall be manufactured for a 150 PSIG working pressure and be sized by the Design Engineer of Record. The valve must meet the requirements of AWWA C512 and be installed in accordance with the Standard Details Section of these Standards. Acceptable Manufacturer A.R.I. Model D-025.

C. **Installation**

Valves shall be properly located, operable and at the correct elevation. All valves and reducers shall be rodded to a nearby tee or cross if possible. As shown in the Standard Details Section of these Standards. If reducers cannot be rodded, concrete blocking or other restraining methods will be required. The valve box shall be centered over the wrench nut and seated on compacted backfill without touching the valve assembly. The maximum depth of the valve nut shall be 5 feet, unless approved by the Director of Public Utilities. When valve extension kits are used, they must be manufactured by the same company which manufactured the valve.

All valve boxes in roadways shall be encased in a trowel-finished 24" diameter circle by 8" thick circular pad of 3000 psi concrete beneath the asphalt course with the cover flush with the top of the pavement.

Valve boxes outside roadways shall be flush with finished grade with a 2'x2'x6" concrete encasement or precast concrete donut.

Precast concrete valve box encasements may be used for valve box encasement outside of paved areas only.

6.04 WATER SERVICE TAPS

A. Materials

Corporation Stops shall be brass, complete with a flared coupling and AWWA Standard threads as per AWWA C800. Taps shall be located at 10 or 2 o'clock on the circumference of the pipe. Service taps shall be staggered alternating from one side of the water main to the other, and at least 12 inches apart. The taps must be a minimum of 24 inches apart if they are on the same side of the pipe. Irrigation tap and domestic taps shall be metered separately.

All taps shall include service saddles.

Service Saddles shall be bronze body (85-5-5 waterworks brass) and double strap for taps with silicon bronze nuts conforming to ASTM A98 and factory-installed grade 60 rubber gaskets.

Service Lines ¾" to 2" shall be blue C.T.S. Pipe with inserts.

Meter Boxes for ¾-inch and 1-inch Services shall be 12 ½ inch depth cast iron MBX-1 and a complete unit (less meter) for setting a 5/8 by 3/4-inch water meter. Meter box grade adjuster rings are not acceptable. Meter Box to be installed with 4" above grade in grassy areas. Installed at the property line. Include touch reader hole.

Meter Boxes for 2-inch Services shall be 18 1/8 inch depth cast iron MBX-5. Piping for 1½ and 2-inch water meters shall be constructed from brass and copper tubing and shall be equipped with angled check valve outlets and by-pass flanged valve or by-pass flanged ball valve inlets. Meter boxes shall not be allowed in travel lanes or traffic areas. Meter box grade adjuster rings are not acceptable. Meter Box to be installed 4" above grade in grassy areas. Include touch reader hole.

Meters for services shall be supplied and installed by the City of Dunn. Meters shall be compatible with Sensus fixed network (Accu Stream with Smart Point) Shall be paid for by the Developer and installed by the City of Dunn Public Utilities Department after approval by the Director of Public Utilities. A strainer shall be provided upstream of the meter on lines greater than 2 inches.

Meter Boxes shall not be located in sidewalk or travel lanes, except as noted below, unless traffic rated or approved by Director.

Meter Vaults within paved areas shall meet HS-20 loading requirements and shall be located outside travel areas. The access door shall be aluminum with a flush drop lift handle, stainless steel hinges and bolts, a stainless steel slam lock, an automatic hold open arm, and compression springs to allow for easy opening. Positive drainage shall be provided for all meter vaults. Positive drainage shall be construed to mean a “daylight” drain not less than 4” schedule 40 PVC pipe with flap valve on the end.

B. Individual Water Services

Individual water services shall be provided from the main to each water meter for single family residences in accordance with the Standard Details section of these Standards. A private side cut-off valve shall be required per City of Dunn Ordinance Book, Chap. 21 – Utilities; Art. II –Connections; Sect. 21-40 - Private Side Water Cut-off Valves. Multi-family units may be in accordance with the Standard Detail for multi-family units in the Standard Details section of these Standards. All connections shall be made by wet taps.

Split residential tap will be allowed if a 1” tap is made. Otherwise, meter irrigation & domestic must be separate taps.

Service connections shall be made perpendicular from the main line and shall run straight horizontally toward the meter and then vertically to the meter which shall be located at the edge of the right of way or easement of the served property. Refer to the standard detail on water service installations for more information. No water meter box or vault shall be located in streets, sidewalks, or parking areas in residential areas. In non-residential areas, meter locations shall be approved on a case-by-case basis. Provisions for backflow prevention shall be as specified in Section 6.06 of these Standards.

Service taps to existing water lines shall be made by the City of Dunn Utilities Department, unless otherwise approved by the Director of Public Utilities. Service taps to new water lines shall be made by the Contractor in accordance with these Standards.

Water meters shall be sized based on water demand. Water meter size shall be determined from the following table; or as otherwise specified by the Director of Public Utilities. All non-residential projects shall submit sealed calculations prepared in conformance with the AWWA Manual of Practice for approval of type of meter and meter size by the City.

Meter Size (inches)	Flow Range (GPM)
5/8" PD	0 - 20
1" PD	20 - 50
1½" PD	50 - 100
2" C	100 - 200
3" C	200 - 400
4" C	400 - 600
6" C	600-800
8" C	800-1000
10" C	1000-2000

PD = Positive Displacement
 T = Turbine (may be required on a case-by-case basis)
 C = Compound (must be sized on a case-by-case basis)

6.05 CLEARANCE BETWEEN WATER MAINS, SANITARY AND STORM SEWERS

Water mains shall be laid at least 10 feet laterally (measured edge to edge) from existing or proposed sanitary or storm sewers unless NCDENR determines that local conditions or barriers prevent a 10-foot lateral separation--in which case:

- (1) The water main is laid in a separate trench, with the elevation of the bottom of the water main at least 18 inches above the top of the sewer; or
- (2) The water main is laid in the same trench as the sewer with the water main located at one side on a bench of undisturbed earth, and with the elevation of the bottom of the water main at least 18 inches above the top of the sewer.

Whenever it is necessary for a water main to cross over a sewer, the water main shall be laid at such an elevation that the bottom of the water main is at least 18 inches above the top of the sewer, unless local conditions or barriers prevent an 18 inch vertical separation--in which case both the water main and sewer shall be constructed of ferrous materials and with joints that are equivalent to water main standards for a distance of 10 feet on each side of the point of crossing.

Whenever it is necessary for a water main to cross under a sewer, both the water main and the sewer shall be constructed of ferrous materials and with joints equivalent to water main standards for a distance of 10 feet on each side of the point of crossing. A section of water main pipe shall be centered at the point of crossing.

Water mains and storm sewer mains shall have a minimum vertical separation of 12 inches when horizontal separation is less than 5 feet.

Water lines that cross and run beneath storm drainage pipes that are greater than or equal to 42" diameter (single pipe) or 36" diameter (multiple pipes) shall be installed as restrained joint pipe and enclosed in casing pipe. Installation may be by bore and jack or excavation at discretion of Director of Public Utilities.

Water lines that cross streams and/or creeks shall be installed without disturbance inside the top of bank on either side of the stream/creek. Installation may be by bore and jack or horizontal directional drilling (HDD). Other means of crossing must be approved by the Director of Public Utilities.

Where distribution systems are installed in areas of groundwater contaminated by organic compounds, pipe and joint materials which do not allow permeation of the organic compounds shall be used. Non-permeable materials shall be used for all portions of the system in contact with contamination, including: pipe, joint materials, hydrant leads, and service connections.

6.06 BACKFLOW PREVENTION AND CROSS CONNECTION

A. General

Cross-Connection shall mean any unprotected actual or potential connection or structural arrangement between a public or a consumer's water system and any other source or system through which it is possible to introduce any contamination or pollution, other than the intended potable water with which the system is supplied.

All residential water services for domestic purposes shall be provided with a dual check backflow prevention device on the meter setter within the meter box.

All irrigation services and non-residential services shall be provided with reduced pressure principle backflow prevention installed in accordance with the State of North Carolina and the Foundation for Cross Connection Control and Hydraulic Research. Reduced pressure zone (RPZ) backflow preventers shall be installed immediately behind the meter (on the private side) with the installation to be above ground. Alternate installations require approval of the Director of Public Utilities. Above-ground installations may require an insulated box mounted on a 4" concrete slab, wired for a heater and provided with a heater. A 4" concrete slab shall be provided for insulated boxes.

Cross-connection control protection devices are required based on degree of health hazard involved as listed in Appendix-B of the Rules Governing Public

Water Systems in North Carolina. These guidelines are the minimum requirements. The devices shall meet American Society of Sanitary Engineering (ASSE) standards or be on the University of Southern California approval list. The devices shall be installed and tested (both initial and periodic testing thereafter) in accordance with the manufacturer's recommendations or the local cross-connection control program, whichever is more stringent.

Wilkins Regulator Co. Model 975 R

For the following main sizes: 2 ½", 3", 4", 6", 8" & 10"

Wilkins Regulator Co. Model 975 B

For the following main sizes: ¾", 1", 1 ¼", 1 ½" & 2

Wilkins Regulator Co. Model 575 R

For the following main sizes:

2 ½", 3", 4", 6", M8", & M10"

Wilkins Regulator Co. Model 975 AB

For the following main sizes:

¾", 1", 1 ¼", 1 ½" & 2"

6.07 AUTOMATIC FIRE SPRINKLER SYSTEMS

A. General

Working drawings and calculations for all fire sprinkler systems and standpipe systems, prepared by a Professional Engineer registered in North Carolina, shall be submitted to the City of Dunn Inspection Department for approval before installation begins.

B. Design

Design shall include backflow prevention measures, details on any proposed fire pumps and/or tanks, calculations to insure that the allowable pressures in the City system are maintained. Flow data for system design shall be field-verified by the designer. The City will provide assistance with opening valves and hydrants for the collection of data. Fire lanes are required in front of all FDC, Riser Rooms, Fire Hydrants, PIV, and other entrances and exits as determined by the City.

C. Post Indicator Valve

A post indicator valve shall be provided on the owner's side at the right of way or edge of easement. The valve shall be locked in open position monitored by an electronic tamper switch. When backflow prevention devices are contained within a building, an outside access (above the finish floor elevation) shall be provided. The top of the post indicator valve shall be installed at 36 inches from the finished grade and must be protected from vehicular obstruction with means

of steel bollards when not located behind curb. The City shall maintain up to, but not including, the post indicator valve.

D. Backflow Prevention

When a fire protection system is proposed and no anti-freeze chemicals are to be used, a University of Southern California-approved double check valve assembly shall be included on the sprinkler fire protection line. If any chemicals are proposed to be added to a sprinkler fire protection system, a reduced pressure principle backflow preventer approved by Underwriters Laboratories and/or the State of North Carolina and the Foundation for Cross Connection Control and Hydraulic Research, University of Southern California shall be used.

E. Fire Department Connection

Where automatic fire sprinkler systems are used, a Fire Department Connection (FDC) shall be provided. The Fire Department Connection shall be located 36 inches above proposed grade and within 50 feet of a fire hydrant and at fall zone line or as specified by the Fire Department, and shall be located so that nothing obstructs direct access. A 5 foot clearance shall be provided around the FDC connection and labeled with 4 inch contrasting colored letters. When a sprinkler system serves only part of a large structure, the fire department connection shall be labeled as to which section of the structure that sprinkler riser serves. This labeling shall be a minimum of 2 inch lettering on a permanent sign. FDC shall have national standard threads and have brass caps with chains.

F. Dedicated Riser Room

A dedicated sprinkler riser room providing an entry door to the room from the exterior of the building in accordance with NC Building Code shall be provided. The exterior riser room door plus all other required or City designated fire exits shall have a protected clearance of 5 feet from any obstruction by vehicular movement by means of curbing, bollards, or concrete bumpers.

G. Access

All non-residential or other buildings which have a fire sprinkler protection system shall provide a "Knox Box" key entry system. This Knox Box shall be mounted on the exterior entrance to the dedicated riser room. Mount Knox Box on wall at 5 feet A.F.F. on door handle side of dedicated riser room door. This Knox Box shall be ordered through the City of Dunn Fire Department and shall be in place before a Certificate of Occupancy is issued. Forms are available from the City Fire Department. Average delivery time is 5 to 6 weeks. Keys to access the facility shall be provided to the City Fire Department by the owner/manager.

H. Identification

The exterior door leading to the dedicated sprinkler riser room shall be labeled with minimum 4 inch lettering designating "SPRINKLER RISER ROOM" in a contrasting color. Durable vinyl lettering is suggested.

I. Installation

All gas or electrical panels must be protected with steel bollards from vehicular traffic.

6.08 TESTING AND INSPECTION

Under no circumstance shall any waterline system valve be operated without prior approval by the Construction Inspector. Damage to City infrastructure resulting from illegal operation of valves shall be the responsibility of the Contractor. In addition, the Contractor shall be subject to a fine for operating a valve without prior approval.

All materials shall be inspected by the Construction Inspector before they shall be allowed to be installed. Materials rejected by the Construction Inspector shall be immediately removed from the job site.

The Contractor shall furnish all materials, labor, equipment, used to perform all testing and inspections to the satisfaction of the Construction Inspector. The Contractor shall coordinate with Public Utilities when blowing off water mains.

Water service taps shall not be made until after all water main testing is completed, and bacteriological testing is satisfactory.

A. Hydrostatic Testing

No valve in the existing City of Dunn water system shall be operated without authorization from the Construction Inspector or City Staff. Each section of line which is to be hydrostatically tested shall be slowly filled with water at a rate which will allow complete evacuation of air from the line. Once the line is full, it shall be blown off at a minimum of 2.5 FPS to flush and remove any debris. The line must be pretested at 200 psi for 2 hours prior to contacting inspector for testing. Hand pumps shall not be used for the pressure testing of water mains. Taps used for testing purposes shall be removed after testing in accordance with Section 6.11 of these Standards.

Each water line shall be tested to a pressure of 200 psi as measured at the lowest elevation of the line for a duration of 2 hours. The pressure gauge used in the

hydrostatic test shall be calibrated in increments of 10 psi or less. At the end of the test period, the leakage shall be measured with an accurate water meter. Note that all visible leaks are to be repaired regardless of the amount of leakage. The construction inspector may require pressure tests to be performed in small section to determine if there is a problem with a particular section of waterline. No chlorine dosage will be allowed in line during testing.

ALLOWABLE LEAKAGE	
Pipe Size (inches)	Amount of Allowable Leakage (gallons per 1000 feet of pipe)
4	0.75
6	1.10
8	1.47
12	2.21
16	2.94
20	3.68
24	4.41

B. Chlorination

All additions or replacements to the water system shall be chlorinated before being placed in service. Such chlorination must take place under the supervision of the Construction Inspector.

Chlorination of a completed line shall be carried out in the following manner:

- 1) The specific procedure and order of testing and blowoffs shall be approved by the Construction Inspector before beginning the chlorination process.
- 2) Taps shall be made at the control valve at the upstream end of the line and at all extremities of the line including valves.
- 3) A solution of water containing high test hypochlorite (65%) available chlorine shall be introduced into the line by regulated pumping at the control-valve tap. The solution shall be of such a concentration that the line shall have a uniform concentration of 100 ppm total chlorine immediately after chlorination. The following chart shows the required quantity of 65% HTH compound to be contained in solution in each 1000 foot section of line to produce the desired concentration of 100 ppm.

HYPOCHLORITE SOLUTION	
Pipe Size (inches)	High Test Hypochlorite (65%) (pounds per 1000 feet of line)
6"	1.88
8"	3.35
10"	5.70
12"	7.53
14"	10.26
16"	13.43
20"	20.92
24"	30.14

- 4) The HTH solution shall be circulated in the main by opening the control valve and systematically manipulating hydrants and taps at the line extremities. The HTH solution must be pumped in at a constant rate for each discharge rate in order that a uniform concentration will be produced in mains. *Note that for projects that are surrounded by populated development areas, the Construction Inspector can require that the circulation of HTH solution be accompanied with mechanical pumping.*
- 5) HTH solution shall remain in lines for no less than 24 hours or as directed by the Director of Public Utilities.
- 6) Extreme care shall be exercised at all times to prevent the HTH solution from entering existing mains.

C. Bacteriological Sampling

All new water systems shall be valved off from the existing water system until a satisfactory bacteriological sample is obtained and the Construction Inspector has authorized the use of the new water system.

1. Free residual chlorine after 24 hours shall be at least 10 ppm or the Construction Inspector shall require that the lines be rechlorinated.
2. Flushing of lines may proceed after 24 hours, provided the free residual chlorine analysis is satisfactory. Flushing shall be continued until a chlorine test kit shows that the lines contain only the normal chlorine residual.

3. Samples for bacteriological analysis shall be collected by the City of Dunn Water Plant Personnel, they will perform the Bac-T Testing and provide results to the Project Inspector and to the Contractor.
4. If bacteriological test results are unsatisfactory, the Contractor shall immediately obtain another Water Blowoff Permit, rechlorinate and retest the lines, proceeding with such measures as are necessary to secure properly disinfected lines.

6.09 FIRE PROTECTION DURING CONSTRUCTION

The fire protection water supply system, including fire hydrants, shall be installed and tested prior to placing combustible materials on the project site.

6.10 IRRIGATION SYSTEMS

No irrigation systems to be installed in the City's right of way.

Irrigation systems shall have a backflow preventer installed in accordance with Section 6.06 of these Standards. All irrigation systems are required to secure a plumbing permit from the Inspection Department prior to installation and shall be inspected after installation. A separate meter is required for irrigation systems.

All irrigation line street crossings shall be contained within an encasement conduit. ductile iron or steel casing pipes shall be used. The City may, in some instances, permit irrigation systems installed in the medians of City-maintained roadways. These systems must also have french drains installed behind the curb and gutter and piped to a storm drainage collection system. These systems shall be allowed only when some permanent mechanism is established for the private perpetual maintenance of the system(s). Split taps will only be allowed on 1" taps or larger.

6.11 REPAIR OF WATER LINES

Joint Leaks of cast iron pipe, ductile iron pipe, and PVC pipe shall use a bell joint leak repair clamp as manufactured by Rockwell, or other approved equal.

Line Breaks or Punctures shall be repaired by a full circle repair clamp as manufactured by Rockwell, Mueller, or other approved equal.

Line Splits or Blow Outs shall be repaired by replacing the damaged section with ductile iron pipe with a cast iron coupling at each end. The following cast pipe couplings shall be used for each pipe material indicated:

- A.C. Pipe - Rockwell 441 cast coupling or other approved equal
- Ductile Iron Pipe - Rockwell 431 cast coupling or other approved equal
- PVC Pipe - Rockwell 411 cast coupling or other approved equal

For A.C. Pipe to PVC or Ductile Iron Pipe connections, use Romac or HY-Max with different end diameters sized specifically for the pipe materials, and pipe outside diameter at each end.

Water Service Line Repairs

- A water service line severed between the water main and the water meter shall be repaired using new C.T.S. Blue with inserts 3/4" – 2" and bronze or brass 3-piece flare unions.
- A corporation stop pulled out of a PVC pipe water main shall have a new service saddle and a new corporation stop installed on the water main.
- A corporation stop pulled out of a ductile iron pipe water main shall have a full circle repair clamp placed over the old tap hole. A new tap shall be made and a new corporation stop installed on the water main.

<u>Size</u>	<u>Color</u>	<u>Material</u>
3/4"	Blue	CTS
1"	Blue	CTS
2"	Blue	CTS
3"	Blue	PVC

END OF SECTION 6.00

**SECTION 7.00
SANITARY SEWER**

SUB-INDEX

- 7.01 GRAVITY SEWER MAINS**
 - A. Design**
 - B. Materials**
 - C. Additional Requirements for Flexible and Semi-Rigid Sanitary Sewer Pipe**

- 7.02 FORCE SEWER MAINS**
 - A. Materials**
 - B. Installation**

- 7.03 MANHOLES**
 - A. Materials**

- 7.04 SERVICE CONNECTIONS**
 - A. Materials**
 - B. Installation**

- 7.05 TESTING AND INSPECTION**

- 7.06 REPAIR OF SANITARY SEWER LINES**

- 7.07 WASTEWATER PUMP STATIONS**
 - A. General Requirements**
 - B. Site Work**
 - C. Odor Control**
 - D. Piping and Valves**
 - E. Wet Well**
 - F. Electrical**
 - G. Alarm Dialer**
 - H. Generator Sets**
 - I. Transfer Switch**
 - J. SCADA**
 - K. Pump Motor Controls**
 - L. Force Main**
 - M. Water Service**
 - N. Landscaping and Appearance**
 - O. Warranties and Documentation**
 - P. Testing and Inspection**
 - Q. Davit Crane**
 - R. Fences and Gates**

SECTION 7.00

SANITARY SEWER

7.01 GRAVITY SEWER MAINS

A. Design

Location

1. All public sanitary sewer mains shall be installed in dedicated street right of way or in dedicated utility easements. Sanitary sewer mains installed in City of Dunn maintained streets shall be located in the center of travel lanes. Mains located within N.C. Department of Transportation right of way shall be placed outside of pavement limits, in accordance with NCDOT standards. See Section 2.10 for landscape plantings within Utility easements.

2. Minimum widths of public sanitary sewer easements shall be:

<u>Pipe Size</u>	<u>Pipe Depth</u>	<u>Easement Width</u>
12" and smaller	Less than 20'	20'
12" and smaller	Greater than 20'	30'
Greater than 12", up to 36"	Less than 20'	30'
Greater than 12", up to 36"	Greater than 20'	40'
Greater than 24"	All depths	Director of Public Utilities Specified

3. Sewer mains shall be centered within their easements.

4. Proposed sanitary sewers paralleling a creek shall be designed to a proper depth to allow lateral connections such that all creek crossings will be below stream bed elevation unless otherwise approved by the Director of Public Utilities. The top of the sewer main shall have at least one foot of cover between it and the stream bed. Concrete encasement and ductile iron pipe, in accordance with the Standard Details Section of these Standards, shall be required when the cover between the top of the pipe and the stream bed is less than 3 feet.

Sewer lines crossing under stream and/or storm drainage pipe containing a single pipe greater than 42 inches or multiple pipes greater than 36 inches may be required to be installed with restrained joint pipe inside a steel casing pipe. Installation may be by bore and jack or excavation which will be at the discretion of the Director of Public Utilities. All encasements to be extended a minimum of 10 feet beyond the stream bank and/or storm drainage pipe.

5. Sanitary sewer mains shall not be installed under any portion of water impoundments unless approved by the Director of Public Utilities.
6. The following minimum separations must be maintained:
 - a) any private or public water supply source, including WS-1 waters or Class I or Class II impounded reservoirs used as a source of drinking water – 100 feet;
 - b) any waters classified WS-II, WS-III, B, SA, ORW, HQW or SB (from normal high water [or tide elevation] – 50 feet;
 - c) any other stream, lake, or impoundment – 25 feet or as required by State law.

Where the required minimum separations cannot be maintained, ferrous sanitary sewer pipe with joints equivalent to water main standards shall be used. However, in no instance may sanitary sewer lines be installed less than 25 feet from a private well or less than 100 feet from a public water supply source (or as required by State law).

7. Sanitary sewer lines shall be extended to adjacent upstream property lines, in order to serve all upstream properties. These lines shall be sized to serve all upstream tributary areas.

Size

1. The minimum size of public gravity sanitary sewer mains shall be 8”.
2. New sewer interceptors shall be designed based on the proposed land use (in accordance with the City’s Master Land Use Plan) of the contributory area. The following flow factors shall be used:

Land Use	Flow Factor
Residential	120 gpd/bedroom
Office & Institutional	0.09 gpd/square feet of building space
Commercial	0.12 gpd/square feet of building space
Industrial	0.10 gpd/square feet of building space

Flow factors not listed herein shall be in accordance with the factors recommended by the NCDEQ.

These figures cover normal infiltration; however an additional allowance shall be required where conditions are unfavorable.

3. For existing sewer systems, an additional allowance shall be made to the above flow factors where the existing flow exceeds these values and immediate remedial measures are not proposed.
4. The ratio of peak to average daily flow shall be 2.5.
5. Sanitary sewers shall be designed to carry the projected peak flow at no more than ½ full. The recommended minimum velocity for sanitary sewer lines is 2 fps.

The minimum grades for public sanitary sewers shall be as follows:

Main Size (inches)	Minimum Slope (feet/100 feet)
8	0.40
12	0.22
15	0.15
16	0.14
18	0.12
21	0.10
24	0.08
27	0.07
30	0.06
36	0.06

6. The maximum grade for sanitary sewers is 10%. The maximum velocity in sanitary sewers is 15 feet per second. These limits may be exceeded

with the approval of the Director of Public Utilities and with the incorporation of the following provisions:

- a) All sewers of greater than 10% slope shall be ductile iron pipe;
 - b) High velocity manholes, in accordance with the Standard Details Section of these Standards shall be used on all sewers with a slope greater than 10%;
 - c) Concrete anchors shall be installed on all sewers of greater than 10% slope at the following spacings:
 - i) Not over 36' center to center on grades from 10% to 25%;
 - ii) Not over 24' center to center on grades from 25% to 40%;
 - iii) Not over 16' center to center on grades exceeding 40%.
7. Sewer extensions should be designed for projected flows even when the diameter of the receiving sewer is less than the diameter of the proposed extension.
 8. Pipe diameter changes shall occur in a manhole with the invert of the larger pipe lowered sufficiently to maintain the same energy gradient. An approximate method of securing these results is to place the 0.8 depth point of both sewers at the same elevation.
 9. All residential subdivision lots shall be served by public gravity sanitary sewer unless otherwise approved by the Director of Public Utilities. If a pump is approved, it shall be privately maintained, must pump into a gravity service connection placed on the lot, and must have a note on the construction plans and recorded plat indicating a private pump may be required to serve the lot with sanitary sewer service.
 10. Downstream receiving sewer infrastructure shall be evaluated to confirm adequate capacity by the design engineer for each project. Developer shall be required to upgrade insufficient infrastructure.

Installation

1. Sanitary sewer mains shall be deep enough to serve adjoining and upstream properties and allow for sufficient slope in lateral lines without being exposed in parallel streams or swales. All sanitary sewer mains shall have the following minimum covers:

- a) 4.5 feet from the top of pipe to finished subgrade when under a roadway or adjacent to a roadway which may be widened in the future;
- b) 3 feet from top of pipe to finished grade in all other areas.

The above requirements may be waived at the direction of the Director of Public Utilities, in which case ductile iron pipe shall be installed.

- 2. The construction of all sanitary sewer lines which will be maintained by the City must be performed by a contractor licensed in North Carolina.
- 3. Sewer mains from 14 to 20 feet deep shall require special bedding in accordance with the Standard Details Section of these Standards.
- 4. Sewers over 20 feet deep shall require ductile iron for the entire run between manholes.
- 5. Pipe trench excavation and backfilling shall be performed in accordance with Section 5.00 of these Standards.
- 6. Transitions of pipe material shall occur only at manholes.
- 7. Sanitary sewers shall be laid at least 10 feet laterally edge to edge from existing or proposed water mains unless the top of the sewer main is at least 24 inches below the bottom of the water main and there is a horizontal separation of at least 3 feet from the closest edges of the pipes.
- 8. Where sanitary sewers cross beneath water mains with a vertical separation of 24 inches or less or where water mains cross under sewer mains, the entire leg of sewer line shall be ductile iron pipe. The water line pipe shall be centered at the point of crossing and shall cross sanitary sewer lines at an approximate 90 degree angle.
- 9. Where sanitary and storm sewers cross with a vertical separation of less than 12 inches the entire leg of sanitary sewer shall be of ductile iron pipe. Sanitary sewers shall have the top of pipe at least 12 inches below the bottom of storm sewer pipe when the horizontal separation between the closest edges of the two pipes is 3 feet or less.
- 10. There shall be a minimum 5-foot horizontal separation between parallel gravity and/or force mains.
- 11. Sewer line easements shall be completely cleared of all vegetation, graded smooth, free from rocks, boulders, roots, stumps, and other debris, free

from ponded water, and seeded and mulched upon the completion of construction.

12. The first new downstream manhole(s) of any sanitary sewer line extension under construction shall be plugged on the outlet side and secured with stainless steel cable to prevent the passage of groundwater, runoff and sediment into the existing sanitary sewer system. All water upstream of the plug shall be pumped out of the sanitary sewer line and all sediment and solids shall be removed and properly disposed of by the Contractor. The plug shall have an identification plaque of stainless or aluminum directly mounted to show contractor's name. Inspection of installation of plug shall be required by the Construction Inspector. The plug shall not be removed until the line has been inspected by the Construction Inspector to insure that all possible points of inflow or infiltration have been secured. Failure to meet this requirement will result in a \$1,000 per day fine. If the plug blows out and causes equipment or material damage or spills downstream, the Contractor shall be responsible for resulting fines and costs of repairs. Authorization to remove the plug shall be required by Construction Inspector. If the Contractor fails to obtain necessary approvals and removes the plug before the system is activated, the Contractor shall be responsible for resulting State and City fines and damages resulting.

Manholes

1. All manhole cone sections shall be the eccentric type.
2. Manholes shall be spaced at a maximum distance of 425 feet apart.
3. Manholes for sewers under 18 inches in diameter shall be a minimum of 4 feet in diameter. Manholes for sewers 18 inches in diameter or greater shall be 5 feet in diameter.
4. All manholes that are over 20 feet deep shall be 5 feet in diameter.
5. Manholes shall be installed at each deflection of line and/or grade. The flow channel through manholes should be smooth and shall conform to the shape of the entering/exiting sewer line. A standard 0.20-foot drop shall be provided at each manhole. Inverts "in" and "out" shall be as designated on the approved plans. Sewers shall be designed to minimize free drops in manholes.

Either precast or brick and mortar inverts may be used conforming to these Standards. The invert shall be smooth and uniform in shape along the entire length.

6. Outside drops shall be used when free drops exceed 24 inches. For drop manholes, the entire upstream leg of sewer must be ductile iron. For drop manholes, see the Standard Details Section of these Standards. Where the difference between the incoming pipe and manhole invert is less than 24" inches but greater than 12 inches, the invert shall be filleted to prevent solids deposition.
7. Manholes not located in roadways shall have a top elevation a minimum of 12 inches above finished grade. Manholes located along outfalls shall have a top elevation a minimum of 24 inches above finished grade or 100 year flood plain, or 12 inches above 500 year flood plain, whichever is higher.
8. Watertight manhole rings and covers shall only be allowed upon approval by the Director of Public Utilities. Manholes with watertight tops shall be vented in accordance with the Standard Details Section of these Standards.
9. Manholes located within flood plain areas, on outfalls, and within any areas of high groundwater shall be waterproofed by wrapping all joints with a minimum 8-inch width band of butyl joint wrap.
10. All manholes shall be vacuumed tested in accordance with ASTM C-1244.

B. Materials

The Director of Public Utilities will maintain a list of approved manufacturers for all sanitary sewer collection system products. New manufacturers must submit requests for approval to the Director of Public Utilities. Additional information such as catalogs, lists of installations in the area or material samples may be required. A written response will be mailed to the applicant accepting or rejecting the product within 90 days of the receipt of all necessary information.

Each length of sanitary sewer pipe installed shall have plainly and permanently marked thereon the following information:

1. Pipe class or strength designation;
2. Manufacturer's name or trademark;
3. Nominal pipe size.

Ductile Iron Pipe

Ductile iron pipe for gravity sewer use shall be designed and manufactured in accordance with AWWA C150 and C151 for a laying condition Type 2 and a working pressure as follows:

3" - 12"	350 psi
14" - 20"	250 psi
24"	200 psi
30" & up	150 psi

Pipe joints shall be of the push-on type as per AWWA C1211. Pipe lining shall be Protecto 401 Ceramic Epoxy lined.

Polyvinyl Chloride (PVC) Pipe

PVC pipe shall be made of PVC plastic having a cell classification of 12454-B, 12454-C or 13364-B (with minimum tensile modulus of 500,000 psi) as defined in Specification D1784. PVC pipe shall have integral wall bell and spigot joints for the conveyance of domestic sewage. Fittings shall be made of PVC plastic having a cell classification of 12454-B, 12454-C or 13343-C as defined in Specification D1784. Fittings must be manufactured by pipe supplier or approved equal, and have bell and/or spigot configurations compatible with that of the pipe. Compounds with superior properties are also acceptable.

All pipe less than 16 inches in diameter shall have a maximum Standard Dimension Ratio (SDR) of 26. Where laying conditions so warrant, and in accordance with manufacturer's recommendations, lower SDR values (stronger pipe) may be required.

PVC pipe 16 inches in diameter and larger SDR-26.

Installation shall consist of Class I bedding material (as defined in Section 7.01 C) placed 4 inches below the pipe barrel and continuing to 4 inches above the pipe barrel, as per ASTM D2321. In addition, the installation of PVC pipe shall satisfy the requirements of Section 7.01-C below. See the Standard Details Section of these Standards for bedding requirements.

C. Additional Requirements for Flexible and Semi-Rigid Sanitary Sewer Pipe

Installation of flexible and semi-rigid sanitary sewer pipe shall satisfy the requirements of the manufacturer and/or the following, whichever is more stringent:

1. Installation shall follow the recommendations of ASTM D-2321 "Underground Installation of Flexible Thermoplastic Sewer Pipe." For flexible and semi-rigid pipes, bedding and embedment material shall be Class I. In any area where the pipe will be installed below existing or future ground water levels or where the trench could be subject to inundation, additional Class I material shall be used for bedding. Refer to

the Standard Details Section of these Standards for embedment requirements.

2. The manufacturer's specifications or otherwise approved method shall be used in determining the stiffness class of the pipe to be installed so as to attain the required deflection control. The class of the pipe must be approved by the Director of Public Utilities prior to installation.
3. The maximum allowable deflection after installation shall be less than 5% for flexible pipe and 3% for semi-rigid pipe. The mandrel (go/no-go) deflection test must be performed on each line prior to acceptance, and no less than 30 days after installation. The Contractor shall supply the mandrel used for this performance test. The mandrel device shall be cylindrical in shape having 9 possible contact points with the pipe. The mandrel's length and diameter (ID of proving ring) shall equal the dimensions in the following table, and shall be subject to the Construction Inspector's approval.

For flexible pipes the following shall apply:

Nominal Diameter (inches)	Mandrel Length (inches)	Mandrel Diameter (inches)
6	6	5.65
8	8	7.40
10	10	9.31
12	10	11.22
15	12	14.09
18	Varies	17.05
21	Varies	19.09
24	Varies	21.46
27	Varies	24.70
30	Varies	27.69
36	Varies	28.13

4. For PVC pipe, the pipe shall be produced with bell and spigot end construction. Joining will be accomplished by rubber gasket in accordance with manufacturer's recommendation, unless otherwise directed or approved by the Director of Public Utilities. Flexible watertight elastomeric seals in accordance with ASTM D3212-81, may also be used. Each pipe length shall be clearly marked with information including pipe size, profile number, and class number.
5. Minimum trench width shall be one pipe diameter plus 9 inches on each side of the pipe.

6. Bedding (6-inch minimum) and embedment materials shall be per ASTM D2321. Embedment materials shall be installed from trench wall to trench wall and from the invert to a minimum of 6 inches above the crown of the pipe.
7. The bedding and embedment material shall be compacted to a minimum of 90% Standard Proctor density for Class I materials.
8. If hydraulic jack shoring is utilized for trench walls where shoring is used, it shall be kept to the area just above the top of the pipe. This will ensure the embedment materials and pipe will not be disturbed when removal is made.
9. Bedding and embedment material classifications shall be defined as follows:

Class I - Angular, (¼ to 1½ inch) graded stone, including a number of fill materials that have regional significance such as coral, slag, cinders, crushed stone, crushed gravel, and crushed shells.

Class II - Coarse sands and gravels with maximum particle size of 1½ inch, including variously graded sands and gravels containing small percentages of fines, generally granular and non-cohesive, either wet or dry. Soil types GW, GP, SW and SP are included in this class.

Class III - Fine sand and clayey gravels, including fine sands, sand-clay mixtures, and gravel-clay mixtures. Soil types GM, GC, SM, and SC are included in this class.

Class IV - Silt, silty clays, and clays, including inorganic clays and silts of medium to high plasticity and liquid limits. Soil types MH, ML, CH and CL are included in this class. These materials are not recommended for embedment.

7.02 FORCE SEWER MAINS

A. Materials

Ductile Iron Pipe shall be required for force sewer mains at shallow depths (less than 3 feet) or when crossing water and storm piping. Ductile iron pipe shall be designed and manufactured in accordance with AWWA C150 and C151 for a laying condition Type 2 and a minimum working pressure as follows:

3" - 12"	350 psi
14" - 20"	250 psi
24"	200 psi
30" - 54"	150 psi

Pipe joints shall be of the push-on type as per AWWA C111. Pipe lining shall be lined with Protecto 401 Ceramic Epoxy Coating in accordance with AWWA C104. The Director of Public Utilities reserves the right to require other pipe lining materials in certain applications.

PVC Pipe PVC pipe shall meet the requirements of AWWA C900. Pipe shall be Class 150, SDR 18, integral bell with strength equal to the pipe wall, cast iron O.D., 18-foot length, with a solid elastomeric ring.

PVC pipe for force mains with a diameter of 3 inches or less shall be SDR-21 or Schedule 40 in accordance with ASTM D1785.

PVC pipe shall require the installation of a 3-inch wide detector tape placed a maximum of 2 feet below the covering surface.

Pipe fittings shall be compact designed and manufactured per AWWA C153. Joints for fittings shall be mechanical joint and lined with cement mortar with a seal coat of bituminous material, all in accordance with AWWA C104.

Combination air valves shall be A.R.I. Model D025 or an approved equal.

B. Installation

Reaction blocking for all fittings or components subject to hydrostatic thrust shall be securely anchored by the use of concrete thrust blocks poured in place. The reaction areas are shown in the Standard Details Section of these Standards. No concrete shall interfere with the future removal of fittings. Material for reaction blocking shall be 3000 psi concrete.

Force mains shall be installed with a minimum cover of 4.5 feet measured from the top of the pipe to existing edge of pavement. Force mains shall be appropriately identified upon installation so that they will not be confused with potable waterlines. The pipe material shall be designated continuously on each joint of pipe as "sewer."

Force mains shall be designed and installed to minimize high points.

Sewage combination air valves shall be installed at all the high points of all force mains in accordance with the Standard Details Section of these Standards.

Manholes containing valves shall receive a bituminous or coal tar epoxy coating on the interior.

Force sewer mains shall be installed in dedicated public rights of way or in dedicated utility easements. See Section 2.10 for landscape planting requirements within easements. Easements shall have the following dimensions:

Line Size	Easement Width
12" and under	20 feet
greater than 12"	30 feet

All force mains shall have an in-line valve located 25 feet from the pump station. In addition, force main valves shall be spaced at appropriate intervals as determined by the Director of Public Utilities, and shall have **locking** valve box caps marked "Sewer." Force main valves shall be resilient wedge gate type for force mains less than 12"; valves greater than 12", shall be Dezurik eccentric plug valves, or approved equal.

Force mains at air release manholes shall be a minimum of 6' deep.

The receiving manhole plus the first downstream manhole below the receiving manhole for a force main shall receive an interior coating of Koppers "Super Service Black" with a total dry film thickness of 10 mils. All nicks and scratches shall be touched up prior to acceptance of the manhole. The force main shall discharge at the invert of the receiving manhole and shall be as close as possible to 180° from the outlet pipe.

No drop is allowed in the receiving manhole for a force main.

Locator devices as manufactured by 3M Corporation shall be placed directly on top of the sewer force mains, along major thoroughfares and cross-country installations (and as otherwise directed by the Director of Public Utilities) at 100 feet intervals and turns/bends.

7.03 MANHOLES

Materials

Manholes shall be precast concrete. All manholes shall have eccentric cone sections.

Precast concrete manholes shall meet ASTM C478 as to design and manufacturer. The standard joint shall be sealed with a plastic cement putty meeting Federal Specification SS-S-00210, such as Ram-Nek or a butyl rubber sealant. All lift holes must be plugged with non shrinking grout after installation.

For precast concrete manholes, see the Standard Details Section of these Standards.

Manhole frames and covers shall be cast in ductile iron, conforming to ASTM A-48 Class 30, with "Sanitary Sewer" stamped on the cover and two 1-inch perforated holes. Castings shall be machined to give even and continuous bearing on the full length of the frame. Castings shall be free of porosity and blow holes, and shall receive one coat of Koppers Super Service Bitumastic black paint. Paint shall be kept off of bolt threads and surfaces shall be thoroughly wire-brushed before painting. Manhole frames shall be bolted to the manhole as per the Standard Details Section of these Standards. All manhole rings in roadways shall be encased in a concrete collar, 18 inches by 12 inches, of 3,000 psi concrete beneath the asphalt, with the cover flush with the top of pavement and rated for an AASHTO loading Class HS-20, as shown in the Standard Details Section of these Standards.

Watertight manhole frames and covers shall have neoprene gasket, machine bearing surfaces. Bolts shall be standard hexagonal-head, countersunk such that when fully tightened bolt head is flush with the top of the cover. Castings shall be free of porosity and blow holes, and shall receive one coat of Koppers Super Service Bitumastic black paint. Paint shall be kept off of bolt threads and surfaces shall be thoroughly wire-brushed before painting. Watertight manhole frames and covers shall only be permitted in lieu of elevating the manhole tops above the 100 and/or 500 year flood plain with specific approval by the Director of Public Utilities.

Manhole steps shall be furnished with the precast sections. Steps shall be of polypropylene material reinforced with a half-inch diameter grade 60 reinforcing steel rod. Manhole steps shall be designed for a vertical load of 400 pounds and a horizontal pull out load of 1,000 pounds. Steps shall be set 16" on center. Holes for the installation of manhole steps shall not project through the manhole wall. There shall be a minimum of 1-inch wall thickness from the deepest penetration of the step installation hole and the outside wall. Steps shall be at least 10" clear width and shall project at least 4" from the wall into which it is embedded. Steps shall not be located over the influent or effluent pipes and shall be installed along a vertical manhole wall from the shelf to the top of cone.

All manholes shall have 6-inch, 3,000 psi concrete bottoms resting on a minimum of 6 inches of #57 stone. Sewer mains shall enter and exit radially through the manhole. Inverts shall be constructed with a width and height equal to half that of the effluent pipe and shall be so brushed and troweled that a minimum energy loss occurs in the manhole.

At each inlet and outlet of line 8 inches or greater, wastewater lines are to be connected to the manholes by means of compression connectors (flexible sleeves) cast into the manhole section. Flexible connectors are to be manufactured of high

have a minimum slope of 2.0 feet per 100 feet. Service lines 6-inch in diameter shall have a minimum slope of 1.0 feet per 100 feet. Cleanouts shall be required on all sewer services at a maximum spacing of 50 feet on 4-inch services and 100 feet on 6-inch services. A cleanout shall be placed on all service lines at the right of way line or at the edge of the easement. All cleanouts shall extend a minimum of 6 inches above finished grade or meet the optional installation requirements in accordance with the Standard Details Section of these Standards. Sewer cleanouts located in paved areas must have traffic load bearing mini-manhole.

All 6-inch service lines shall tie directly into a manhole.

All service lines which are connected into manholes shall be installed less than 24 inches above the invert or shall be installed with a standard drop as shown on the Standard Details Section of these Standards. Service lines shall not be installed through manhole cone sections or manhole joints. The use of service saddles will only be permitted for connection to existing sewer lines.

7.05 TESTING AND INSPECTION

All materials used must be inspected by the Construction Inspector before they shall be allowed to be installed. Materials rejected by the Construction Inspector shall be immediately removed from the job site.

The Contractor shall furnish all materials, labor, and equipment used to perform all testing and inspection to the satisfaction of the Construction Inspector.

Sanitary sewer lines shall be free and clean from obstructions and shall be visually inspected from every manhole to ensure all lines exhibit a fully circular pattern. Lines which do not exhibit a true line and grade or have structural defects shall be corrected. Require all 8" and above to be inspected by camera. Any sewer mains and services shall require internal visual inspection by TV Camera at the expense of the developer at beginning of one year warranty and at end of one year if deemed necessary. Sanitary sewer service connections shall be visually inspected prior to backfilling.

See Section 7.01 C for additional testing requirements for flexible and semi-rigid pipe.

Low-pressure air testing shall be performed before all laterals or stubs are installed on the line and after the main has been backfilled to finished grade. Plugs shall be installed at each manhole to seal off the section of line to be tested. The line will be pressurized with a single hose and monitored by a separate hose connection from the plug. Air shall be slowly introduced into the sealed line until the internal air pressure reaches 4.0 psig. The air pressure shall then be allowed to stabilize for a minimum of 2 minutes to no less than 3.5 psig (plus groundwater

quality rubber or synthetic rubber and all strap clamps or draw bolts are to be manufactured from stainless steel.

7.04 SERVICE CONNECTIONS

A. Materials

PVC pipe shall be schedule 40 or greater supplied in 18 foot lengths. The pipe may be joined by elastomeric gaskets.

Ductile iron pipe shall be used for sanitary sewer services with less than 3 feet of cover or in excess of 16 feet of cover.

Services for new lines shall use in-line wyes of like material unless otherwise approved by the Director of Public Utilities.

Service saddles for existing PVC or ABS lines shall be of the same material as the main, solvent welded and fastened with double stainless steel bands as shown on the Standard Details Section of these Standards.

Service saddles for existing cast iron soil pipe services may be "ROMAC C" sewer saddles consisting of a virgin SBR gasket compounded for sewer service, a ductile iron saddle casting, a 304 stainless steel adjustable strap for fastening the gasket and the saddle casting to the sewer main and a 304 stainless steel adjustable circle clamp for securing the service line into the SBR gasket.

B. Installation

Individually owned structures shall require individual sewer taps to public sewer. All service connections to existing sanitary sewer mains shall be made by the City of Dunn Public Utilities Department.

Service taps into mains shall be made on the top quarter of the main with the wye angled with the direction of flow in the main. All services installed on new lines shall be inline wyes unless otherwise approved by the Director of Public Utilities.

Service lines between 3 and 14 feet in depth do not require special bedding. All service lines between 14 and 20 feet in depth shall require Class I bedding from 4 inches below service line to 4 inches above the service line. Service lines greater than 16 feet or less than 3 feet in depth must be ductile iron.

Service connections to the main lines shall be perpendicular to the main line to the edge of the right of way or easement line. Service lines 4-inch in diameter shall

pressure, if any). When the pressure reaches 3.5 psig, the time required for the pressure to drop 1.0 psi shall be observed and recorded. The line shall be termed “acceptable” if the pressure does not drop more than 1.0 psi in the time prescribed for the test in the following table:

STANDARD AIR TEST TABLE									
Specification time (min:sec) required for pressure drop from 3½ to 2½ psig when testing one pipe diameter only									
Length of Time (feet)	Pipe Diameter (inches)								
	4	6	8	10	12	15	18	21	24
25	0:04	0:10	0:18	0:28	0:40	1:02	1:29	2:01	2:38
50	0:09	0:20	0:35	0:55	1:19	2:04	2:58	4:03	5:17
75	0:13	0:30	0:53	1:23	1:59	3:06	4:27	6:04	7:55
100	0:18	0:40	1:10	1:50	2:38	4:08	5:56	8:05	10:34
125	0:22	0:50	1:28	2:18	3:18	5:09	7:26	9:55	11:20
150	0:26	0:59	1:46	2:45	3:58	6:11	8:30		
175	0:31	1:09	2:03	3:13	4:37	7:05			
200	0:35	1:19	2:21	3:40	5:17				12:06
225	0:40	1:29	2:38	4:08	5:40			10:25	13:36
250	0:44	1:39	2:56	4:35			8:31	11:35	15:07
275	0:48	1:49	3:14	4:43			9:21	12:44	16:38
300	0:53	1:59	3:31				10:12	13:53	18:09
350	1:02	2:19	3:47			8:16	11:54	16:12	21:10
400	1:10	2:38			6:03	9:27	13:36	18:31	24:12
450	1:19	2:50			6:48	10:38	15:19	20:50	27:13
500	1:28			5:14	7:34	11:49	17:01	23:09	30:14

If the section of line tested fails to meet these requirements, the source of leakage shall be determined and repaired. The section of line shall then be retested.

The Construction Inspector may require that an infiltration test be performed. Infiltration shall not exceed 100 GPD per inch per mile.

At the discretion of the Director of Public Utilities, sanitary sewer manholes in areas of special concern may be required to be vacuum tested in accordance with ASTM C-1244.

7.06 REPAIR OF SANITARY SEWER LINES

The repair of damaged sanitary sewer lines shall be as follows:

1. V.C. Pipe - Replace damaged section with PVC or DI. Install a Fernco coupling at each end (encased in concrete).
2. PVC Pipe - Replace damaged section with PVC or DI pipe. Install a Fernco coupling at each end (encased in concrete).
3. ABS/PVC Truss Pipe - Replace damaged section with PVC or DI. Install a Fernco coupling at each end (encased in concrete).
4. A.C. Pipe – Replace damaged sections of A.C. pipe from bell to bell, use Hy-Max Couplings @ connections using DI or PVC pipe.

All repairs to damaged sanitary sewer lines shall be backfilled with ABC stone (crusher run) to a density of 95% Standard Proctor.

7.07 WASTEWATER PUMP STATIONS

A. General Requirements

In situations where gravity sewer is not feasible, the City of Dunn will consider allowing the installation of a wastewater pump station and force main. Note that the following factors shall be utilized in determining where wastewater pump stations may be installed:

1. Determination of, and design to, handle the wastewater flow that would be generated by the total natural drainage basin based upon a combination of the proposed land use plan and/or approved developments, whichever flow is greater, or as directed by the Director of Public Utilities with a design life as specified by the City. The City may require pump station to be constructed downstream to serve a larger basin.
2. Evaluation (and upgrades, if necessary) of the capacity and suitability (with respect to potential for odor problems) of the receiving sewer main at the point of discharge and points downstream to determine if the downstream infrastructure can handle the transferred sewer flow. In addition, new pump stations may not discharge upstream of other existing pump stations. The Director of Public Utilities has the ability to approve deviations to this requirement due to extenuating circumstances.

3. A cost analysis of the pumping versus a gravity alternative (if one is available). The estimated installed cost of the gravity alternative divided by the estimated installed cost of the pump station alternative must be equal to or greater than 3.5 for the City to consider allowing a pumping station. The City reserves the right to require special features and/or special components on certain pump stations per the Director of Public Utilities.
4. The City reserves the right on any pump station to perform the design and/or construction administration, with the developer reimbursing the City in full.
5. The City reserves the right to disallow pump stations where, in the City's opinion, it is not efficient or desirable to have another pump station.
6. New developments may be required to take downstream or upstream pump stations off line, or upgrade them as directed by the Director of Public Utilities.
7. For any new or upgraded pump station, one spare pump of identified size and manufacturer shall be provided to the City prior to pump station startup. The spare pump will be stored at the Public Utilities Department.

Wastewater pump stations shall meet all requirements of these standards and NCDEQ Design Standards. **The developer and the developer's engineer shall meet with the City Director of Public Utilities in a "pre-design meeting" prior to preliminary plan-level submittal of a site or subdivision requiring a pump station. The meeting shall be to discuss the site layout and other details and requirements for any proposed pump station before design begins.** All pump stations shall be Gorman Rupp suction lift and all construction materials shall be suitable for exposure to wastewater. Pump stations shall meet the N.C. Building Code and shall be designed to comply with all OSHA regulations in addition to these Standards.

All stations shall have a minimum of 2 pumps of equal capacity. The pumps shall be capable of handling flows in excess of the expected peak flow. The peak flow for design shall be equal to 2.5 times the average daily flow. Where 3 or more pumps are required, they should be of such capacity that with any one unit out of service, the remaining units will have capacity to handle peak sewage flows. Pumps and the sewage force main shall be sized to provide a minimum velocity in the force main of 2.0 fps and a maximum velocity of 10 fps maximum allowable velocity is dependent upon force main material. The City reserves the right to require a larger force main size at no cost to the City based upon operating (power) costs.

Wastewater pump stations, all related structures and controls, shall be protected from physical damage by the 100 year and 500 year local and FEMA flood plains and shall be elevated to 2 feet above the most restrictive elevation. Flood elevations shall be supported by a flood study based on future land uses. Stations shall be designed to remain fully operational and accessible during the 100 year flood. Both flood elevations shall be shown on all site plans.

All sewage pump stations shall be equipped with an alternate power source. Alternate power sources include on-site standby power.

Small package type pump stations or grinder pumps may be approved by the Director of Public Utilities for private pump stations which serve only one site. These pump stations will be allowed only if the flow rate is less than 100 GPM and the force main is less than or equal to 4 inches in diameter. Private pump stations shall meet City and NCDENR-DWQ minimum design criteria. Documentation of future maintenance of both the station and the force main by owner of record shall be required.

B. Site Work

Pump station sites shall be conveyed to the City via deed and/or recordation, as specified by the City. A pump station site layout plan for all pump stations shall be laid out with the City in a separate pre-design meeting at preliminary plan review stage of any development project requesting installation of a pump station. The site layout plan shall require Board approval simultaneous with the preliminary site plan for the development project site.

The site shall be graded generally to drain away from the pump station and to remove stormwater runoff from site in a non-erosive manner.

The site shall be designed to accommodate **both** a WB50 and an SU design vehicle in a traffic pattern as directed by the Director of Public Utilities. In certain instances, remote fill ports may be required.

All components of the pump station shall be surrounded by a concrete slab with minimum HS-20 loading flush with surrounding grade. Concrete slab and hatches shall be HS-20 loading.

Signage shall be provided on the gate which provides the name of the station, its address, and emergency number of 910-892-2948 8am to 5pm Monday-Friday 910-892-2399 5pm-8AM (green lettering on a utility sign).

The site shall consist of a fenced-in hard surfaced area, a gravel vehicular area, plus required landscape buffers. The site shall be stabilized by crushed stone, low maintenance vegetative ground cover or other suitable materials.

The site area shall be secured by a 6-foot high chain link fence topped with 3 strands of barbed wire, or of a material as approved by the Director of Public Utilities. Fence products shall be only new materials using hot dipped galvanized iron or steel components and aluminum coated fence. Gates shall permit 180° opening and shall be located so as to provide vehicle accessibility for lifting the pumping units and any other operational tasks as required. There shall be a minimum gate opening of 12 feet to facilitate truck access. Larger gates may be required to accommodate other design vehicles' turning radii.

A 12-foot (minimum) wide access road to the site with vertical grades not to exceed 10% shall be provided. Access road shall consist of an all-weather surface (minimum of 8" ABC) with minimum 40' long paved strip from roadway. No driveways may be located off of access road. Access road shall be fully contained within a minimum 20 foot wide combined access and utility easement, platted by the Developer. Reduction of width of access road to 10' may be approved at the discretion of the Director of Public Utilities.

The site shall feature locks and security features as dictated by the Public Utilities Department along with all necessary OSHA signage. The site shall feature a minimum high pressure sodium vapor light of 600 watt (minimum) capacity to illuminate the pump station area. The light shall be mounted on a Class V utility pole at a height of 30 feet and controlled by means of a photo cell and an HOA switch located on the light pole, unless otherwise approved by the Director of Public Utilities.

C. Odor Control

Pump stations which shall be maintained by the City of Dunn may be required to incorporate a chemical feed and storage facility for both downstream and proximity odor control purposes. A hydrogen sulfide generation calculation may be required.

Chemical feed facilities should consist of the following at a minimum:

- Double walled liquid chemical storage tanks with a minimum capacity of 2,500 gallons;
- Two Wallace & Tierman Model 44 chemical feed pumps, calibration chambers and valves or a packaged-type chemical feed system with duplex pumps, calibration chamber, in a heated stainless steel chamber;
- A modular building to house tanks and pumps with lights, heater and sump pump may be required;

- A containment system in case of tank or piping failure may be required in addition to a double-walled tank.

The City reserves the right to require mechanical ventilation and treatment of exhaust from the wet well to address anticipated or existing proximity odors.

D. Piping and Valves

Suction and discharge piping shall be minimum Class 50 ductile iron flanged pipe and as manufactured under AWWA Specification C 141. A check valve and a gate valve shall be provided for the discharge pipe of each pump. Check valve shall be iron bodied, fully bronze mounted with bronze clapper disc and bronze seat ring, and shall have a weight loaded lever arm capable of being mounted on either side of the valve and rated for 175 psi working pressure. The gate valve shall be hand-wheel operated. Entrance velocity into the pump shall not exceed 5ft/s to prevent vortices from forming and leading to the potential for air entrapment. The invert elevations for incoming sewer lines shall be set to minimize turbulence and prevent a cascading effect.

E. Wet Well

The wet well shall be precast concrete manhole sections conforming to ASTM C-478, latest revision. Extended bases or another foundation shall be used to provide adequate bearing surface if needed. All concrete shall have a minimum 28 day compressive strength of 3,000 psi. The wet well shall be designed to prevent the formation of vortices and the floor shall have a minimum side slope of 1:1 directed to a hopper bottom. Also, buoyancy calculations will be required for the wet well, free of pumps and water, to ensure that the anti-flotation design is adequate.

The manhole sections shall have joints of a durable mastic sealing material and the joints shall be further waterproofed on the outside of the wet well by the application of asphalt, overlapped by a 12 inch wide band of butyl joint wrap, and a finish mopping of asphalt. The interior side of the joints shall be plastered smooth with portland cement grout. The interior of the wet well shall then receive two successive coats of Koppers "Super Service Black," "Duramer", or a suitable coal tar epoxy, with a total dry film thickness of 10 mils. All nicks and scratches shall be touched up in the field before backfilling occurs.

The wet well shall feature a 316 stainless steel or 6063 alloy aluminum screening basket in front of the influent pipe. The basket shall be rectangular in shape and formed from ¼" x 3" bars on 2½ inch centers on a channel or angle frame. Grating, wire mesh, or perforated plates are not acceptable substitutes. Baskets shall be fabricated with cross members and bracing to provide structural stability under full loading. All bolted connections in the wet well shall be made using stainless steel nuts, bolts and washers. Baskets shall be raised and lowered by

means of a stainless steel chain or wire rope with rings. A specially designed hatch shall be provided that will permit the raised basket screen to be maneuvered into or out of the wet well. This access hatch shall be a square hatch of ¼” aluminum, 6063 alloy, and diamond pattern plate with steel hinges on an aluminum frame cast in place in the cover slab.

The wet well shall have a vent made from ductile iron, with flanged joint pipe fittings. An insect screen shall be included at the exposed end of the vent pipe. The insect screen shall be bronze or aluminum.

F. Electrical

Electrical service to all pump stations shall be 3 phase, 240 VAC or 480 VAC. No 208 volt stations are allowed. No open delta services are allowed. If pump motors are over 10 hp, 480 service will be required. The electrical power entrance shall be through a meter base, followed by a NEMA 3R heavy duty, single throw, fusible safety switch with a solid neutral; followed by a NEMA 3R automatic transfer switch as specified herein. All of these electrical components shall be suitably sized to be capable of service with both sewage pumps running.

Provide a minimum of 1 110 volt receptacle to be located at the pump station. All electrical components, including panel, shall be sealed off in accordance with the N.C. Electrical Code requirements for electrical service to gas pumps.

NEMA 3R Enclosure: All outdoor equipment shall be enclosed in be a NEMA Type 3R enclosure of suitable size to house all components. A locking hasp shall be provided in addition to screw clamp type latches. Enclosure shall be fabricated from 14 gauge steel. The top of the enclosure shall serve as a drip shield and the seam-free sides shall prevent rain and sleet from entering. Inner panel shall be made of 12 gauge steel and shall be painted white. The enclosure and interior panel shall be painted with heat fused modified polyester powder, electrostatically applied over a phosphatized base. Enclosure shall be ANSI/ASA 61 grey.

G. Alarm & SCADA

Required on all pump stations. See Director of Public Utilities for these specifications.

H. Generator Sets

Required on all pump stations. See Director of Public Utilities for these specifications. Sound proofing shall be required for every generator. Generator shall operate all components of pump station including pole light.

I. Transfer Switch

Required on all pump stations. See Director of Public Utilities for these specifications.

J. SCADA

Required on all pump stations. See Director of Public Utilities for these specifications.

K. Pump Motor Controls

General: Pump motor control equipment shall be enclosed in a prefabricated modular building as manufactured by Bally, Inc. or approval equal. Minimum size shall be 10'x10'.

1. **Line Terminal Block:** A terminal block shall be furnished with properly sized line lugs to accept the main power source entering the control panel. Load lugs shall be adequate to accept all required load side wiring requirements. All live parts shall be fully shielded.
2. **Motor Circuit Breakers (200-240 VAC):** A properly sized, molded case, thermal magnetic circuit breaker shall be provided for each pump motor. Line and load sides shall be equipped with lugs properly sized for the horsepower and current rating of the motor(s). They shall be attached to mounting brackets which are specifically manufactured for use with the particular circuit breaker. The interrupting rating shall be 10,000 RMS symmetrical amps.
3. **Motor Circuit Breakers (440-480 VAC):** A properly sized, molded case, hydraulic-magnetic circuit breaker shall be provided for each pump motor. Line and load sides shall be provided with lugs properly sized for the horsepower and current rating of the motor(s). The interrupting rating shall be 5,000 RMS symmetrical amps.
4. **Transformer Primary Circuit Breaker (when transformer is required):**
A properly sized, 2 pole, molded case circuit breaker shall be furnished ahead of the control power 120 VAC power transformer for short circuit protection and disconnecting power to the transformer. The circuit breaker shall conform to the standards for the motor circuit breaker(s).
5. **Control Power Transformer (when neutral is not available at job site - standard on 460 VAC):** An industrial quality control transformer shall be furnished to provide control voltage. The transformer shall be sized

with an adequate KVA rating to provide 120 VAC power for all items required in the control and alarm circuits. Transformer shall be protected in its secondary by properly sized fuses and/or circuit breaker(s).

6. **Magnetic Contactors and Overload Relays:** A NEMA-rated across-the-line magnetic contactor shall be furnished for each motor. A separate, panel mounted, 3 overload relay shall be supplied for each motor. Each leg of the overload relay shall be equipped with a properly sized overload heater. Contactor and overload relay shall be properly sized for the required horsepower, voltage and phase. Reduced voltage auto transformer starters will be required for motor sizes over 50 hp or when the power company requires reduced voltage auto transformer starters. Solid state starters will not be allowed.
7. **Elapsed Time Meters:** Six digit, non-resettable elapsed time meters shall be mounted in the control panel enclosure to record the running time of each pump.
8. **Condensation Strip Heater with Thermostat:** A strip heater shall be furnished to prevent condensation within the control panel enclosure. The heater shall be controlled by a panel mounted, adjustable thermostat.
9. **Phase and Voltage Monitor:** A phase failure, reversal and under voltage monitor shall be supplied to prevent the motors from running under low voltage, phase loss, or phase reversal conditions. The monitor will lock out the control circuit until the problem is corrected and the monitor automatically resets.
10. **Lightning Arrestor:** Lightning arrestors shall be provided to protect motors and control equipment from lightning-induced line surges. Lightning arrestors shall be Transient Voltage Surge Suppressors Series 57,000 as manufactured by Leviton or approved equal. Lightning arrestors shall be distribution panel-mount style in a weather tight case with hinged cover. Protection shall be via individual line replaceable modules with hybrid circuitry.
11. **Thru-Door Overload Reset Push Buttons:** Overload reset push buttons shall be provided for each overload relay. Push buttons shall be mounted so that with inner door closed, overload relays may be reset without entering high voltage compartment.
12. **Switches:** Heavy duty industrial grade oil tight switches shall be provided for each pump for "Hands-Off-Automatic" operation selection. All switch components shall be made of corrosion resistant metals and polyesters. Contact blocks shall be made of see-through polycarbonate for simplified inspection of contacts. Cams and strokes shall be Teflon impregnated for

abrasion free service without lubrication. The switches required shall be as follows:

Switch Function (Name Plate)	Voltage
Manual-Off-Automatic	120 VAC

13. **Pilot Lights:** Full voltage heavy duty industrial grade oil tight pilot lights shall be provided. All pilot light components shall be made of corrosion resistant metals and polyesters. An insulated socket shall be furnished to eliminate the possibility of shock during bulb change. Lens shall be made of lexan. The pilot lights required shall be as follows:

Pilot Light Function (Name Plate)	Voltage	Lens Color
Pump 1	120 VAC	green
Pump 2	120 VAC	green

14. **Seal Failure Circuit Test Push Button (illuminated):** Heavy duty industrial grade oil tight push buttons shall be provided for each submersible pump motor. All push button components shall be made of corrosion resistant metals and polyesters. Contact blocks shall be made of see-through polycarbonate for simplified inspection of contacts. An insulated socket shall be furnished to eliminate the possibility of shock during bulb change. Lens shall be made of lexan. The push buttons required shall be as follows:

Pilot Light Function (Name Plate)	Voltage	Lens Color
P1 Seal Fail	120 VAC	amber
P2 Seal Fail	120 VAC	amber

15. **Pump Alternator Circuit (for duplex pump operation):** The electro-mechanical alternator relay shall be of industrial design specifically for use in pump applications. It shall have single pole double throw heavy duty 10 amp silver cadmium oxide contacts enclosed in a transparent cover. The snap action contacts shall transfer when the unit is de-energized. The circuit shall never be closed or opened while current is being conducted. The alternator circuit shall alternate the lead pump position between the pumps and shall allow the lag pump to start in response to a rising water level in the wet well.

16. **Control Relay(s)**: Plug-in control relays with 120 VAC coils shall be provided as required. Contact rating shall be 5 amps (minimum). Sockets shall be of the same manufacture as the relays.
17. **High Wet Well Level Alarm**: The control panel shall be provided with a suitable alarm circuit, activated by a separate level control. This alarm shall signal a high water condition in the sump. Terminals shall be furnished in the control panel for connection of an externally mounted alarm device. A red flashing light and audible alarm shall be provided as a visual alarm of the high water condition in the wet well. The alarm light must be visible from a public road.
18. **Gauge Kit**: Each pump shall be equipped with a glycerin-filled compound gauge to monitor suction pressures, and a glycerin-filled pressure gauge to monitor discharge pressures. Gauges shall be a minimum of 4 inches in diameter, and shall be graduated in feet water column. Rated accuracy shall be 1 percent of full scale reading. Compound gauges shall be graduated .34 to 34 feet water column minimum. Pressure gauges shall be graduated 0 to 140 feet column minimum.

Gauges shall be mounted on a resilient panel and frame assembly which shall be firmly secured to pumps or piping. Gauge installations shall be complete with all hoses and fittings, and shall include a shutoff valve installed in each gauge line at the point of connection to suction and discharge pipes.

19. **External Alarms**: Lift station manufacturer shall furnish a 115-volt, AC single projector, vibrating type horn with weatherproof housing. Housing shall be equipped with mounting lugs and conduit tap. The Contractor shall mount, wire, and run conduit to the horn as shown on the plans. Wiring shall be connected to the appropriate terminal blocks in the motor control center as shown on the lift station wiring schematic.

The pump station shall be supplied with one 115-volt AC alarm light in a vapor-tight fixture with red globe, guard, conduit box, and mounting fixtures. Alarm light and mounting fixtures shall be designed to permit mounting in such a manner that rainwater cannot stand or collect in the gasketed area of the fixture, between the base and globe.

20. **Level Control System**: The level control system shall start and stop the pump motors in response to changes in wet well level, as set forth herein.

The level control system shall be capable of operating with a submersible transducer type system to monitor wetwell liquid level, as specified below,

with float continuous for back-up. A float back up system shall also be included.

The level control system shall be designed to accomplish the following tasks. That device, or group of devices, that perform these tasks shall hereafter be referred to as the level controller.

1. Continuously monitor the level of liquid in the wet well.
2. Start and stop the pumps as required by the level of liquid in the wet well.
3. Select the operation of one pump or both pumps.
4. Select the sequence of pump operation upon generator command for automatic alternation.
5. Provide alarm indications upon occurrence of predetermined malfunctions.
6. Upon restoration of utility power after a power outage, the system shall delay the application of power to the lag pump by a length of time that has been pre-selected by the operator.
7. Shut down a pump motor when the temperature of that pump reaches a level which could cause pump damage.

The level controller shall continuously monitor the wet well level, permitting the operator to read wet well level at any time.

1. Upon operator selection of automatic operation, the level controller shall start the motor for one pump when the liquid level in the wet well rises to the "lead pump start level". When the liquid is lowered to the "lead pump stop level", the level controller shall stop this pump. These actions shall constitute one pumping cycle.
2. Should the wet well level continue to rise, the level controller shall start the second pump when the liquid reaches the "lag pump start level" so that both pumps are operating.
3. Upon operator selection of automatic alternation, the level controller shall select first one pump, then the second pump, to run as lead pump for a pumping cycle. Alternation shall occur at the end of the pumping cycle.

The electronic pressure switch shall include integral components to perform all pressure sensing, signal conditioning, EMI and RFI suppression, DC power supply and 120V outputs. Comparators shall be solid state, and shall be integrated with other components to perform as described below. The electronic pressure switch shall be capable of operating on a supply voltage of 108V to 132V AC 60 Hertz, in an ambient temperature range of -18°C (0°F) through +55°C (131°F). Control range shall be 0 to 20.0 feet of water with an overall repeat accuracy of ± 0.1 feet of water. The electronic pressure switch shall consist of the

following integral components: pressure sensor, display, electronic comparators, and output relays.

1. The pressure sensor shall be a strain gauge transducer and shall receive an input pressure from the air bubbler system. The transducer shall convert the input to a proportional electrical signal for distribution to the display and electronic comparators. The transducer output shall be filtered to prevent control response to level pulsations or surges. The transducer range shall be 0 - 15 PSI, temperature compensated from -40°C (-40°F) through +85°C (+185°F), with a repeat accuracy of $\pm 0.25\%$ full scale about a fixed temperature. Transducer overpressure rating shall be 3 times full scale.
2. The electronic pressure switch shall incorporate a digital panel meter which, upon operator selection, shall display liquid level in the wet well, and the preset start and stop level for both lead and lag pump. The meter shall be a 3 1/2 digit display calibrated to read out directly in feet of water, accurate to within one-tenth foot (0.1 foot), with a full scale indication of not less than 20 feet.
3. Level adjustments shall be electronic comparator setpoints to control the levels at which the lead and lag pumps start and stop. Each of the level settings shall be adjustable, and accessible to the operator without opening the control panel or any cover panel on the electronic pressure switch.
4. Each output relay in the electronic pressure switch shall be solid state. Each relay input shall be optically isolated from its output and shall incorporate zero crossover switching to provide high immunity to electrical noise. The ON state of each relay shall be indicated by illumination of a light emitting diode. The output of each relay shall be individually fused providing fused overload and short circuit protection. Each output relay shall have an inductive load rating equivalent to one NEMA size 4 contactor. A pilot relay shall be incorporated for loads greater than a size 4 contactor.
5. Each electronic pressure switch shall be subject to a severe environmental test to minimize field failures. The test shall include but is not be limited to a vibration test, exposure to elevated temperatures, and a burn-in under load. Further testing may be conducted at the manufacturer's discretion.
6. The electronic pressure switch shall be equipped with replaceable plug-in integrated circuits and output fuses. The main circuit board assembly shall be provided with keyed plug-in connections to "off-board" components permitting main board removal without de-soldering. All printed circuits shall have a conformal coating applied to both sides to protect against moisture of fungus.

Circuit design in which application of power to the lag pump motor starter is contingent upon completion of the lead pump circuit shall not be acceptable.

High Water With Alarm Silence:

1. The electronic pressure switch shall be equipped with an additional electronic comparator and solid state output relay to alert maintenance personnel to a high liquid level in the wet well. In the event that the wet well liquid reaches a preset high water alarm level, the solid state output shall energize a high water alarm relay and an indicating light visible on the front of the control panel. The high water alarm relay shall be equipped with (1) SPDT dry contact. Two 115 VAC alarm circuits shall also be supplied which may be used to energize field connected alarm devices. The high water alarm relay shall remain energized until the wet well has been lowered and the circuit has been manually reset.
2. An alarm silence pushbutton and relay shall be provided to permit maintenance personnel to de-energize one of the 115 VAC alarm circuits while corrective actions are underway. The high water alarm indicator, dry contacts and remaining 115 VAC alarm circuit shall be maintained in the alarm condition. Depressing the alarm silence pushbutton shall also cause the high water alarm circuit to reset when the wet well has been lowered.

Submersible Transducer System

1. The level control system shall utilize a submersible transducer. It shall be a strain gauge transducer with a pressure sensor housed in a 316 SST or Titanium case designed to extend into the wet well.
 2. The pressure transducer shall provide a proportional signal for distribution to the display and electronic comparators of the electronic pressure switch, and remainder of the level control system. Sensor range shall be 0-12 feet water column minimum, with an over-pressure rating 3 times full scale.
 3. The transducer shall have output capability of 1.5-7.5 VDC or 4-20mA. The transducer's polyurethane jacketed shielded cable shall be of suitable length for proper installation into the wet well without splicing.
21. **High Temperature Shutdown Circuit(s):** The high pump motor temperature circuit shall provide terminals for connection of the leads from the temperature sensor provided in the pump motor windings. Upon a high temperature condition in the pump windings, the control power to the pump motor contactor shall be disconnected, thus stopping the pump motor. The pump shall automatically restart when the pump motor temperature returns to an acceptable level.

22. **Ground Lug(s):** Equipment ground lug(s) shall be provided for grounding the enclosure. The ground lug(s) shall be suitable for the service provided to the enclosure and shall be sized per table 250-95 of the N.E.C. In all cases the enclosure must be adequately grounded per article 250 of the N.E.C.
23. **Terminals:** Terminals shall be provided for connecting mercury float switch leads, temperature sensor and seal fail sensor leads. Terminal blocks shall be rated for 600 volt use and accept a wire range of #22-8. All live parts shall be fully shielded. Block shall be constructed of nylon and have insulating walls on all sides of the lug. Blocks must be UL recognized.
24. **Construction Standards:** Subpanel shall be drilled and tapped to accept machine thread bolts (self tapping screws are not acceptable). All control wiring shall be 16 AWG machine tool wire, Carol type 76512 or equal. All control wire shall be color coded or numbered in accordance with JIC standards. Power (motor) wiring shall be in accordance with the most recent National Electrical Code. Major groups of wires shall be contained in a plastic wiring trough such as Panduit type E or other approved equal.
25. **Guarantee:** The manufacturer of the control panel shall furnish a warranty for one year from the date of installation stipulating that all equipment shall be free from defects in design, materials, and workmanship. The control panel manufacturer shall furnish replacement parts for any component proven defective, whether of his or other manufacture during the guarantee period, excepting only those items which are normally consumed in service, such as light bulbs.

L. Force Main

Force main shall be as specified as Section 7.02. All PVC force mains shall have detector tape installed a maximum of 2 feet below the ground and over the force main. The detector tape shall be a 3-inch wide tape marked "Sewage Force Main" as manufactured by Allen or approved equal. The pipe shall have "sewer" designated on each joint. Locator devices as manufactured by 3M Corporation shall be placed directly on top of sewer force mains, along major thoroughfares and cross country installations (and as otherwise directed by Director of Public Utilities) at 100 feet intervals and turn/bends.

M. Water Service

A minimum 1" public water service or well shall be provided to supply water at a minimum flow rate of 5 gpm with a residual pressure of 30 psi to a yard hydrant located on the pump station site. A City water meter and an above-ground RPZ in a heated hot box shall be required.

N. Landscaping and Appearance

Buffers shall be provided along both sides of the access road and surrounding the gravel vehicular area of the pump station site. Buffers shall extend 50 feet in all four directions from the required gravel vehicular area, plus a 10 foot buffer along both sides of the 20 foot access easement, and shall be included within the site dedicated to the City for the station. Buffers shall either be supplemented to be equivalent to or planted with an opaque buffer.

Color of crane shall be determined by the City.

The City shall reserve the right to establish other appearance requirements.

Buffers shall be maintained by the developer for two years from date of final (end of year) acceptance of pump station.

O. Warranties and Documentation

Warranties: In addition to the City's required standard one year workmanship and materials warranty, the following shall apply. The developer shall warrant all pump station equipment for one year from the date of beginning of one year warranty of the pump station, as identified in the Letter of Acceptance for the pump station. The City reserves the right to make necessary emergency repairs and/or perform work necessary in emergency situations within this warranty period. The developer shall be responsible for reimbursement costs associated with any such work. If a non-emergency repair or other work becomes necessary within the warranty period, the City shall provide written notice to the Owner of need for such work. If the work is not completed within the time frame specified in the written notice, the City shall undertake the work and the developer shall be responsible for reimbursing those costs.

Pre-Construction Documentation: The following information shall be provided to the City (for both Development projects and City – funded projects) for review and approval by the City prior to construction of the pump station. This review and approval shall not relieve the design engineer from the responsibility of insuring that the project meets all City standards:

- Shop Drawings for:
 - pumps
 - jib crane
 - generator
 - control panel
 - modular building
 - odor control
 - check valves
 - Other components as directed by the Director of Public Utilities

Pre-Start Up Documentation: The following documentation shall be supplied to the Director of Public Utilities **prior** to the Operational or “start-up” test for the pump station, and must be submitted in a complete package labeled Operation and Maintenance Manuals that is signed and sealed by the design engineer.

1. Cover Sheet listing the following: Pump manufacturer; source of repair parts, complete with address and phone number; operating conditions - rated capacity and TDH of each pump; model number, serial number, impeller diameter of each pump; all data plate information from each pump motor; data on all other equipment included as components in the pump station;
2. Pump Performance Design Curve with operating conditions indicated on it; also manufacturer’s (factory) Certified Pump Curve for each pump.
3. Detailed dimensional drawings of the pump and pump base elbow;
4. Detailed dimensional drawings of the pump motor;
5. A control panel wiring diagram;
6. Pump and Motor Installation and Service Manual and specific pump parts list with part numbers.
7. Detailed information related to other components of the pump station, including but not limited to: control panel, alarm dialer, generator;
8. As-Builts;
9. P.E. certification;
10. Warranty letter;
11. Recorded access easement and/or right of way documentation.
12. Documentation of recorded site and access easement dedication to City.

P. Testing and Inspection

Hydrostatic Testing of Force Main: The force main shall be completely filled with water, all air shall be expelled from the pipe, and the discharge end of the pipeline shall be plugged and adequately blocked before the hydrostatic test begins.

The force main shall be tested to a pressure of 200 psi or 3 times the rated Total Dynamic Head of the pumps in psi, whichever is larger, as measured at the lowest elevation of the pipeline, for a duration of 2 hours. The pressure gauge used in the hydrostatic test shall be calibrated in increments of 10 psi or less. At the end of the test period, the leakage shall be measured with an accurate water meter.

PIPE SIZE ALLOWABLE LEAKAGE	
Pipe size (inches)	Leakage per 1000 feet of pipe (gallons)
4	0.73
6	1.11
8	1.47
12	2.21
16	2.94
20	3.68
24	4.41
30	5.52
36	6.62

All visible leaks are to be repaired regardless of the amount of leakage.

Operational Test: A full operational test is required in conjunction with the punch list inspection before the pump station can be accepted by the City of Dunn for routine maintenance. The City of Dunn Field Inspection Test and Report (at end of Section 7.00) shall be completed during the test. The wet well shall be thoroughly cleaned to remove dirt, mud, gravel, and other foreign debris. The force main must be full and the wet well must be full to the high water alarm mark. The operational test shall check the proper functioning of the pumps, pump controls, and other pump station equipment. The pump and motor serial numbers shall be verified. All components of the pump station shall be checked to ensure that they are capable of performing the service intended. Contractor shall pull and reset both pumps in the presence of City staff before approval of the guide rail system. The operational test shall be performed by the City of Dunn. The Contractor or Developer shall ensure that a representative from the various pump station equipment manufacturers are present at the operational test to review proper operation of the equipment with the City of Dunn personnel.

Contractor's Responsibility: The Contractor shall furnish all materials, labor, and equipment to perform all testing. The Contractor shall coordinate with the City of Dunn for the use of water for testing. Contractor shall submit 3 copies of Operation and Maintenance (O&M) Manuals to the City.

Q. Davit Crane

1.01 SECTION INCLUDES

- A. This section covers light to medium duty davit cranes for permanent or portable applications.

1.02 REFERENCES

- A. American Institute of Steel Construction (AISC) – Manual of Steel Construction, Part 5, Specifications for Structural Joints Using ASTM A325 or ASTM A490 Bolts
- B. ASTM International (ASTM):
 - 1. ASTM A36 – Carbon Structural Steel
 - 2. ASTM A325 – Structural Bolts, Steel, Heated Treated, 120/150 ksi Minimum Tensile Strength
 - 3. ASTM A490 – Structural Bolts, Alloy Steel, Heat Treated, 150 ksi Minimum Tensile Strength
- C. American Welding Society (AWS) D1.1 – Structural Welding Code
- D. Occupational Safety and Health Administration (OSHA) – Specification 1910.179 – Overhead and Gantry Cranes.
- E. Quality Assurance: manufacturer shall be registered ISO 9001:2000 compliant with an independent certification agency approved by the International Organization for Standardization.

1.03 SUBMITTALS

- A. Submit under provisions of Section 01 30 10
- B. Product Data: Manufacturer’s data sheets on each product to be used, including:
 - 1. Describe capacities, performance, operation, and applied forces to foundation
 - 2. Preparation instruction and recommendations
 - 3. Storage and handling requirements and recommendations
 - 4. Installation methods
- C. Shop Drawings:
 - 1. Shop drawings showing configuration, dimensions, service area, and construction and installation details.

1.04 QUALITY ASSURANCE

- A. Manufacturer shall have a minimum of 5 years’ experience producing substantially similar equipment.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Store in manufacturer’s unopened packaging until ready for installation.
- B. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.

1.06 PROJECT CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommend by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

1.07 WARRANTY

- A. Manufacturer's Warranty: On manufacturer's standard form, in which manufacturer agrees to repair or replace assemblies and components that fail in materials and workmanship within warranty period from date of Substantial Completion.
 - 1. 5 year warranty for crane products to cover defects in material and workmanship.

PART 2 – PRODUCTS

2.01 DAVIT CRANE

- A. Davit crane shall be as manufactured by Thern, Inc., Columbia, or approved equal.
- B. Design Factor shall be greater than 2.6:1 for all components including the lifting winch and base.
- C. Hook Height shall be fixed or adjustable by moving the boom up or down between 0 and 40 degrees above horizontal, with a minimum of ____ inches between the lowest position and the highest position with the boom fully extended. (Height to be determined by Design Engineer)
- D. Boom Angle shall be adjustable with a hand operated screw jack acting to raise or lower the boom between 0 and 40 degrees above horizontal.
- E. Wire rope shall pass over a sheave at the end of the boom. Sheave shall have a bronze bearing.
- F. Minimum height of the boom shall be ____ inches between mounting surface and the underside of the boom in all base configurations. (Height to be determined by Design Engineer)
- G. Boom and outer mast shall rotate 360 degrees on sleeve bearings with a rotational handle attached to outer mast to facilitate rotation. Outer mast shall lock in one of 30 degree incremental positions with locking pin. Rotational stop option shall limit rotation in 30 degree increments.
- H. Crane components shall be fastened together using stainless steel clevis style pins.
- I. Davit crane shall be labeled with a non-corrosive metal identification plate labeled or imprinted with the manufacturer's name, model number, serial number, capacity rating, and other essential information.
- J. Crane base shall be fabricated from heavy gauge steel with predrilled mounting holes
- N. Crane base shall allow for removal of the mast.

2.02 FINISH

A. STANDARD MODELS

1. Crane boom, mast, and base shall be fabricated from stainless steel.
- B. Manual Lifting Winch: winch shall have machine cut gears, an adjustable handle that mounts securely to the drive shaft, bronze and radial ball bearings, and a positive load holding Weston style brake able to stop and hold the load automatically if the winch handle is released.

2.03 WIRE ROPE

- A. Wire rope construction shall be minimum 5/16" type 304 stainless steel.
- B. Latch type hooks shall be used and shall be either non-rotating eye type or swivel type to allow 360 degrees rotation under all load conditions. Hooks shall be heat treated drop forged type 304/316 stainless steel.

PART 3 – EXECUTION

3.01 EXAMINATION

- A. Do not begin installation until support structures have been properly prepared.
- B. Design and construction of reinforced concrete footings and slabs as detailed on Drawings and specified in other sections. Verify that accurate crane applied forces and anchor bolt patterns are provided for foundation design.

3.02 INSTALLATION

- A. Install units and accessories in accordance with manufacturer's instructions and approved shop drawings.
- B. Do not modify crane components in any manner without advance written approval by crane manufacturer
- C. Clearances for moving crane components:
1. 3 inches (76 mm) minimum vertical clearance from any overhead obstruction
 2. 2 inches (51 mm) minimum horizontal clearance from any lateral obstruction

3.03 FIELD QUALITY CONTROL

- A. Perform field quality control testing as recommended by manufacturer
- B. Move through entire travel to ensure crane is clear of obstructions and moves freely and smoothly
- C. Inspect installed crane. Verify all bolts are tight and lock washers fully compressed.
- D. Field test crane and accessories for operating functions. Ensure crane movement is smooth and proper. Adjust as required and correct deficiencies.
- E. Clean surfaces. If necessary, touch-up paint damage, scratches, and blemishes with manufacturer provided matching paint.
- F. Protect crane from other construction operations.

3.04 DEMONSTRATING AND TRAINING

- A. Provide demonstration and training session for Owner’s representative covering operation and maintenance.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

3.05 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION 41 22 13.21

R. Fences and Gates

PART 1 - GENERAL

1.01 SCOPE

- A. The Contractor shall provide a commercial grade security chain link fence where indicated and as configured on the Construction Plans and specified herein.

PART 2 - MATERIALS

2.01 FABRIC

- A. Fabric shall be composed of No. 9 gauge wire woven in a two-inch mesh galvanized by the hot dip process after weaving. Top and bottom selvages shall have a twisted and barbed finished. Barbing shall be done by cutting wire on a bias. Wire pickets of which the fabric is made shall have a tensile strength of not less than 90,000 pounds per square inch based on the cross-sectional area of the galvanized wire.
- B. The fabric shall withstand a galvanizing test of six one-minute immersions under the Preece Test. The test shall be made on a wire picket at least four inches long so as to include at least one bend and one Line posts, end posts and corner posts, shall be hot dip galvanized pipe tubing. Posts shall be sized based on fabric height as follows:

<u>Fabric Height</u>	<u>Line Post 8' Spacing</u>	<u>End Post & Corner Post</u>
4' to 6'	2" OD	2-1/2" OD
7' to 9'	2-1/2" OD	3" OD
10'-12'	3" OD	4" OD
over 12'	4" OD	4" OD

- C. Gate posts shall be hot dipped galvanized pipe tubing and shall be sized based on gate leaf width as follows:

<u>Gate Leaf Size</u>	<u>Gate Post</u>
6' or less	3" OD

6' to 12'	3" OD
12' to 20'	4" OD
20' to 24'	6-5/8" OD
over 24'	8-5/8" OD

- D. Top rail shall be hot dip galvanized pipe tubing, provided with couplings approximately every twenty feet. Couplings shall be outside sleeve type and at least seven inches long, one coupling in every five to have a heavy spring to take up expansion and contraction of top rail. The top rail shall pass through base of line post tops and form a continuous brace from end to end of each stretch of fence. The top rail shall be securely fastened to terminal posts by pressed steel connections. Rails shall be sized based on fabric height as follows:

<u>Fabric Height</u>	<u>Top, Middle & Bottom Rails</u>
4' to 6'	1-5/8" OD
7' to 9'	1-5/8" OD
10' to 12'	2" OD
over 12"	2" OD

2.02 ACCESSORIES

- A. Braces shall be hot dip galvanized and of the same size and material as the top rail. Braces shall be spaced midway between top rail and ground, and shall extend from terminal post to first adjacent line post. Braces shall be securely fastened to posts by suitable pressed steel connections, then trussed from line post back to terminal post with 3/8 inch round rods.
- B. All fittings shall be hot dip galvanized and shall be made of malleable cast iron or pressed steel.
- C. Extension arms shall be hot dip galvanized. Line post arms shall be of pressed steel; end and corner post arms of malleable iron or pressed steel; gate posts to have ball top. Each arm shall be suitable for carrying barbed wire at an angle of forty-five degrees.
1. Three lines of four-point pattern barbed wire, spaced not more than 3" on center, shall be provided as shown on the details. Each line shall be composed of two strands of No. 11 gauge wire, galvanized after weaving.
 2. The top most barbed wire shall be approximately twelve inches above the fabric and approximately twelve inches out from fence line. Barbed wires shall be securely fastened in slots by heavy wire pins. Arms having projections to be bent down over barbed wire will not be acceptable.
- D. Where indicated on the plans or in the Contract Documents, privacy slats shall be installed. Slats shall be DuraSlatt, as manufactured by FRP Systems, Inc., PDS Fence Products, or approved equal.
1. Slats shall be fabricated from a durable, semi-rigid fiberglass reinforced plastic composed of glass fiber reinforcements, high quality polyester

resins, pigments, and fillers. Strips are to be 0.06" nominal thickness, 1.75" nominal width (suitable for 9 gauge. 2" chain-link mesh), and appropriate length for the fence height.

2. The strips shall be installed diagonally, as per manufacturer's recommendations and are to be securely in the fence by means of aluminum pop rivets. Color of slats shall be as selected by Owner from the manufacturers standard color set.

2.03 COLOR COATING SYSTEMS

- A. Where indicated on the plans or in the Contract Documents, a vinyl coated fencing system shall be installed. All other provisions of this section shall apply with the following modifications.
- B. The fabric shall be vinyl coated with a material meeting ASTM F668-99a specifications for Class 2a PVC coating. The PVC coating shall be extruded and bonded over hot dip galvanized steel wire. Core wire shall be minimum 11 gauge, and finished vinyl coated fabric shall be minimum 8 gauge. Fabric shall be woven after vinyl coating is applied. Color shall be as selected by Owner from the manufacturers standard color selection.
- C. All framework shall be either vinyl coated or polyester powder coated. Coated framework shall meet applicable sections of ASTM F1043 and/or ASTM F1234-93 specifications. Framework shall be hot dip galvanized prior to application of either coating. The framework shall have a minimum 10 mil vinyl coating, or a minimum 3 mil polyester powder coating. Fittings and accessories shall also be coated to match framework and fabric.

PART 3 - EXECUTION

3.01 GENERAL

- A. Skilled workman, trained and experienced in the installation of commercial chain link fencing, shall install all fencing components.
- B. All fence corners and gates shall be staked in the field by the Contractor and approved by the Engineer prior to fencing installation.
- C. Fencing shall be installed true to line, with posts located at all corners and breaks in grade, with maximum post spacing as shown. Posts shall be installed plumb and set in concrete.
- D. Fabric shall be fastened to line posts with fabric bands spaced approximately fourteen inches apart and to top rail with tie wires spaced approximately twenty-four inches apart.

END OF SECTION 32 31 15

**SECTION 8.00
STORM DRAINAGE**

SUB-INDEX

8.01 STORM DRAINAGE MATERIALS

- A. Pipe Materials
- B. Structure Materials

8.02 STORM SEWERS

- A. Location
- B. Sizing and Design
- C. Installation
- D. Pipe Inlets and Outlets
- E. Street Drainage

8.03 STORMWATER IMPOUNDMENTS

SECTION 8.00

STORM DRAINAGE

8.01 STORM DRAINAGE MATERIALS

A. Pipe Materials

1. **Reinforced Concrete Pipe** shall conform to ASTM C76, Table III or Table IV with a minimum 12-inch inside diameter. Joints shall be sealed with a plastic cement putty meeting Federal Specification SS-S-00210, such as Ram-Nek or a butyl rubber sealant.
2. **Corrugated Steel Pipe or Pipe-Arch** shall have a minimum 12-inch nominal diameter and conform to AASHTO M36 with pipe ends having no less than 2 round corrugations on each end. Bands for connecting pipes shall be corrugated with a minimum of 2 corrugations for each pipe. Pipe shall be fully bituminous coated with an asphalt paved invert in accordance with the requirements of AASHTO M190 for Type C pipe.
3. **ADS N-12 High Density Polyethylene Corrugated Storm Sewer Pipe (for use on private property only)** shall have a minimum 12-inch nominal diameter and shall be used only in areas outside of public right of way. ADS pipe shall not be installed under any pavement or curb and gutter, and shall be installed with Class I or Class II bedding to the spring line of the pipe. Pipe material shall meet the product specifications of ASTM F667 and shall have a smooth interior.

B. Structure Materials

All storm drainage structures such as manholes, inlets, junction boxes and catch basins shall be constructed of either solid brick, solid block, or precast concrete.

1. **Clay Brick** shall be solid, rough, sound clay brick conforming to ASTM C32, Grade MS. The brick shall be laid with full shove joints, filling up the joints with mortar. The thickness of the joints shall not exceed 3/8 of an inch.
2. **Concrete Block** or brick shall be solid and conform to ASTM C139 as to design and manufacture. The block or brick shall be embedded in a mortar bed to form a 1/2-inch mortar joint.
3. **Precast Concrete Manholes** shall conform to ASTM C478 as to design and manufacture. All manhole cones shall be the eccentric type. Manhole

joints shall be sealed with a plastic cement putty meeting Federal Specification SS-S-00210, such as Ram-Nek or a butyl rubber sealant.

4. **Manhole Frames and Covers** shall be cast iron or ductile iron with “Storm Sewer” stamped on the cover and two 1-inch holes. Castings shall be machined to give even and continuous bearing on the full length of the frame. Castings shall be free of porosity and blow holes, and shall receive one coat of Koppers Super Service Bitumastic black paint. Paint shall be kept off of bolt threads, and surfaces shall be thoroughly wire brushed before painting. All manhole rings in roadways shall be installed in accordance with the applicable Standard Detail in the Standard Details Section of these Standards.
5. **Manhole Steps** shall be of polypropylene material reinforced with a ½-inch diameter reinforcing rod. They shall be designed for a vertical load of 400 pounds and a horizontal pullout load of 1,000 pounds, and shall be set 16 inches on center. Holes for the installation of manhole steps shall not project through the manhole wall, but shall stop a minimum of 1 inch from the outside wall. Steps shall be at least 10 inches clear width and shall project at least 4 inches from the wall into which they are embedded. Steps in precast concrete structures shall be installed by the manufacturer.
6. **Catch Basins** (curb inlets) for street drainage shall be in accordance with NCDOT Standard Details. Precast concrete boxes are allowed, but precast manholes are not acceptable for use as catch basins.
7. **Headwalls and Endwalls** may be cast in place per NCDOT Standard Details, or precast with wing walls and apron by an approved manufacturer. Precast headwalls and endwalls shall require approval by the City Engineer and shall be installed in accordance with the manufacturer’s recommended installation procedures and specifications.

8.02 STORM SEWERS

A. **Location**

1. All storm sewers that convey public water from street runoff or conveys runoff around a site, shall be installed in a dedicated street right of way or, when outside the right-of-way, in private drainage dedicated easements. Minimum widths of storm sewer easements shall be 20 feet for pipes up to and including 48 inches in diameter, and 30 feet for pipes greater than 48 inches in diameter.

2. See Sections 6.00 and 7.00 of these Standards for horizontal and vertical separation requirements between storm drainage pipe, water lines, and sanitary sewer lines.
3. The City of Dunn shall maintain only the storm sewer systems within City-maintained rights of way and on City-owned property. Storm drainage systems located on private property shall be maintained by the property owner(s). In the event that privately-owned storm drainage systems are not maintained by the property owner, and are causing an emergency situation, the City of Dunn shall take corrective action and back-charge the property owner for all costs associated with the corrective action.
4. Unless prevented by topographic constraints, storm sewer shall not discharge into front yards of lots, but shall extend to within 20 feet of the rear property line in lots up to $\frac{1}{2}$ acre in size and shall extend a minimum of 150 feet from right of way in lots larger than $\frac{1}{2}$ acre.

B. Sizing and Design

1. Storm sewer systems shall be designed on the basis of the 2-year storm for inlet spacing, the 10-year storm for street drainage pipe sizing, the 25-year storm for cross-street drainage, and the 100-year storm for flood plain areas. The City's Engineer may require that the 500 year storm event be used in certain instances. Pipes shall be designed based on $\frac{2}{3}$ flow of a full pipe.
2. Runoff rates shall be calculated by the Rational Method, the SCS Method, or other acceptable procedure. Runoff computations shall be based on rainfall data published by the National Weather Service for this area.
3. For drainage areas less than 2 square miles, the Rational Method is recommended to calculate runoff. For drainage areas greater than 2 square miles, the SCS Method or other recognized method is recommended.
4. Time of concentration (tc) shall be appropriate for the drainage area in question using Kirpich Equation (Bureau of Reclamation, 1974, p. 71).
5. Storm duration shall equal the time of concentration.
6. Storm sewer pipe shall be sized in accordance with the Manning Equation.
7. Storm sewers shall be designed to provide a velocity of at least 2 feet per second at design flow.

8. The minimum pipe diameter shall be 12 inches where the inlet is grated and 15 inches where the inlet is not grated.

C. Installation

1. All storm sewers shall be installed to provide a true line and grade between structures.
2. Structures shall be installed at each deflection of line and/or grade.
3. The maximum length between access points shall be 400 feet for all pipe sizes.
4. No inaccessible storm drainage structures shall be allowed.
5. Pipe may enter through the corner of all structure material types except for precast concrete “waffle” boxes.
6. A reinforced concrete slab, designed by a Professional Engineer, may be used at oversized structures to adjust an inlet to standard horizontal dimensions.
7. The minimum cover for storm sewer pipe shall be 2 feet to finished subgrade under roadways and 1 foot to finished grade in nonload-bearing areas. Trench excavation and backfilling shall be in accordance with Section 5.00 of these standards.
8. Pipe shall not project into a drainage structure but shall be finished flush with the inside of the structure.
9. Catch basins between 5 and 20 feet in depth shall have minimum interior dimensions of 4 feet by 4 feet, and those over 20 feet in depth shall have minimum interior dimensions of 5 feet by 5 feet.
10. Each drainage structure shall have a shaped invert constructed from concrete, and a bench with a maximum 5:1 slope. The bench shall begin at a height of one-half the pipe diameter for 15 to 24-inch pipe, one-third the pipe diameter for 30 to 48-inch pipe, and one-fourth the diameter for pipe greater than 48 inches in diameter.
11. Precast concrete structures may be installed only to depths certified as acceptable by the manufacturer.

D. Pipe Inlets and Outlets

1. Headwalls, endwalls, or flared end sections shall be installed at all inlets and discharge points.
2. Flared end sections shall be installed on single pipe culverts up to and including 60 inches in diameter, and on multiple pipe culverts up to and including 36 inches in diameter.
3. Headwalls and endwalls shall be installed on single or multiple pipe culverts greater than 36 inches in diameter.
4. Precast headwalls shall only be installed at single pipe culverts.
5. Energy dissipaters shall be installed at all discharge points and shall be properly sized to ensure that stormwater is released at a nonerosive velocity. Dissipaters shall be designed to include scour protection.
6. A fabric or washed stone barrier shall be installed between the dissipation pad and the natural ground.
7. Storm drainage channels and ditches shall be designed to carry design flow at nonerosive velocities. Calculations indicating design velocities shall be provided along with typical channel cross-sections. The maximum allowable design velocity in grass channels is 4 feet per second.
8. The City Engineer may require additional information on the impact of stormwater discharge on adjacent properties.

E. Street Drainage

1. Stormwater shall not be allowed to flow across streets at intersections. Drainage structures shall be provided to intercept flow prior to the radius of intersections or the street design shall provide for a continuous grade around the radius to channel flow down the intersecting street.
2. No stormwater inlets shall be placed within travel areas of a roadway.
3. Curb inlets shall be designed to intercept stormwater before the gutter spread exceeds 8 feet for the 2-year storm. In areas of heavy pedestrian traffic, the maximum allowable spread may be decreased by the City Engineer.

8.03 STORMWATER IMPOUNDMENTS

Where there are existing or potential drainage and/or flooding problems downstream as determined by the City Engineer, retention or detention facilities may be required.

The minimum drainage area for retention (wet facilities) is 10 acres. Detention (dry) facilities shall be utilized where the upstream drainage area is less than 10 acres.

In addition, the following guidelines shall be followed when designing wet ponds:

1. Side slopes shall be no steeper than 3:1 and no flatter than 10:1.
2. Both barrel and riser shall be concrete, and the riser shall be located in or near the embankment.
3. The riser inlet shall be covered with a trash rack to prevent clogging.
4. A maintenance access shall be provided via a minimum 10-foot wide gravel road in a minimum 20-foot wide maintenance access easement or public right of way. The road shall be adequate to withstand heavy equipment. The access road shall not cross the emergency spillway, and shall have a maximum slope of 5:1.
5. The design shall include a minimum 20-foot maintenance easement around the perimeter of the basin and dam structure.
6. On-site disposal areas capable of receiving sediment from at least 2 clean-out cycles should be reserved in adjacent open space, if available.
7. The outlet channel shall be protected by an appropriately designed velocity dissipater.
8. The embankment shall allow for a minimum 1-foot freeboard.
9. Anti-seep collars shall be installed around the barrel and a core trench shall be installed under the embankment to key it to the substrate.
10. Retention facilities shall not be used as erosion control devices during construction except as approved by the City Engineer.

For all stormwater impoundments, the City shall receive design calculations including, but not limited to, hydrographs, routing and outlet sizing. The designer and developer shall consider liability in the design and selection of the type of

structure. Plans for all stormwater impoundments must be reviewed and approved by the City's Engineer.

END OF SECTION 8.00

SECTION 9.00
“AS-BUILT” DRAWING REQUIREMENTS

All entities who develop or construct within the City of Dunn shall submit to the City of Dunn Construction Inspector an as-built set of construction drawings as a part of the City’s inspections and/or acceptance process. Initial “review” set shall include 3 sets of 24” x 36” blueprints. Final submittal shall be on 24” x 36” mylar and accompanied by a digital copy of the as built drawings, as specified later in this section. Lettering shall be bold, clear, and a minimum of 1/8” in height. The following items and the signed and sealed Professional Engineers Certification shall be affixed directly to the first sheet of the mylar as-builts:

- As-Built Certification per Item 3 below
- State required water permit PE Certification (if applicable)
- State required sewer permit PE Certification (if applicable)

Attached is the City of Dunn “As-Built Checklist” which lists all information required on as-built, or record drawings. In addition, other specific certifications may be required on some projects.

**City of Dunn
Public Utilities Department**

All entities who construct the following: public waterlines or sewer lines or related facilities, public or private storm drainage or stormwater systems, streets to be publicly or privately maintained, and/or other utilities or structures within public rights-of-way or easements, shall submit to the City of Dunn Department of Public Utilities, an as-built set of post-construction drawings as a part of the City's inspections acceptance process. **As-builts must be submitted prior to acceptance of the improvements or issuance of a Certificate of Occupancy.** The following checklist must be attached to each set of as-builts submitted for approval. Each blank must be initialed by the applicant as being included on the as-builts or marked N/A if not applicable to the project. All plan sheets must be 24" X 36". Lettering shall be bold, clear and a minimum of 1/8" height. In addition, all applicable information listed below must be included on all as-built drawings.

As-Built Checklist

1. AS-BUILT INFORMATION:

Project: _____ **Phase:** _____
Submitted by: _____ **Phone #:** _____

(Please check)

Blue Line for Review only

Mylar or Vellum (Final)

Transmittal Date: _____

2. INFORMATION REQUIRED TO BE ON COVER SHEET: Page # _____

- _____ A. Acreage in total tract
- _____ B. Average lot size
- _____ C. Total number of lots
- _____ D. Total linear footage of infrastructure chart, Page # _____
 - _____ Streets (List individually in lengths)
 - _____ Sidewalk (List individual in lengths)
 - _____ Water mains (Identify lengths by size and material types)
 - _____ Sewer mains (Identify lengths by size and material types)
 - _____ Storm drainage (Identify by size)
 - _____ Number of valves (For each size)
 - _____ Number of fire hydrants
 - _____ Number of manholes
 - _____ Number of Catch basins
 - _____ Other (Any additional appurtenances)
- _____ E. Benchmark Reference information for City's GPS Monumentation grid and/or USGS monuments

3. INFORMATION REQUIRED TO BE ON EACH SHEET OF AS-BUILT PLANS:

- _____ A. The following P.E. Certification is required on each sheet of the as-builts:

<p>I certify that these as-builts are accurate and that each of the items listed on the City's "As-Built Checklist" as contained in the City of Dunn Engineering Design and Construction Standards is provided on this set of as-built drawings (____ total sheets in this set). I certify that all of the information provided is field-verified as-built information.</p>		
(Seal)	Signature Registered Land Surveyor	Date
(Seal)	Signature by Professional Engineer	Date
	Acceptance by Construction Inspector	Date

- _____ B. Statement designating that drawings are "record" and/or "as-built" drawings
 _____ C. Seal and signature of NC registered P.E. or PLS that prepared as-builts

4. OTHER INFORMATION REQUIRED AT THE TIME OF AS-BUILT SUBMITTAL:

- _____ A. Provide a copy of **recorded** plats and/or deeds of easements indicating dedication (per approved plan) all public and private easements and right of ways for the project.

5. GENERAL INFORMATION: Page # _____

- _____ A. Boundary of tract by courses and distance with references
 _____ B. 500 scale vicinity map with site delineated
 _____ C. Scale of drawings and bar scale
 _____ D. North arrow
 _____ E. All easements identified and dimensioned
 _____ F. Tie to N.C. grid coordinate system (NAD1983 State Plane). The closest City of Dunn Geodectic Monument shall be identified in Autocad file with respective elevation grid coordinates, and the combined factor.
 _____ G. As-Built data shall be submitted on a CD and shall include both Autocad dwg/dxf and a scanned pdf copy of all as-built sheets.

6. STREETS (Public or Private) Page # _____

- _____ A. Horizontal alignment with radii, (lengths, P.C. and P.T. stations, tangents, and all other curve information
 _____ B. Vertical alignment with centerline grades, vertical curve lengths, station and elevation of all PVC's and PVT's, and centerline profile
 _____ C. Copies of Maintenance Agreements or Covenants addressing maintenance of any private streets, alleys, streetscaping, private easements, etc.
 _____ D. Areas where road stabilization fabrics or heavier pavement structures are used

7. **STORM DRAINAGE AND ENVIRONMENTAL** Page # _____

- _____ A. Outline of FEMA 500 year flood plain and elevation
- _____ B. Outline of FEMA 100 year flood plain and elevation
- _____ C. Outline of local 100 year flood areas and elevation per City flood plain ordinance
- _____ D. Outline of backwater easements
- _____ E. Elevation of all flood areas and finished floor elevations for adjacent structures on which minimum finished floor elevations were required
- _____ F. Outline of Wetlands Cape Fear Buffers
- _____ G. Pipe materials
- _____ H. ***Structure invert and top elevations***
- _____ I. Pipe size
- _____ J. Pipe slope and distance
- _____ K. Size of riprap dissipation pad
- _____ L. Statement of stormwater velocity at all outlets
- _____ M. Maintenance agreement responsibility statement
- _____ N. Permanent stormwater BMP's with location and associated drainage easements required
- _____ O. Berm elevations and invert/top elevations for associated storm drainage inlets where required on construction drawings

8. **WATER SYSTEM** Page # _____

- _____ A. Pipe material labeled
- _____ B. Pipe size and length labeled
- _____ C. Separation from sanitary and storm sewer shown on plans
- _____ D. Locations with distance references (2 each per appurtenance)
_____ *Valves* _____ *Fire Hydrants* _____ *Blow-offs*
_____ *Meters* _____ *Air release valves*
- _____ E. Certification by N.C.P.E. of construction in accordance with sanitary water extension permit
_____ Certification required on the coversheet of the plans, and
_____ As a separately submitted certification sheet
- _____ F. Location and length of bore and jacks

9. **SANITARY SEWER SYSTEM** Page # _____

- _____ A. Pipe material labeled
- _____ B. Pipe size and length labeled
- _____ C. Manhole top elevations
- _____ D. Invert in and out elevations
- _____ E. Pipe slope
- _____ F. Locations with distance references (2 each appurtenance)
_____ *Clean-outs* _____ *Air release valves*
_____ *Manholes* _____ *Force main valves*
- _____ G. Horizontal control (angles at manholes)
- _____ H. 100 year and 500 year flood plain elevations
- _____ I. Certification by N.C.P.E. of construction in accordance with sanitary sewer extension permit
_____ Certification required on the cover sheet of the plans, and
_____ As a separately submitted certification sheet
- _____ J. Location and length of bore and jacks
- _____ K. Location and elevation of any vents
- _____ L. Areas of special bedding

10. *For items shown above in bold italics, a survey point file of both horizontal (x, y) and vertical (tops and inverts, or Z) information shall be required. X, Y, Z coordinates shall be provided on a CD, tied to NC grid or City monumentation grid, and accompanied by a certification sealed by a registered land surveyor. This information should accompany final submittal of mylar as-builts.*

I certify that the information listed above is provided herein in these as-builts or record drawings.

(Seal)

Registered Land Surveyor

Date

City of Dunn USE ONLY:

As-Builts Received By: _____	Date: _____
As-Builts Reviewed By: _____	Date: _____
(Attached) Comments Generated By: _____	Date: _____
Mylars Received By: _____	Date: _____

END OF SECTION 9.00

**SECTION 10.00
ENVIRONMENTAL**

SUB-INDEX

10.01 GENERAL

10.02 TREE PROTECTION AND PRESERVATION

- A. Tree Protection Fencing**
- B. Combination Silt/Tree Protection Fencing**
- C. Construction Operations**

10.03 INDIVIDUAL LOT REQUIREMENTS

- A. Erosion and Sedimentation Control**
- B. Tree Preservation**

**10.04 UTILITY INSTALLATION ASSOCIATED WITH
ENVIRONMENTALLY SENSITIVE AREAS**

- A. Stream Crossing**

10.01 GENERAL

This chapter contains standards, specifications, techniques and devices required to preserve the natural function of the environment. These techniques and devices are the minimal acceptable for use in the City of Dunn. The use of other techniques and devices is acceptable if adequate measures are provided by the alternative and prior approval is given by the Director of Engineering based on a review of specifications and details for the measure. The designer should also refer to Section 4.00 of these specifications for more Sedimentation & Erosion Control Standards.

10.02 TREE PROTECTION AND PRESERVATION

Tree protection and preservation is required whenever preservation or protection of existing vegetation is required per the City of Dunn Planning Department UDO and other ordinances, policies, etc. Fencing locations shall be shown on preliminary and construction drawings and may be modified in the field with approval of the Inspector.

Trees shall be protected by fencing installed the distance from the trunk of the tree that equals the diameter of the trunk of the tree divided by two and converted into feet or at the drip line of the tree branches; whichever is more stringent. Tree protection fencing shall be installed before any work is done on the site and inspected during the Certificate of Compliance Inspection.

Encroachment into buffer areas must be permitted by the Engineering Department per Section 7.06, D., 4., e Environmental Buffer Areas of the City of Dunn, Unified Development Ordinance and 2003 N.C. Sess. Law ch. 73, § 5.1.

A. Tree Protection Fencing

Standard tree protection fencing shall be used to protect any tree save area including riparian buffers, thoroughfare buffers, open space or areas designated by the Town's Engineering, Planning, or Parks and Recreation Departments. Fencing shall consist of high-visibility orange, UV-resistant high tensile strength poly barricade fabric with 5' steel posts located at a maximum 8' spacing, with minimum 10 gauge line wires. Signage shall be required which states "TREE PROTECTION AREA DO NOT ENTER" along the fencing at 50 foot intervals (maximum), and shall be made out of a durable waterproof material with a minimum of 3" lettering spaced clearly legible in accordance with the standard detail and the approved erosion control plan.

B. Combination Silt/Tree Protection Fencing

Combination temporary silt/tree protection fencing may be used wherever denuded area abuts any tree save area. This measure shall comply with those material and installation criteria specified for silt fence in section 4.03, A. Signage as described above in Section 10.02, A shall also be required in accordance with the standard detail and the approved erosion control plan.

C. Construction Operations in (or adjacent to) Tree Save Areas

When construction operations (including but not limited to cut and fill) cannot be avoided in or near either tree save areas or the drip line of the tree, the following criteria shall be met:

1. No more than 2” of fill may be placed on the roots or around the trunk of a tree.
2. Cut slopes shall be no closer than 3 times the diameter of the tree, and shall not cause removal of more than 25% of the root zone surrounding the tree.
3. No heavy machinery shall be used within the drip line of the tree. Construction equipment shall be limited to small rubber-tired equipment and hand work.
4. Root pruning with instruction by an arborist is required prior to the installation of any permanent structures or excavation that encroaches into the root zone of a tree.
5. All denuded area around the tree must be covered by at least 3” of mulch within 10 days of completion of work around the tree.
6. A 2 (two) year warranty period may be required for all work done in (or adjacent to) a tree save area.

10.03 INDIVIDUAL LOT REQUIREMENTS

A. Erosion and Sedimentation Control

Erosion and Sedimentation Control measures are required on lots that have an active construction in compliance with Section 4.09.

B. Tree Preservation


Tree preservation must take place on all lots with active construction in compliance with 10.02 of this section.


10.04 UTILITY INSTALLATION IN ENVIRONMENTALLY SENSITIVE AREAS

A. Stream Crossing

In areas where utility line installation is proposed to go through an area determined to be environmentally sensitive (such as stream, wetlands and/or floodplain) the following items shall be incorporated into design and construction in order to minimize adverse impacts to the area. Permits from regulatory agencies with jurisdiction, site specific erosion control devices (diversions, pumping, removal of fill, stabilization, etc.), a detailed construction sequence for the specific utility crossing, special techniques as required, and a special preconstruction meeting prior to starting the work. At the end of each work day, until completion, the site shall have appropriate erosion control measures installed to prevent damage from sedimentation and all channels must be restored to have positive flow. Once work has started, it must be completed in the shortest timeframe possible.

END OF SECTION 10.00





MAJOR STREET W/ CURB & GUTTER

NO ON-STREET PARKING



CITY OF DUNN
NORTH CAROLINA
Department of Public Works

Revised: 3/09/22

Scale: NTS



300.01

Sheet 1 of 1




COLLECTOR STREET
 WITH CURB & GUTTER
 CITY of DUNN
 NORTH CAROLINA
 Department of Public Works


Revised: 3/09/22
Scale: NTS
300.02
Sheet 1 of 1



SUB-COLLECTOR STREET WITH CURB & GUTTER
 NO ON-STREET PARKING
 CITY of DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 3/09/22
Scale: NTS
300.03
Sheet 1 of 1





MINOR STREET WITH CURB & GUTTER

NO ON-STREET PARKING


CITY of DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 3/09/22

Scale: NTS

300.05

Sheet 1 of 1



NOTE:
ALLEYS ARE PROHIBITED IN
RESIDENTIAL BLOCKS UNLESS
APPROVED BY THE PLANNING
BOARD





ALLEY (PRIVATE OR PUBLIC)
16' PAVEMENT / 20' RIGHT-OF-WAY
CITY of DUNN
NORTH CAROLINA
Department of Public Works


Revised: 3/22/22
Scale: NTS

300.06


Sheet 1 of 1









18" MOUNTABLE CURB & GUTTER




30" CURB & GUTTER



30" ROLLED CURB & GUTTER




24" CURB & GUTTER




36" OR 48" VALLEY GUTTER

NOTES:



USE NON-REINFORCED, AIR ENTRAINED, CONCRETE WITH A MINIMUM STRENGTH OF 3000 LBS.




COMMERCIAL DRIVEWAY



STANDARD DRIVEWAY




ALTERNATE DRIVEWAY






NOTES:

1. CURB AND GUTTER SECTION WILL BE POURED CONTINUOUS THROUGH THE STANDARD AND ALTERNATE DRIVEWAY WITH THE FACE OF CURB DROPPED DOWN AS SHOWN.
2. DRIVEWAY WILL BE CONSTRUCTED AFTER THE CURB FORMS HAVE BEEN REMOVED.
3. CONCRETE SHALL BE NON-REINFORCED, AIR-ENTRAINED WITH A MINIMUM STRENGTH OF 3000 LBS.




- NOTE:
1. SIDEWALK WILL BE REQUIRED AS DETERMINED BY THE CITY OF DUNN / PLANNING BOARD.
 2. SIDEWALK SHALL HAVE EXPANSION JOINTS EVERY 30' AND FALSE JOINTS EVERY 10'.







NOTE:
 COORDINATE PLACEMENT OF CROSSWALKS
 IN ALL CASES WITH THE LOCATION OF
 WHEELCHAIR RAMPS



ISOMETRIC VIEW



W	A	W+A+9	X	B
5'	0.0'	5.8'	5.8'	5.0'*
6'	0.0'	6.8'	6.8'	6.0'**
7'	0.0'	7.8'	7.3'	6.5'**
8'	0.0'	8.8'	7.3'	6.5'**
5'	2.0'	7.8'	7.8'	5.0'
5'	2.5'	8.3'	8.1'	4.8'
5'	3.0'	8.8'	8.3'	4.4'
5'	3.5'	9.3'	8.4'	4.1'
5'	4.0'	9.8'	8.6'	3.8'
5'	4.5'	10.3'	8.7'	3.4'
5'	5.0'	10.8'	8.9'	3.1'

B = X - (A + 9")
 B = DISTANCE FROM FRONT EDGE OF SIDEWALK TO BACK POINT OF 12:1 (8.33%) SLOPE.
 * BACK OF SIDEWALK DROP REQUIRED FOR ALL SIDEWALK SLOPES.
 ** BACK OF SIDEWALK DROP REQUIRED FOR SIDEWALK SLOPES 0.04.

CAST-IN-PLACE DETECTABLE/TACTILE WARNING SURFACE NOTES:
 A. FOR DETAILS ON DETECTABLE WARNING SURFACE, SEE SHEET 5.
 B. SURFACE SHALL BE MADE OF VITRIFIED POLYMER COMPOSITE (VPC).
 C. DETECTABLE WARNING SURFACE SHALL BE MANUFACTURED BY ENGINEERED PLASTICS, INC., WILLIAMSVILLE, NY, BRAND NAME- ARMOR-TILE™, OR AN APPROVED EQUAL AVAILABLE AT (336) 992-0237.
 D. COLOR OF TILE SHALL BE STANDARD BRICK RED (FEDERAL COLOR NO. 22144).
 E. INSTALLATION OF THE TILE SHALL BE ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS, AND A PRINTED COPY (IN THE APPROPRIATE LANGUAGE) OF THE INSTRUCTIONS SHALL BE ON THE JOB SITE DURING THE INSTALLATION.




**WHEELCHAIR/HANDICAP RAMP
 WITH DETECTABLE WARNING SURFACE**

CITY of DUNN
 NORTH CAROLINA
 Department of Public Works


Revised: 1/28/11
 Scale: NTS

300.14




Sheet 1 of 5



DETAIL SHOWING TYPICAL LOCATION OF WHEELCHAIR RAMPS, PEDESTRIAN CROSSWALKS AND STOP LINES FOR TEE INTERSECTIONS




DETAIL SHOWING TYPICAL LOCATION OF WHEELCHAIR RAMPS, PEDESTRIAN CROSSWALKS AND STOP LINES




ALLOWABLE LOCATIONS
DUAL RAMP RADII.....ANY

NOTE: A PORTION OF ONE OR BOTH RAMPS MAY EXTEND OUTSIDE THE RETURN.



PLAN VIEW

DUAL RAMPS
ANY RADII
(40" MIN. FLOOR WIDTH)



PLAN VIEW
DIAGONAL RAMP

NOTES:
SEE CITY STD. #511 SHEET 4 OF 5.
REFER TO NOTES 2, 12, 13, & 17
FOR ADDITIONAL INFORMATION ON
CROSSWALKS.

A PORTION OF RAMP MAY EXTEND
OUTSIDE THE RETURN.

* DIAGONAL RAMP MAX. 25' RADII
WITH 5'-0" MIN. FLOOR WIDTH.

NOTES:

1. CONSTRUCT THE WALKING SURFACE WITH A SLIP RESISTANCE, AND A 70% CONTRASTING COLOR TO THE SIDEWALK.
2. CROSSWALK WIDTHS AND CONFIGURATION VARY, BUT MUST CONFORM TO TRAFFIC DESIGN STANDARDS.
3. NORTH CAROLINA GENERAL STATUE 136-44.14 REQUIRES THAT ALL STREET CURBS BEING CONSTRUCTED OR RECONSTRUCTED FOR MAINTENANCE PROCEDURES, TRAFFIC OPERATIONS, REPAIRS, CORRECTION OF UTILITIES OR ALTERED FOR ANY REASON AFTER SEPTEMBER 1, 1973 SHALL PROVIDE WHEELCHAIR RAMPS FOR THE PHYSICALLY DISABLED AT ALL INTERSECTIONS WHERE BOTH CURB AND GUTTER AND SIDEWALKS ARE PROVIDED AND AT ALL OTHER POINTS OF PEDESTRIAN FLOW. IN ADDITION, SECTION 228 OF THE 1973 FEDERAL AID HIGHWAY SAFETY ACT REQUIRES PROVISION OF CURB RAMPS ON ANY CURB CONSTRUCTION AFTER JULY 1, 1978 WHETHER A SIDEWALK IS PROPOSED INITIALLY OR IS PLANNED FOR A FUTURE DATE.
THE AMERICANS WITH DISABILITIES ACT (ADA) OF 1990 EXTENDS TO INDIVIDUALS WITH DISABILITIES. COMPREHENSIVE CIVIL RIGHTS PROTECTIONS SIMILAR TO THOSE PROVIDED TO PERSONS ON THE BASIS OF RACE, SEX, NATIONAL ORIGIN, AND RELIGION UNDER THE CIVIL RIGHTS ACT OF 1984. THESE CURB RAMPS HAVE BEEN DESIGNATED TO COMPLY WITH THE CURRENT ADA STANDARDS.
4. PROVIDE HANDICAP RAMPS AT LOCATIONS AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. LOCATE WHEELCHAIR RAMPS AS DIRECTED BY THE ENGINEER WHERE EXISTING LIGHT POLES, FIRE HYDRANTS, DROP INLETS, ETC. AFFECT PLACEMENT. WHERE TWO RAMPS ARE INSTALLED, PLACE NOT LESS THAN 2 FEET OF FULL HEIGHT CURB BETWEEN THE RAMPS. PLACE DUAL RAMPS AS NEAR PERPENDICULAR TO THE TRAVEL LANE BEING CROSSED AS POSSIBLE.
5. CONCRETE WHEELCHAIR RAMPS WILL BE MEASURED AND PAID FOR IN UNITS OF 'EACH'.
6. PAY FOR ALL DEPRESSED CURBS AT WHEELCHAIR RAMPS AS THE TYPE CURB AND GUTTER USED ADJACENT TO DEPRESSED CURB. (LINEAR FEET)
7. SUCH PRICES AND PAYMENTS ARE CONSIDERED FULL COMPENSATION FOR ALL MATERIALS, LABORS, EQUIPMENT, TOOLS, AND INCIDENTALS NECESSARY TO SATISFACTORILY COMPLETE THE WORK.
8. DO NOT EXCEED 0.08 (12:1) SLOPE ON THE WHEELCHAIR RAMP IN RELATIONSHIP TO THE GRADE OF THE STREET.
9. CONSTRUCT WHEELCHAIR RAMPS 40" (3'-4") OR GREATER FOR DUAL RAMPS.
10. USE CLASS "A" CONCRETE WITH A SIDEWALK FINISH IN ORDER TO OBTAIN A ROUGH NON-SKID TYPE SURFACE. CONCRETE SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 825 AND SECTION 848 OF THE CURRENT EDITION OF THE NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES.
11. PLACE A 1/2" EXPANSION JOINT WHERE THE CONCRETE WHEELCHAIR RAMP JOINS THE CURB AND AS SHOWN ON NCDOT STD DWG. 848.01.
12. PLACE THE INSIDE PEDESTRIAN CROSSWALK LINES NO CLOSE IN THE INTERSECTION BY BISECTING THE INTERSECTION RADII, WITH ALLOWANCE OF A 4" CLEAR ZONE IN THE VEHICULAR TRAVELWAY, WHEN ONE RAMP IS INSTALLED. (SEE NOTE 17)
13. COORDINATE THE CURB CUT AND THE PEDESTRIAN CROSSWALK LINES SO THE FLOOR OF THE WHEELCHAIR RAMP WILL FALL WITHIN THE PEDESTRIAN CROSSWALK LINES. PLACE DIAGONAL RAMPS WITH FLARED SIDES SO 24" OF FULL HEIGHT CURB FALLS WITHIN THE CROSSWALK MARKINGS ON EACH SIDE OF THE FLARES.
14. CONSTRUCT THE PEDESTRIAN CROSSWALK A MINIMUM OF 6 FEET. A CROSSWALK WIDTH OF 10 FEET OR GREATER IS DESIRABLE.
15. USE STOP LINES, NORMALLY PERPENDICULAR TO THE LANE LINES, WHERE IT IS IMPORTANT TO INDICATE THE POINT BEHIND WHICH VEHICLES ARE REQUIRED TO STOP IN COMPLIANCE WITH A TRAFFIC SIGNAL, STOP SIGN, OR OTHER LEGAL REQUIREMENT. AN UNUSUAL APPROACH SKEW MAY REQUIRE THE PLACEMENT OF THE STOP LINE TO BE PARALLEL TO THE INTERSECTING ROADWAY.
16. TERMINATE PARKING A MINIMUM OF 20 FEET BACK OF PEDESTRIAN CROSSWALK.
17. PLACE ALL PAVEMENT MARKINGS IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), PUBLISHED BY THE FEDERAL HIGHWAY ADMINISTRATION, AND THE NORTH CAROLINA SUPPLEMENT TO THE MUTCD.
18. PRIOR TO THE POURING OF THE CONCRETE, THE FOUNDATION, FORMWORK, ETC. MUST BE APPROVED BY THE PUBLIC WORKS DEPARTMENT.
19. RETROFITTING:
 - A. NEW DETECTABLE DOMES ONTO EXISTING WCR -
SEE NCDOT STD. NO. 848.05 (SHEET 2 OF 4). USE VPC TILE PER SHEET 1.
 - B. NEW WCR ONTO EXISTING SIDEWALK WITH GRASS STRIP -
SEE NCDOT STD NO. 848.06 (SHEET 1 OF 5). USE VPC TILE PER SHEET 1.
 - C. NEW WRC ONTO EXISTING SIDEWALK WHICH IS ADJACENT TO CURB -
SEE NCDOT STD NO. 848.06 (SHEET 2 OF 5). USE VPC TILE PER SHEET 1.
 - D. WHEN RETROFITTING NEW WHEELCHAIR RAMPS. THE ENTIRE CURB AND GUTTER WITHIN THE WHEELCHAIR AREA SHALL BE REMOVED AND REPLACED. THE REMOVAL OF THE EXISTING CURB AND GUTTER WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE UNIT PRICE PER LINEAR FOOT FOR 2'-6" CONCRETE CURB AND GUTTER.



WHEELCHAIR/HANDICAP RAMP
WITH DETECTABLE WARNING SURFACE


CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11

Scale: NTS

300.14

Sheet 4 of 5



www.Armor-Tile.com

ENGINEERED PLASTICS

© 2008 ENGINEERED PLASTICS
 CONFIDENTIAL AND PROPRIETARY DOCUMENT
 ANY ONE OR MORE OF THE FOLLOWING
 PATENTS MAY APPLY
 U.S. PATENT NO. 6,300,664, 5,775,855,
 5,448,790, AND 5,855,522 BY
 C.O.A. PATENT NO. 2,802,532, 2,070,884
 US PATENTS PENDING
 © KENNETH E. SZOKELY

MATERIAL LIST		
#	DESCRIPTION	PART No. QTY
1	ARMOR-TILE	ADA-C-2448-00 1

** COLOR CODE
 YELLOW (TY), RED (RD), BLACK (BK),
 DARK GREY (DG), LIGHT GREY (LG),
 WHITE (WH), OCRE YELLOW (OC),
 BLUE (BL), COLONIAL RED (CR)
 CUSTOM COLORS AVAILABLE

No.	DATE	REVISION	APPR.



REVISION	BY	DATE

PROJECT: VITRIFIED POLYMER COMPOSITE

Armor-Tile ADA
 SOUND AMPLIFYING DETECTABLE/TACTILE
 WARNING SURFACE TILE

Armor-Tile
 DETECTABLE/TACTILE
 WARNING SURFACE TILE
 24" x 48" CAST IN PLACE
 INLINE DOME TACTILE TILE
 PLANS AND DETAILS

DRAWN BY: ADA-C-2448	REV. No: 0
----------------------	------------



WHEELCHAIR/HANDICAP RAMP WITH DETECTABLE WARNING SURFACE


CITY of DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 1/28/11
 Scale: NTS


300.14

Sheet 5 of 5






PLAN VIEW




ELEVATION



NOTE:
 COORDINATE PLACEMENT OF
 CROSSWALKS IN ALL CASES
 WITH THE LOCATION OF
 WHEELCHAIR RAMPS

CONSTRUCTION SPECIFICATIONS

1. CONSTRUCT THE SEDIMENT BARRIER OF STANDARD STRENGTH OR EXTRA STRENGTH SYNTHETIC FILTER FABRICS.
2. ENSURE THAT THE HEIGHT OF THE SEDIMENT FENCE DOES NOT EXCEED 24" ABOVE THE GROUND SURFACE. (HIGHER FENCES MAY IMPOUND VOLUMES OF WATER SUFFICIENT TO CAUSE FAILURE OF THE STRUCTURE.)
3. CONSTRUCT THE FILTER FABRIC FROM A CONTINUOUS ROLL CUT TO LENGTH OF THE BARRIER TO AVOID JOINTS. WHEN JOINTS ARE NECESSARY, SECURELY FASTEN THE FILTER CLOTH ONLY AT A SUPPORT POST WITH 4 FEET MINIMUM OVERLAP TO THE NEXT POST.
4. SUPPORT STANDARD STRENGTH FILTER FABRIC BY WIRE MESH FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS. EXTEND THE WIRE MESH SUPPORT TO THE BOTTOM OF THE TRENCH. FASTEN THE WIRE REINFORCEMENT, THEN FABRIC ON THE UPSLOPE SIDE OF THE FENCE POST. WIRE OR PLASTIC ZIP TIES SHOULD HAVE A MINIMUM 50 LB TENSILE STRENGTH.
5. WHEN A WIRE MESH SUPPORT FENCE IS USED, SPACE POSTS A MAXIMUM OF 8' APART. SUPPORT POSTS SHOULD BE DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24".
6. EXTRA STRENGTH FILTER FABRIC WITH 6' POST SPACING DOES NOT REQUIRE WIRE MESH SUPPORT FENCE. SECURELY FASTEN THE FILTER FABRIC DIRECTLY TO POSTS. WIRE OR PLASTIC ZIP TIES SHOULD HAVE MINIMUM 50 LB TENSILE STRENGTH.
7. EXCAVATE A TRENCH APPROXIMATELY 4" WIDE AND 8" DEEP ALONG THE PROPOSED LINE OF POSTS AND UPSLOPE FROM THE BARRIER.
8. PLACE 12" OF THE FABRIC ALONG THE BOTTOM AND THE SIDE OF THE TRENCH.
9. BACKFILL THE TRENCH WITH SOIL PLACED OVER THE FILTER FABRIC AND COMPACT. THOROUGH COMPACTION OF THE BACKFILL IS CRITICAL TO SILT FENCE PERFORMANCE.
10. DO NOT ATTACH FILTER FABRIC TO EXISTING TREES.



MAINTENANCE

1. INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
2. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.
3. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. TAKE CARE TO AVOID UNDERMINING THE FENCE DURING CLEANOUT.
4. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.


MAXIMUM PLACEMENT OF POST USING HOGWIRE WITH APPROVED EROSION CONTROL FABRICS TO BE 10 FEET.

MAXIMUM PLACEMENT OF POST WITHOUT HOG WIRE USING APPROVED EROSION CONTROL FABRICS TO BE 6 FEET TO 8 FEET APART.


POST METAL T-POST 5 FEET OR 6 FEET IN HEIGHT DEPENDING ON FILL SLOPE.

FABRIC 36 INCHES IN WIDTH (MUST MEET ENGINEERS SPECIFICATIONS FOR EROSION CONTROL)


STONE #4 WASHED STONE TO BE PLACED 12 INCHES DEEP AT SILT FENCE



CROSS SECTION



TOP VIEW



FRONT VIEW

NOTE:
STRUCTURAL STONE SHALL BE (CLASS "B" STONE FOR EROSION CONTROL PURPOSES.

TEMPORARY STONE OUTLET

FOR SILT FENCE


CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11

Scale: NTS

400.01

Sheet 1 of 1




MAINTENANCE:

INSPECT TEMPORARY SEDIMENT TRAPS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT ($\frac{1}{2}$ INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT, AND RESTORE THE TRAP TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOSAL AREA, AND REPLACE THE PART OF THE GRAVEL FACING THAT IS IMPAIRED BY SEDIMENT.

CHECK THE STRUCTURE FOR DAMAGE FROM EROSION OR PIPING. PERIODICALLY CHECK THE DEPTH OF THE SPILLWAY TO ENSURE IT IS A MINIMUM OF 1.5 FEET BELOW THE LOW POINT OF THE EMBANKMENT. IMMEDIATELY FILL ANY SETTLEMENT OF THE EMBANKMENT TO SLIGHTLY ABOVE DESIGN GRADE. ANY RIPRAP DISPLACED FROM THE SPILLWAY MUST BE REPLACED IMMEDIATELY.

AFTER ALL SEDIMENT AREAS HAVE BEEN PERMANENTLY STABILIZED, REMOVE THE STRUCTURE AND ALL UNSTABLE SEDIMENT. SMOOTH THE AREA TO BLEND WITH THE ADJOINING AREAS, AND STABILIZE PROPERLY.

ATTACH SKIMMER TO BOTTOM OF STORM INLET PRIOR TO BIO-CELL CONSTRUCTION, REMOVE SKIMMER



INSTALL WITH 1.7\" ORIFICE TO CONTROL POND DRAINDOWN

6\" PVC PIPE THRU DAM

4\" DRAIN HOSE

SKIMMER MAINTENANCE NOTES:

INSPECT SKIMMER SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (ONE-HALF INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE HEIGHT OF THE FIRST BAFFLE. PULL THE SKIMMER TO ONE SIDE SO THAT THE SEDIMENT UNDERNEATH IT CAN BE EXCAVATED. EXCAVATE THE SEDIMENT FROM THE ENTIRE BASIN, NOT JUST AROUND THE SKIMMER OR THE FIRST CELL. MAKE SURE VEGETATION GROWING IN THE BOTTOM OF THE BASIN DOES NOT HOLD DOWN THE SKIMMER.


REPAIR THE BAFFLES IF THEY ARE DAMAGED. RE-ANCHOR THE BAFFLES IF WATER IS FLOWING UNDERNEATH OR AROUND THEM.

IF THE SKIMMER IS CLOGGED WITH TRASH AND THERE IS WATER IN THE BASIN, USUALLY JERKING ON THE ROPE WILL MAKE THE SKIMMER BOB UP AND DOWN AND DISLODGE THE DEBRIS AND RESTORE FLOW. IF THIS DOES NOT WORK, PULL THE SKIMMER OVER TO THE SIDE OF THE BASIN AND REMOVE THE DEBRIS. ALSO CHECK THE ORIFICE INSIDE THE SKIMMER TO SEE IF IT IS CLOGGED; IF SO REMOVE THE DEBRIS.

IF THE SKIMMER ARM OR BARREL PIPE IS CLOGGED, THE ORIFICE CAN BE REMOVED AND THE OBSTRUCTION CLEARED WITH A PLUMBER'S SNAKE OR BY FLUSHING WITH WATER. BE SURE AND REPLACE THE ORIFICE BEFORE REPOSITIONING THE SKIMMER.

CHECK THE FABRIC LINED SPILLWAY FOR DAMAGE AND MAKE ANY REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIDTH OF THE SPILLWAY. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE SKIMMER AND POOL AREAS.

FREEZING WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. SOME SPECIAL PRECAUTIONS SHOULD BE TAKEN IN THE WINTER TO PREVENT THE SKIMMER FROM PLUGGING WITH ICE.




CONSTRUCTION SPECIFICATIONS

1. CLEAR THE AREA OF ALL DEBRIS THAT MIGHT HINDER EXCAVATION AND DISPOSAL OF SPOIL.
2. INSTALL THE CLASS 'B' RIP-RAP IN A SEMI CIRCLE AROUND THE PIPE INLET. THE STONE SHOULD BE BUILT UP HIGHER ON EACH END WHERE IT TIES INTO THE EMBANKMENT. THE MINIMUM CREST WIDTH OF THE RIP-RAP SHOULD BE 3 FEET, WITH A MINIMUM BOTTOM WIDTH OF 11 FEET. THE MINIMUM HEIGHT SHOULD BE 2 FEET, BUT ALSO 1 FOOT LOWER THAN THE SHOULDER OF THE EMBANKMENT OR DIVERSIONS.
3. A 1 FOOT LAYER OF NC DOT #5 OR #57 STONE SHOULD BE PLACED ON THE OUTSIDE SLOPE OF THE RIP-RAP.
4. THE SEDIMENT STORAGE AREA SHOULD BE EXCAVATED AROUND THE OUTSIDE OF THE STONE HORSESHOE 18" BELOW NATURAL GRADE.
5. WHEN THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, FILL DEPRESSION AND ESTABLISH FINAL GRADING ELEVATIONS, COMPACT AREA PROPERLY AND STABILIZE WITH GROUND COVER.

MAINTENANCE

1. INSPECT ROCK PIPE INLET PROTECTION AT LEAST ONCE WEEKLY AND AFTER EACH SIGNICANT (1/2 INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE SEDIMENT STORAGE AREA TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOSAL AREA AND REPLACE THE CONTAMINATED PART OF THE GRAVEL FACING.
2. CHECK THE STRUCTURE FOR DAMAGE. ANY RIP-RAP DISPLACED FROM THE STONE HORSESHOE MUST BE REPLACED IMMEDIATELY.
3. AFTER ALL THE SEDIMENT-PRODUCING AREAS HAVE BEEN PERMANENTLY STABILIZED, REMOVE THE STRUCTURE AND ALL THE UNSTABLE SEDIMENT. SMOOTH THE AREA TO BLEND WITH THE ADJOINING AREAS AND PROVIDE PERMANENT GROUND COVER.



SECTION THROUGH EMBANKMENT AND BASIN CONTROLS

N.T.S.

CONSTRUCTION SPECIFICATIONS

- 1) Site preparations – Clear, grub, and strip topsoil from areas under the embankment to remove trees, vegetation, roots, and other objectionable material. To facilitate sediment cleanout and restoration, clear the pool area of all brush, trees, and other objectionable materials. Stockpile all topsoil or soil containing organic matter for use on the outer shell of the embankment to facilitate vegetative establishment. Place temporary sediment control measures below the basin as needed.
- 2) Cut-off trench – Excavate a cut-off trench along the centerline of the earth fill embankment. Cut the trench to stable soil material, but in no case make it less than 2 feet deep. The cut-off trench must extend into both abutments to at least the elevation of the riser crest. Make the minimum bottom width wide enough to permit operation of excavation and compaction equipment but in no case less than 2 feet. Make side slopes of the trench no steeper than 1:1. Compaction requirements are the same as those for the embankment. Keep the trench dry during backfilling and compaction operations.
- 3) Embankment – Take fill material from the approved areas shown on the plans. It should be clean mineral soil, free of roots, woody vegetation, rocks, and other objectionable material. Scarify areas on which fill is to be placed before placing fill. The fill material must contain sufficient moisture so it can be formed by hand into a ball without crumbling. If water can be squeezed out of the ball, it is too wet for proper compaction. Place fill material in 6 to 8 inch continuous layers over the entire length of the fill area and then compact it. Compaction may be obtained by routing the construction hauling equipment over the fill so that the entire surface of each layer is traversed by at least one wheel or tread track of the heavy equipment, or a compactor may be used. Construct the embankment to an elevation 10% higher than the design height to allow for settling.
- 4) Conduit spillways – Securely attach the riser to the barrel or barrel stub to make a watertight structural connection. Secure all connections between barrel sections by approved watertight assemblies. Place the barrel and riser on a firm, smooth foundation of impervious soil. Do not use pervious material such as sand, gravel, or crushed stone as backfill around the pipe or anti-seep collars. Place the fill material around the pipe spillway in 4-inch layers and compact it under and around the pipe to at least the same density as the adjacent embankment. Care must be taken not to raise the pipe from firm contact with its foundation when compacting under the pipe haunches.

Place a minimum depth of 2 feet of hand-compacted backfill over the pipe spillway before crossing it with construction equipment. Anchor the riser in place by concrete or other satisfactory means to prevent flotation. In no case should the pipe conduit be installed by cutting a trench through the dam after the embankment is complete.

- 5) Emergency spillway – Install the emergency spillway in undisturbed soil. The achievement of planned elevations, grade, design width, and entrance and exit channel slopes are critical to the successful operation of the emergency spillway.
- 6) Inlets – Discharge water into the basin in a manner to prevent erosion. Use diversions with outlet protection to divert sediment-laden water to the upper end of the pool area to improve basin trap efficiency. (References: Runoff Control Measures and Outlet Protection)
- 7) Erosion control – Construct the structure so that the disturbed area is minimized. Divert surface water away from bare areas. Complete the embankment before the area is cleared. Stabilize the emergency spillway embankment and all other disturbed areas above the crest of the principal spillway immediately after construction. (References: Surface Stabilization)
- 8) Safety – Sediment basins may attract children and can be dangerous. Avoid steep side slopes and fence and mark basins with warning signs if trespassing is likely. Follow all state and local requirements.

MAINTENANCE

Check sediment basins after periods of significant runoff. Remove sediment and restore the basin to its original dimensions when sediment accumulates to one-half the design depth.

Check the embankment, spillways, and outlet for erosion damage, and inspect the embankment for piping and settlement. Make all necessary repairs immediately. Remove all trash and other debris from the riser and pool area.



**STANDARD RISER/BARRELL SEDIMENT BASIN
CONSTRUCTION SPECIFICATIONS**


**CITY of DUNN
NORTH CAROLINA
Department of Public Works**

Revised: 1/28/11

Scale: NTS

400.05

Sheet 2 of 2




USE 2 TO 15-INCH STONE (NCDOT CLASS A OR B EROSION CONTROL STONE). KEY THE STONE INTO THE DITCH BANKS AND EXTEND IT BEYOND THE ABUTMENTS A MINIMUM OF 18 INCHES TO AVOID WASHOUTS FROM OVERFLOW AROUND THE DAM.

CONSTRUCTION SPECIFICATIONS

1. PLACE STONE TO THE LINES AND DIMENSIONS SHOWN IN THE PLAN ON A FILTER FABRIC FOUNDATION.
2. KEEP THE CENTER STONE SECTION AT LEAST 9 INCHES BELOW NATURAL GROUND LEVEL WHERE THE DAM ABUTS THE CHANNEL BANKS.
3. EXTEND STONE AT LEAST 1.5 FT BEYOND THE DITCH BANKS TO KEEP OVERFLOW WATER FROM UNDERCUTTING THE DAM AS IT REENTERS THE CHANNEL.

MAINTENANCE

CHECK SEDIMENT BASINS AFTER EACH RAINFALL. REMOVE SEDIMENT AND RESTORE ORIGINAL VOLUME WHEN SEDIMENT ACCUMULATES TO ABOUT ONE-HALF THE DESIGN VOLUME. SEDIMENT SHOULD BE PLACED ABOVE THE BASIN AND ADEQUATELY STABILIZED. CHECK THE STRUCTURE FOR EROSION, PIPING, AND ROCK DISPLACEMENT WEEKLY AND AFTER EACH SIGNIFICANT (½ INCH OR GREATER) RAINSTORM AND REPAIR IMMEDIATELY. REMOVE THE STRUCTURE AND ANY UNSTABLE SEDIMENT IMMEDIATELY AFTER THE CONSTRUCTION SITE HAS BEEN PERMANENTLY STABILIZED. SMOOTH THE BASIN SITE TO BLEND WITH THE SURROUNDING AREA AND STABILIZE. ALL WATER AND SEDIMENT SHOULD BE REMOVED FROM THE BASIN PRIOR TO DAM REMOVAL. SEDIMENT SHOULD BE PLACED IN DESIGNATED DISPOSAL AREAS AND NOT ALLOWED TO FLOW INTO STREAMS OR DRAINAGE WAYS DURING STRUCTURE REMOVAL.




INSTALLATION:

1. REMOVE ALL VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE AND CROWN FOUNDATION FOR POSITIVE DRAINAGE.
2. IF THE SLOPE TOWARDS THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE, 6-8" HIGH WITH 3:1 SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FT FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.
3. PLACE GEOTEXTILE FABRIC ON GRADED FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.
4. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPED FOR DRAINAGE.
5. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A SEDIMENT TRAP OR BASIN.
6. INSTALL PIPE UNDER PAD IF NEEDED TO MAINTAIN PROPER PUBLIC ROAD DRAINAGE.

MAINTENANCE:

1. INSPECT ENTRANCE/EXIT PAD AND SEDIMENT DISPOSAL AREA AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT ($\frac{1}{2}$ " OR GREATER) RAIN EVENT OR HEAVY USE.
2. RESHAPE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
3. TOPDRESS WITH CLEAN STONE AS NEEDED.
4. IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROAD.
5. REPAIR ANY BROKEN ROAD PAVEMENT IMMEDIATELY.





CONSTRUCTION SPECIFICATIONS

1. CONSTRUCT DIVERSION TO DIMENSIONS AND GRADES SHOWN ON PLANS.
2. BUILD RIDGE HIGHER THAN DESIGN AND COMPACT WITH WHEELS OF CONSTRUCTION EQUIPMENT. COMPACTED RIDGE MUST BE AT OR ABOVE DESIGN GRADE AT ALL POINTS. CHANNEL MUST BE CONSTRUCTED ON DESIGN GRADE
3. LEAVE SUFFICIENT AREA ALONG DIVERSION TO PERMIT CLEANOUT AND REGRADING.
4. STABILIZE OUTLETS DURING INSTALLATION OF DIVERSION.
5. WHERE TEMPORARY DIVERSIONS ARE CONSTRUCTED ABOVE STEEP SLOPES, INSTALL TEMPORARY SLOPE DRAINS FOR OUTLETS.
6. FLOW CONTAINING SEDIMENT MUST BE DIVERTED TO A SEDIMENT TRAP.
7. RIDGE MUST BE STABILIZED WITH VEGETATION IF IN PLACE LONGER THAN 30 WORKING DAYS. CHANNEL MUST BE STABLE FOR DESIGN FLOW.

MAINTENANCE

1. INSPECT AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT ($\frac{1}{2}$ " OR GREATER) RAINFALL EVENT. REMOVE SEDIMENT FROM CHANNEL AND REINFORCE RIDGE AS NEEDED. CHECK OUTLETS, REMOVE SEDIMENT FROM TRAPS WHEN THEY ARE 50% FULL, AND MAKE NECESSARY REPAIRS IMMEDIATELY.
2. WHEN WATERSHED AREA HAS BEEN STABILIZED, REMOVE RIDGE AND FILL CHANNEL TO BLEND WITH NATURAL GROUND REMOVE TEMPORARY SLOPE DRAINS. STABILIZE ALL DISTURBED AREAS.






Construction Specification

1. Keep clearing and excavation of the stream banks and bed and approach sections to a minimum.
2. Divert all surface water from the construction site onto undisturbed areas adjoining the stream. Line unstable stream banks with riprap or otherwise appropriately stabilize them.
3. Keep stream crossing at right angles to the stream flow. This is particularly important when culverts are used.
4. Align road approaches with the center line of the crossing for a minimum distance of 30 ft. Raise bridge abutments and culvert fills a minimum of 1 ft. above adjoining approach sections to prevent erosion from surface runoff and to allow flows to pass around structure.
5. Stabilize all disturbed areas subject to flowing water, including planned overflow areas, with riprap or other suitable means if design velocity exceeds the allowable for the in-place soil (Table 8.05a, Appendix 8.05).
6. Ensure that bypass channels necessary to dewater the crossing site are stable before diverting the stream. Upon completion of the crossing, fill, compact, and stabilize the bypass channel appropriately.
7. Remove temporary stream crossings immediately when they are no longer needed. Restore the stream channel to its original cross-section, and smooth and appropriately stabilize all disturbed areas.
8. Leave in stream sediment traps in place to continue capturing sediment.

Maintenance

Inspect temporary stream crossing after runoff-producing rains to check for blockage in channel, erosion of abutments, channel scour, riprap displacement, or piping. Make all repairs immediately to prevent further damage to the installation.





BUTT BLOCKS FIRMLY AGAINST CONCRETE AND LET BLOCKS EXTEND AS NECESSARY AT EDGES.

CONSTRUCTION SPECIFICATIONS

1. TO PREVENT BYPASS FLOW, TOP OF STRUCTURE SHOULD BE 6" MINIMUM BELOW GROUND ELEVATION ON THE DOWNSLOPE SIDE. OTHERWISE, CONSTRUCT A TEMPORARY DIKE TO PREVENT BYPASS FLOW. THE DIKE SHOULD BE COMPACTED AND AT LEAST 6" HIGHER THAN THE STRUCTURE AND STABILIZED APPROPRIATELY.
2. EXCAVATE INLET PROTECTION MAY BE USED WITH STRUCTURAL INLET PROTECTION TO PREVENT BYPASS FLOW, IMPROVE TRAP EFFICIENCY, AND PROVIDE SEDIMENT STORAGE CAPACITY.
3. EXCAVATE FOUNDATION FOR THE BLOCKS ON LEVEL GRADE AT LEAST 2" BELOW THE TOP OF THE STORM DRAIN.
4. PLACE BOTTOM ROW OF BLOCKS AGAINST EDGE OF STORM DRAIN. BUTT BLOCKS FIRMLY AGAINST CONCRETE AND LET BLOCKS EXTEND AS NECESSARY AT EDGES. STORM DRAIN PROVIDES LATERAL SUPPORT AND PREVENTS UNDERCUTTING. SUPPORT BLOCKS Laterally WITH 2"x4" WOOD STUDS THROUGH BLOCK OPENINGS IF NECESSARY. DO NOT USE MORTAR.
5. LAY ONE BLOCK ON ITS SIDE IN EACH SIDE OF THE BOTTOM ROW TO DRAIN THE POOL. PLACE WIRE SCREEN (HARDWARE CLOTH) OVER BLOCK OPENINGS TO HOLD GRAVEL IN PLACE.
6. PLACE GRAVEL AROUND BLOCKS ON A 2:1 SLOPE OR FLATTER, ALLOWING 2-4" BETWEEN TOP OR GRAVEL AND TOPS OF BLOCKS.

MAINTENANCE

1. INSPECT STRUCTURE AT LEAST ONCE WEEKLY AND AFTER EACH SIGNICANT ($\frac{1}{2}$ " OR GREATER) RAINFALL EVENT. REMOVE SEDIMENT, AND MAKE NEEDED REPAIRS IMMEDIATELY.
2. WHEN THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, INSPECTED, AND APPROVED, REMOVE ALL CONSTRUCTION MATERIAL AND ANY UNSTABLE SEDIMENT AND DISPOSE OF THEM PROPERLY. STABILIZE AS SHOWN ON PLAN.




CONSTRUCTION SPECIFICATIONS

1. UNIFORMLY GRADE A SHALLOW DEPRESSION APPROACHING THE INLET.
2. DRIVE 5' STEEL POSTS 2' INTO THE GROUND SURROUNDING THE INLET. SPACE POSTS EVENLY AROUND THE PERIMETER OF THE INLET, A MAXIMUM OF 4' APART.
3. SURROUND THE POSTS WITH WIRE MESH HARDWARE CLOTH. SECURE THE WIRE MESH TO THE STEEL POSTS AT THE TOP, MIDDLE AND BOTTOM. PLACING A 2' FLAP OF THE WIRE MESH UNDER THE GRAVEL FOR ANCHORING IS RECOMMENDED.
4. PLACE CLEAN GRAVEL (NC DOT #5 OR #57 STONE) ON A 2:1 SLOPE WITH A HEIGHT OF 16" AROUND THE WIRE, AND SMOOTH TO AN EVEN GRADE.
5. ONCE THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE ACCUMULATED SEDIMENT, AND ESTABLISH FINAL GRADING ELEVATIONS.
6. COMPACT THE AREA PROPERLY AND STABILIZE IT WITH GROUND COVER.

MAINTENANCE

INSPECT INLETS AT LEAST WEEKLY AND AFTER EACH SIGNICANT (1/2" OR GREATER) RAINFALL EVENT. CLEAR THE MESH WIRE OF ANY DEBRIS OR OTHER OBJUECTS TO PROVIDE ADEQUATE FLOW FOR SUBSEQUENT RAINS. TAKE CARE NOT TO DAMAGE OR UNDERCUT THE WIRE DURING SEDIMENT REMOVAL.




CONSTRUCTION SPECIFICATIONS

1. CLEAR AREA OF ALL DEBRIS. REMOVE AND STOCKPILE OR SPREAD SOIL SO THAT IT WILL NOT BLOCK FLOW OR WASH BACK INTO THE EXCAVATION.
2. EXCAVATE BASIN TO DEPTH, SIDE SLOPES, AND DIMENSIONS SHOWN ON PLANS.
3. SHAPE BASIN TO FIT SITE CONDITIONS WITH LONGEST DIMENSIONS ORIENTED TOWARD THE LARGEST INFLOW.
4. INSTALL WEEP HOLES IN DROP INLET TO DRAIN POOL SLOWLY COVER HOLES WITH WIRE SCREEN (HARDWARE CLOTH) AND GRAVEL TO HOLD SEDIMENT IN PLACE. GRAVEL TO BE 1/2" TO 3/4" WASHED AGGREGATE (NC DOT #57 OR #5), 1' THICK, MINIMUM.
5. EXCAVATE MINIMUM DEPTH 1' AND A MAXIMUM DEPTH AT 2' AS MEASURED FROM THE CREST OF THE INLET STRUCTURE.
6. MAINTAIN SIDE SLOPES AROUND THE EXCAVATION NO STEEPER THAN 2:1.
7. WHEN NECESSARY, SPOIL MAY BE PLACED TO FORM A DIKE ON THE DOWNSLOPE SIDE OF THE EXCAVATION TO PREVENT BYPASS FLOW.
8. STABILIZE ALL DISTURBED AREAS, EXCEPT THE EXCAVATED POOL BOTTOM, IN ACCORDANCE WITH VEGETATION PLAN.


MAINTENANCE

1. INSPECT, CLEAN, AND PROPERLY MAINTAIN THE EXCAVATED BASIN AFTER EVERY RAINFALL UNTIL CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED.
2. REMOVE SEDIMENT WHEN THE EXCAVATED VOLUME IS APPROXIMATELY 50% FULL.
3. REMOVE AND REPLACE GRAVEL OVER WEEP HOLES WHEN DRAINAGE STOPS.
4. WHEN THE CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED, INSPECTED, AND APPROVED, SEAL WEEP HOLES, REMOVE SEDIMENT, AND FILL BASIN WITH STABLE SOIL. COMPACT AND GRADE TO FINAL ELEVATION. STABILIZE ALL DISTURBED AREAS IMMEDIATELY AS SHOWN ON PLANS.




**PLYWOOD
STORM DRAIN INLET FILTER PROTECTION**

N.T.S.



**STONE
STORM DRAIN INLET FILTER PROTECTION**

INSTALL AT THE END OF EACH DAY.



CONSTRUCTION SPECIFICATIONS


1. PLACE SLOPE DRAINS ON UNDISTURBED SOIL OR WELL COMPACTED FILL AT LOCATIONS AND ELEVATIONS SHOWN ON PLANS. SET INLET OF SLOPE DRAIN AT BOTTOM OF THE DIVERSION CHANNEL.
2. SLOPE THE INLET SECTION SLIGHTLY TOWARD THE PIPE OUTLET.
3. PLACE FILL OVER PIPE IN 6" LIFTS, MAXIMUM. COMPACT EACH LIFT BY HAND-TAMPING UNDER AND AROUND THE INLET AND ALONG THE PIPE.
4. CONNECT PIPE TO DIVERSION RIDGE AT TOP OF SLOPE BY COVERING WITH COMPACTED FILL MATERIAL WHERE IT PASSES THROUGH THE DIVERSION RIDGE. FILL OVER PIPE SHOULD BE AT LEAST 1.5' DEEP, WITH TOP WIDTH OF 4', AND 3:1 SIDE SLOPES. TOP OF FILL SHOULD BE 0.5' HIGHER THAN THE ADJOINING DIVERSION RIDGE CREATING AN ISLAND OVER THE PIPE TO PREVENT WASHOUT.
5. MAKE ALL PIPE CONNECTIONS WATERTIGHT AND SECURE SO THAT JOINTS WILL NOT SEPARATE IN USE.
6. SECURE PIPE TO FACE OF SLOPE WITH GROMMETS OR STAKES SPACED NO MORE THAN 10' APART.
7. EXTEND DRAIN BEYOND THE TOE OF THE SLOPE TO STABLE GRADE, AND PROTECT OUTLET FROM EROSION. TERMINATE DRAIN IN A 4' LEVEL SECTION WHERE PRACTICAL.
8. GRADE THE DIVERSION CHANNEL AT THE TOP OF THE SLOPE TOWARD THE TEMPORARY SLOPE DRAIN. POSITIVE GRADE IS IMPORTANT.
9. COMPACTED DIVERSION RIDGE MUST BE AT LEAST 1' HIGHER THAN THE TOP OF THE DRAIN PIPE AT ALL POINTS AND 1.5' HIGHER DIRECTLY OVER THE INLET SECTION.

MAINTENANCE


FAILURE OF A TEMPORARY SLOPE DRAIN CAN CAUSE SEVERE EROSION DAMAGE. THIS PRACTICE REQUIRES INTENSIVE MAINTENANCE. INSPECT SLOPE DRAINS AND SUPPORTING DIVERSIONS AT LEAST ONCE WEEKLY AND AFTER EACH SIGNICANT ($\frac{1}{2}$ " OR GREATER) RAINFALL EVENT.

1. CHECK INLET FOR SEDIMENT OR TRASH ACCUMULATION. CLEAR INLET AND RESTORE PROPER ENTRANCE CONDITION.
2. CHECK FILL OVER PIPE FOR SETTLEMENT, CRACKING, OR PIPING HOLES. REPAIR IMMEDIATELY.
3. CHECK FOR SEEPAGE HOLES AT POINT WHERE PIPE EMERGES FROM DIKE. REPAIR IMMEDIATELY.
4. CHECK CONDUIT FOR EVIDENCE OF LEAKS OR INADEQUATE LATERAL SUPPORT. REPAIR IMMEDIATELY.
5. CHECK OUTLET FOR EROSION OR SEDIMENTATION. CLEAN, REPAIR, OR EXTEND AS NEEDED.
6. WHEN SLOPES HAVE BEEN STABILIZED, INSPECTED, AND APPROVED, REMOVE TEMPORARY DIVERSIONS AND SLOPE DRAINS, AND STABILIZE ALL DISTURBED AREAS.

PIPE OUTLET TO FLAT AREA –
NO WELL-DEFINED CHANNEL




PLAN




SECTION A-A FILTER
BLANKET

PIPE OUTLET TO WELL-DEFINED
CHANNEL



PLAN



SECTION AA

FILTER
BLANKET

NOTES

1. L_a IS THE LENGTH OF RIPRAP APRON
2. $d=1.5$ TIMES THE MAXIMUM STONE DIAMETER BUT NOT LESS THAN 6".
3. IN A WELL-DEFINED CHANNEL EXTEND THE APRON UP ON THE CHANNEL BANKS TO AN ELEVATION OF 6" ABOVE THE MAXIMUM TALLWATER DEPTH OR TO TOP OF THE BANK, WHICHEVER IS LESS.
4. A FILTER BLANKET OR FILTER FABRIC SHOULD BE INSTALLED BETWEEN THE RIP-RAP AND SOIL FOUNDATION.

MAINTENANCE

INSPECT RIPRAP OUTLET STRUCTURES WEEKLY AND AFTER SIGNIFICANT ($\frac{1}{2}$ INCH OR GREATER) RAINFALL EVENTS TO SEE IF ANY EROSION AROUND OR BELOW THE RIPRAP HAS TAKEN PLACE, OR IF STONES HAVE BEEN DISLODGED. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE.

TEMPORARY SEEDING for LATE WINTER/EARLY SPRING

SEEDING MIXTURE

Species	Rate (lb per acre)
Rye (grain)	120
Annual lespedeza (Kobe in Piedmont and Coastal Plain, Korean in mountains)	50

SEEDING DATES

Mountains - Above 2500 ft:	Feb 15 - May 15
Below 2500 ft:	Feb 1 - May 1
Piedmont -	Jan 1 - May 1
Coastal -	Dec 1 - Apr 15

SOIL AMENDMENTS

Follow recommendations of soil tests or apply 2,000 lb/acre ground agricultural limestone and 750 lb/acre 10-10-10 fertilizer.

MULCH

Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch anchoring tool. A disk with blades set nearly straight can be used as a mulch anchoring tool.

MAINTENANCE

Referertilize if growth is not fully adequate. Reseed, referertilize and mulch immediately following erosion or other damage.

TEMPORARY SEEDING for SUMMER

SEEDING MIXTURE

Species	Rate (lb per acre)
German Millet	40

In the Piedmont and Mountain areas, a small-stemmed Sudangrass may be substituted at a rate of 50 lb/acre.

SEEDING DATES

Mountains -	May 15 - Aug 15
Piedmont -	May 1 - Aug 15
Coastal -	Apr 15 - Aug 15

SOIL AMENDMENTS

Follow recommendations of soil tests or apply 2,000 lb/acre ground agricultural limestone and 750 lb/acre 10-10-10 fertilizer.

MULCH

Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch anchoring tool. A disk with blades set nearly straight can be used as a mulch anchoring tool.

MAINTENANCE

Referertilize if growth is not fully adequate. Reseed, referertilize and mulch immediately following erosion or other damage.

TEMPORARY SEEDING for FALL

SEEDING MIXTURE

Species	Rate (lb per acre)
Rye (grain)	120

SEEDING DATES

Mountains	- Aug 15 - Dec 15
Coastal & Piedmont	- Aug 15 - Dec 30

SOIL AMENDMENTS

Follow recommendations of soil tests or apply 2,000 lb/acre ground agricultural limestone and 1,000 lb/acre 10-10-10 fertilizer.

MULCH

Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch anchoring tool. A disk with blades set nearly straight can be used as a mulch anchoring tool.

MAINTENANCE

Repair and referertilize damaged areas immediately. Topdress with 50 lb/acre of nitrogen in March. If it is necessary to extend temporary cover beyond June 15, overseed with 50 lb/acre Kobe (Piedmont and Coastal Plain) or Korean (Mountains) lespedeza in late February or early March.



TEMPORARY SEEDING SPEC'S

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS

400.16

Sheet 1 of 1

PERMANENT SEEDING

DEFINITION

Seeding disturbed areas with perennial grasses and (or) legumes to provide a permanent vegetative cover to lessen runoff and soil erosion.

PURPOSE

To lessen soil erosion and permanently stabilize disturbed areas created by grading of construction sites.

CONDITIONS WHERE PRACTICE APPLIES

All bare soil areas on construction sites which are not covered by structures or other erosion control devices.

PREPARATION

Prepare seedbed by ripping, chiseling, harrowing or plowing to depth of six inches so as to produce a loose, friable surface. Remove all stones, boulders, stumps or debris from the surface which would prohibit germination or plant growth. Spread topsoil in a layer 3" - 6" depth.


Incorporate into the soil 800 to 1,000 pounds of 10-10-10 fertilizer plus 500 pounds of twenty percent (20%) superphosphate per acre and two tons of dolomitic lime per acre unless soil tests indicate that a lower rate of lime can be used.

Mulch after seeding with 1.5 tons of grain straw per acre and either crimp straw into soil or tack with liquid asphalt at 400 gallons per acre or emulsified asphalt at 300 gallons per acre.


<u>PLANTS & MIXTURE</u>	<u>PLANTING RATE/ACRE</u>	<u>PLANTING DATES</u>
Tall Fescue (Low Maintenance)	100-150 lbs.	Aug. 15 - Oct. 15 Feb. 15 - May 1
Tall fescue Waterways and Lawns (High Maint.)	200-250 lbs.	Aug. 15 - Oct. 15 Feb. 15 - May 1
Blend of two turf- type tall Fescues (90%) and two or more improved Kentucky bluegrass varieties (10%) (high maintenance)	200-250 lbs.	Aug. 15 - Oct. 15 Feb. 15 - May 1
Tall Fescue <i>and</i> Kobe or Korean Lespedeza	100 lbs. <i>and</i> 20-25 lbs.	Feb. 15 - May 1 Aug. 15 - Oct. 15
Tall Fescue	50 lbs./acre	Nov. 1 - Feb. 1 (Unscarified)
Tall Fescue and German Millet or Sudangrass 2	60 lbs. <i>and</i> 30 lbs.	July and August
Tall Fescue <i>and</i> Ryegrain 2	70 lbs. <i>and</i> 25 lbs.	Nov. 1 - Jan. 30
Common Bermudagrass	8 lbs. (hulled) 15-20 lbs. (unhulled)	April 15 - June 30 Feb. 1 - March 30

1 For spring seedings, use Scarified Lespedeza seed. For late fall and winter seedings, use unscarified seed.


2 Annuals such as Millet, Sudangrass and Ryegrain must be kept at 10-12" maximum height.



STREAM CROSSING BORE AND JACK




*DEPTH AS NECESSARY TO MEET MINIMUM COVER
AND/OR MINIMUM UTILITY SEPARATION REQUIREMENTS



NOTES:

1. NORMAL SPACING FOR SPIDERS IS 3 PER 13' OR 18' LENGTH OF PIPE, ONE SUPPORT AT EACH END AND A SUPPORT AT 9' CENTER.
2. ENTIRE SPIDER ASSEMBLY TO BE BITUMINOUS COATED AFTER FABRICATION.
3. FIELD MODIFY AS REQUIRED TO PROVIDE DESIGN SLOPE IN CARRIER PIPE.
4. SIZING TABLE ON 500.02 2 of 2



END ELEVATION

SIZE AND WALL THICKNESS OF SMOOTH WALL OR SPIRAL WELDED
ENCASEMENT PIPE SHALL BE AS FOLLOWS:


PIPE SIZE (O.D.) (INCHES)	WALL THICKNESS (INCHES)
12 3/4	0.188
16	0.250
18	0.250
20	0.250
24	0.250
30	0.312
36	0.375

CARRIER / CASING PIPE SHALL HAVE THE
FOLLOWING MINIMUM SIZES:



CARRIER PIPE SIZE (INCHES)	CASING PIPE SIZE (INCHES)
4	12 3/4
6	12 3/4
8	18
10	20
12	24
14	26
16	28

NOTE:

1. UNDER A ROAD MAINTAINED BY NCDOT, THE ENCASEMENT PIPE SHALL BE COATED TO MEET NCDOT REQUIREMENTS.
2. CASING PIPE SHALL BE INSTALLED WITH A MINIMUM COVER OF 3 FEET UNDER PAVEMENT.



FLOWABLE FILL TRENCH-CUT
STREET, WATER, SEWER AND
STORMWATER



GENERAL NOTES:

1. ALL CONCRETE BLOCKING SHALL BE 3000 P.S.I. MINIMUM.
2. ALL HYDRANT VALVES SHALL BE RODDED TO MAIN LINE.
3. HYDRANT TO BE LOCATED 10' FROM P.T. OR P.C. AT INTERSECTIONS.
4. THE HYDRANT PUMPER NOZZLE SHALL BE OF ONE-PIECE DESIGN.
5. THE NOZZLE SHALL BE AN INTEGRAL PART OF THE FIRE HYDRANT AND MUST BE FURNISHED BY THE MANUFACTURER OR AUTHORIZED DISTRIBUTOR. ADAPTERS WILL NOT BE ACCEPTED.
6. HYDRANTS SHALL BE PAINTED SAFETY YELLOW.



STANDARD FIRE HYDRANT


CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 3/09/22

Scale: NTS

600.0

Sheet 1 of 1




WELDED ON THRUST COLLAR	
I.D. PIPE	"A"
6"-16"	2"
20"-24"	3"
30"-36"	4"


THRUST COLLAR REINFORCING		
	"X" BAR	"Y" BAR
BAR LENGTH	2'-2" + O.D. PIPE	1'-1"
REBAR SIZE	#5	#5
NUMBER REQ'D	24	12

NOTES:


1. CONCRETE SHALL BE 3000 P.S.I
2. REINFORCING BARS SHALL BE DEFORMED, AND TIED TOGETHER.
3. BACKFILL TAMPED IN 6" LAYERS
4. TRENCH BOTTOM WIDTH IN VICINITY OF THRUST BLOCK(S) INSTALLATION SHALL BE THE MINIMUM WIDTH AS DESCRIBED BY THE ENGINEER.



ELBOW




HORIZONTAL BEND




TEE

ALL BEARING SURFACES SHALL BE AGAINST UNDISTURBED GROUND (TYP.)




SEE BLOW-OFF DETAIL FOR CLARIFICATION OF CONSTRUCTION REQUIRED AT DEAD ENDS

DEAD END



CROSS


CONCRETE SHALL BE KEPT CLEAR OF PIPE JOINTS (TYP.)



MIN. BEARING AREA EACH DIRECTION OF THRUST IN SQUARE FEET (based on soil supporting value of 2000 psf @ 200 psig test pressure)				
PIPE SIZE	TEES & DEADENDS	90° ELBOWS	45° ELBOW & CROSSES	22-1/2° ELBOWS
6"	4	6	3	2
8"	7	10	5	3
12"	15	21	11	6


NOTES:

- 1.) THRUST BLOCKS SHALL BE INSTALLED ON PVC WATER DISTRIBUTION LINES 6" THRU 12" DIA. IN THE MANNER SHOWN. SEE STANDARD ALT. RESTRAINING DETAIL 600.04 FOR ACCEPTABLE ALTERNATE RESTRAINING SYSTEMS.
- 2.) PIPE GREATER THAN 12 INCH DIAMETER SHALL REQUIRE RESTRAINT JOINT PIPE FOR THE PROPER LENGTH.
- 3.) COMPACT FITTINGS ARE ACCEPTABLE. STANDARD FITTINGS SHALL BE USED WITH CONCRETE THRUST BLOCKING.
- 4.) THRUST BLOCKS SHALL BE INSTALLED ON SEWER FORCE MAIN IN THE MANNER SHOWN.
- 5.) IF SAC-CRETE IS USED, MIXING MUST BE ON SITE UTILIZING A MECHANICAL MIXER.
- 6.) NO CONCRETE SHALL BE PLACED ON BOLTS. WRAP JOINT FITTINGS WITH PLASTIC.
- 7.) CONCRETE SHALL BE A MINIMUM 3,000 psi.
- 8.) ALL BEARING SURFACES SHALL BE AGAINST UNDISTURBED SOIL AND SHALL BE APPROVED BY PWC PROJ. COORDINATOR PRIOR TO PLACEMENT OF CONCRETE.
- 9.) USE OF RESTRAINED JOINT DUCTILE IRON WILL BE REQUIRED IF SOIL CONDITIONS DO NOT ALLOW THE USE OF THRUST BLOCKS
- 10.) ALL VERTICAL BENDS SHALL BE RESTRAINED USING RESTRAINED JOINT DUCTILE IRON PIPE.



IRON RETAINING GLAND M.J. RESTRAINT			
NOMINAL PIPE SIZE	WEDGES QUANTITY	BOLTS QUANTITY	PRESS RATING
6"	3	6	350
8"	4	6	350
12"	8	8	350

8" SIZE SHOWN 6" & 12" SIMILAR
IRON RETAINING GLAND M.J. RESTRAINT




RESTRAINED JOINT DETAIL FOR TYPICAL TEE INTERSECTION
4 WAY INTERSECTION SIMILARLY RESTRAINED

LR (MIN. LENGTH OF RESTRAINT EACH DIRECTION OF THRUST IN LINEAR FEET)

Based on 200 psig pressure, Safety Factor of 2.0:1, BARE DI PIPE AND ML Soil, 3.5' cover
Chart does not apply to pipes wrapped in polyethylene wrap

PIPE SIZE	VALVES DEAD ENDS TEES	90° ELBOWS	45° ELBOW & CROSSES	22-1/2° ELBOWS	REDUCER
6"	55'	31'	13'	7'	8"X2" 67'
8"	72'	40'	17'	8'	8"X6" 30'
12"	102'	57'	24'	12'	12"X8" 54'



NOTES:

- THRUST RESTRAINT SHALL BE INSTALLED ON DUCTILE IRON WATER DISTRIBUTION LINES 6" THRU 12" DIAMETER IN THE MANNER SHOWN. SEE STANDARD THRUST BLOCK DETAIL 600.03 FOR PVC RESTRAINT.
- IRON RETAINING GLAND M.J. RESTRAINT OR OTHER FORMS OF IRON RESTRAINT SHALL NOT BE USED ON PVC PIPE.
- PIPE GREATER THAN 12 INCH DIAMETER SHALL REQUIRE RESTRAINED JOINT PIPE FOR THE PROPER LENGTH.
- COMPACT FITTINGS ARE ACCEPTABLE FOR USE WITH IRON RETAINING GLAND M.J. RESTRAINT AND OTHER FORMS OF DI RESTRAINT.
- THE MINIMUM LENGTH OF RESTRAINT INDICATED SHALL REQUIRE ALL JOINTS WITHIN THE LR DISTANCE TO BE RESTRAINED.
- RESTRAINT SYSTEM SHALL BE INSPECTED AND APPROVED BY THE CITY OF DUNN PRIOR TO BACKFILLING.
- RESTRAINT SYSTEMS MAY VARY BASED UPON THE ENGINEERS' DESIGN AS SHOWN ON THE PLAN AND PROFILE SHEETS.
- GRIPPER RING AND FIELD LOK GASKETS ARE AN ACCEPTABLE METHOD OF RESTRAINT ON DUCTILE IRON PIPE ONLY.



ALTERNATE RESTRAINTS

DUCTILE IRON PIPE ONLY


CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11


Scale: NTS

600.04

Sheet 1 of 1




PLAN



ELEVATION

GENERAL NOTES:

1. 3000 P.S.I. SOLID CONCRETE BLOCKING BEHIND SLEEVE.
2. CONCRETE SHALL NOT CONTACT BOLTS OR ENDS OF MECHANICAL JOINT FITTINGS.
3. 12" X 12" AND 16" X 16" TAPPING SLEEVE IS NOT ALLOWED.



NOTES:

1. ALL MATERIALS SHALL BE IN ACCORDANCE WITH CITY STANDARDS.
2. RAISED MALE FACE SHALL BE REQUIRED TO PROVIDE FOR PROPER ALIGNMENT OF THE TAPPING SLEEVE.
3. ALL VALVES SHALL HAVE 2" SQUARE OPERATING NUT AND SHALL OPEN COUNTERCLOCKWISE.
4. RESILIENT WEDGE GATE VALVE SHALL BE AS MANUFACTURED BY MUELLER CORP., AMERICAN DARLING OR CLOW CORP.
5. VALVE BODY, BONNET AND GATE SHALL BE IN ACCORDANCE WITH AWWA C-509/C-515 AND NSF61.
6. VALVE BODY AND BONNET SHALL BE COATED ON ALL INTERIOR AND EXTERIOR SURFACES WITH A FUSION BONDED EPOXY IN ACCORDANCE WITH AWWA C-550-90.
7. ALL VALVES 24" AND SMALLER SHALL HAVE A SAFE WORKING PRESSURE OF 250 PSI.
8. SEE TAPPING SLEEVE FOR ADDITIONAL INFORMATION.
9. DIMENSIONS SHOWN ARE FOR REFERENCE AND MAY VARY BASED UPON MANUFACTURER. VALVES SHALL BE SIMILAR IN NATURE TO THAT SHOWN AND SHALL NOT DEVIATE IN ESSENTIAL DETAILS.
10. ALL TAPPING SLEEVES SHALL BE HYDROSTATICALLY PRESSURE TESTED PRIOR TO THE TAP BEING ACCOMPLISHED. TEST SHALL BE APPROVED BY PWC PROJECT COORDINATOR PRIOR TO BEGINNING TAPPING PROCESS.

VALVE SIZE	A	B	C	D	E	F	G	H	J	K	L	M	N	R	S	T	TURNS TO OPEN	WEIGHT W/ACC
4	4-3/8	5-7/8	15/16	1-1/2	9	7-1/2	4-7/8	4-63/64	4-29/32	2-1/2	7-1/2	9	14-1/8	9	8-3/4	1/4	14	118
6	6-7/8	6-1/4	1	1-5/8	11	9-1/2	6-7/8	6-63/64	7	2-1/2	9-1/2	11	17-5/8	11-3/4	8-7/8	1/4	21	175
8	6-1/2	7-1/4	1-1/8	1-3/4	13-1/4	11-3/4	6-7/8	8-63/64	9-5/32	2-1/2	11-3/4	13-1/2	21	14-1/4	8-7/8	1/4	28	274
12	7	8-1/4	1-1/4	1-3/4	17-7/8	16-1/4	8-7/8	12-63/64	13-5/16	2-1/2	17	19	28-1/4	19-1/8	12-1	1/4	39	570
16	8-1/2	9-1/8	1-7/16	2-1/16	23	21	12-7/8	16-15/16	17-35/64	3-1/2	21-1/4	23-1/2	38-5/8	26-1/8	16-1 1/8	1/4	55	1140
24	10-1/2	14-1/4	1-7/8	2-1/2	31-3/4	30	16-7/8	24-15/16	25-15/16	3-1/2	29-1/2	32	54-5/8	37-5/8	20-1 3/8	5/16	79	3225




M.J. TAPPING VALVE

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11
Scale: NTS

600.05

Sheet 2 of 4



NOTES:

1. ALL MATERIALS SHALL BE IN ACCORDANCE WITH CITY STANDARDS. SLEEVE BODY SHALL BE DUCTILE IRON ASTM A536.
2. MECHANICAL JOINT TAPPING SLEEVES SHALL BE AS MANUFACTURED BY CLOW, M & H, MUELLER, OR AMERICAN AND SHALL BE FURNISHED WITH SPLIT GLANDS, SPLIT END GASKET, BOLTS, ETC. THE OUTLET FLANGE SHALL BE CL 125 PER ANSI B16.1 COMPATIBLE WITH APPROVED TAPPING VALVES.
3. DIMENSIONS SHOWN ARE FOR REFERENCE AND MAY VARY BASED UPON MANUFACTURER. SLEEVES SHALL BE SIMILAR IN NATURE TO THAT SHOWN AND SHALL NOT DEVIATE IN ESSENTIAL DETAILS.
4. PIPE SURFACES SHALL BE CLEANED THOROUGHLY TO PERMIT FOR A GOOD SEAL PRIOR TO INSTALLATION.
5. EXTERIOR OF TAPPING SLEEVE SHALL BE COATED w/2 COATS ASPHALTIC VARNISH MIL-C450.
6. ALL TAPPING SLEEVES SHALL BE HYDROSTATICALLY PRESSURE TESTED PRIOR TO THE TAP BEING ACCOMPLISHED. TEST SHALL BE APPROVED BY PWC PROJECT COORDINATOR PRIOR TO BEGINNING TAPPING PROCESS.
7. SEE TAPPING VALVE FOR ADDITIONAL INFORMATION.

SLEEVE FOR USE WITH CI OR DI PIPE

SLEEVE SIZE PIPE X BRANCH	6X6	8X6	8X8	12X6	12X8	12X12	16X6	16X8	16X12	24X6	24X8	24X12	24X16	24X24	30X6	30X8	30X12	30X16	30X24
A DIA +.031-.000	7.016	7.016	9.016	7.016	9.016	13.016	7.016	9.016	13.016	11.00	13.5	19.0	23.5	32.0	11.00	13.5	19.0	23.5	32.0
B	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31	.31
C	7-7/8	9-1/16	9	11-5/8	11-7/8	12-7/8	14-1/8	14-1/2	14-7/8	19.5	19.5	19.5	20.5	20.5	23.25	23.25	23.25	23.75	23.75
E	11-3/4	13-7/8	13-7/8	18-1/2	18-1/2	18-1/2	23-1/2	23-1/2	23-1/2	35.5	35.5	35.5	35.5	35.5	43.37	43.37	43.37	43.37	43.37
F	13-1/2	15	15	19-1/2	19-1/2	19-1/2	22-1/2	22-1/2	22-1/2	18.0	18.0	24.0	30.0	36.0	24.0	24.0	24.0	36.0	36.0



DUCTILE IRON M.J. TAPPING SLEEVE

CITY of DUNN
NORTH CAROLINA
Department of Public Works


Revised: 1/28/11

Scale: NTS

600.05


Sheet 3 of 4

NOMINAL PIPE SIZE (INCH)	BRANCH SIZE	APPROX. WT. LBS.
4"	3",4"	28,30
6"	3",4",6"	36,38,45
8"	3",4",6",8"	42,44,48,66
10"	3",4",6",8",10"	45,48,55,70,80,
12"	3",4",6",8",10",12"	50,52,60,81,96,143
16"	3",4",6",8",10",12"	78,80,85,100,115,172
24"	3",4",6",8",10",12"	85,87,90,100,145,230




NOTES:


1. ALL MATERIALS SHALL BE IN ACCORDANCE WITH CITY STANDARDS.
2. TAPPING SLEEVES SHALL BE AS MANUFACTURED BY ROMAC, SMITH-BLAIR, OR APPROVED EQUAL.
3. STAINLESS STEEL TAPPING SLEEVE MAY BE UTILIZED FOR ALL TAPPING OF MAINS UP TO AND INCLUDING 24" DIAMETER WITH 12" OR LESS BRANCH. BRANCH GREATER THAN 12" SHALL REQUIRE FULL BODY D.I. M.J. TAPPING SLEEVE, (SEE DETAIL 600.05 2 OF 4).
4. SHELL AND LUGS SHALL BE STAINLESS STEEL PER ASTM A 240, TYPE 304 AND 304L.
5. BOLTS SHALL BE 5/8" UNC ROLLED THREAD, STAINLESS STEEL PER ASTM A 193 TYPE 304 4" NOM. PIPE SIZE SHALL HAVE MIN. 1/2" BOLTS.
6. NUTS SHALL BE HEAVY HEX STAINLESS STEEL PER ASTM A-194, TYPE 304.
7. WASHERS SHALL BE STEEL AND PLASTIC LUBRICATING WASHER.
8. GASKETS SHALL BE VIRGIN SBR PER ASTM D 2000 MAA 610, COMPOUNDED FOR WATER AND SEWER SERVICE.
9. FLANGE SHALL BE DUCTILE IRON PER ASTM 536, GRADE 65-45-12: OR STAINLESS STEEL PER ASTM A-240, TYPE 304.
10. DIMENSIONS SHOWN ARE FOR REFERENCE AND MAY VARY BASED UPON MANUFACTURER. SLEEVES SHALL BE SIMILAR IN NATURE TO THAT SHOWN AND SHALL NOT DEVIATE IN ESSENTIAL DETAILS.
11. PIPE SURFACES SHALL BE CLEANED THOROUGHLY TO PERMIT A GOOD SEAL PRIOR TO INSTALLATION.
12. ALL TAPPING SLEEVES SHALL BE HYDROSTATICALLY PRESSURE TESTED PRIOR TO THE TAP BEING ACCOMPLISHED. TEST SHALL BE APPROVED BY PWC PROJECT COORDINATOR PRIOR TO BEGINNING TAPPING PROCESS.
13. THE NUMBER OF BOLTS, NUTS AND WASHERS SHOWN ARE FOR ILLUSTRATION ONLY, ACTUAL QUANTITY SHALL BE AS RECOMMENDED BY THE SLEEVE MANUFACTURER FOR THE REQUIRED SERVICE.
14. SEE TAPPING VALVE DETAIL (W.9) FOR ADDITIONAL INFORMATION.




COVER FACE




COVER BACK




COVER SECTION



COVER SECTION



FRAME SECTION



FRAME SECTION



SIGMA CORPORATION

(800) 824-4513
PO Box 519
Alexander City, AL 35011

(800) 738-2956
PO Box 1043
Rockingham, NC 28380

DRAWN BY: RJL DATE: 6/29/2006

METER BOX
(MBX-1 with Touch Reader Hole)

LOAD RATING:
NON-TRAFFIC

MATERIAL SPECIFICATION:
CAST IRON
ASTM A 48 CLASS 30B

OPEN AREA - SQ. IN.
N/A

CATALOG NUMBER

MB-382T



METER BOX for 3/4" & 1" WATER SERVICE


CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11

Scale: NTS

600.06

Sheet 1 of 2



(800) 824-4513
 PO Box 519
 Alexander City, AL 35011

(800) 738-2956
 PO Box 1043
 Rockingham, NC 28380

DRAWN BY: R.J.L DATE: 6/29/2006

**METER BOX
 (MBX-5A)**

LOAD RATING:
 NON-TRAFFIC

MATERIAL SPECIFICATION:
 CAST IRON
 ASTM A 48 CLASS 30B

OPEN AREA - SQ. IN.
 N/A

CATALOG NUMBER
MB-2202T




METER BOX for 2" WATER SERVICE

CITY of DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 1/28/11
 Scale: NTS

600.06

Sheet 2 of 2



3/4" CORP. STOP AT MAIN LINE


3/4" CUT OFF CITY SIDE OF METER

UNION NUT

3/4" CUSTOMER SUPPLIED GATE VALVE REQUIRED ON CUSTOMER SIDE - MAX. 12" FROM METER BOX.


NOTES:

1. CUT-OFF VALVE REQUIREMENTS AS SPECIFIED IN THE CITY OF DUNN ORDINANCE BOOK, CHAP 21 - UTILITIES.
2. THE METER WILL NOT BE INSTALLED IF THE SETTER IS NOT CENTERED IN THE METER BOX, THE SETTER HAS BEEN PULLED TO ONE END, THE SETTER IS LAYING ON ITS SIDE, THE SETTER IS TOO CLOSE TO THE BOX LID, THE BOX IS BELOW GRADE OR BROKEN, THE CUSTOMERS SERVICE LINE IS NOT HOOKED TO THE UNION NUT, OR THE 3/4" GATE VALVE HAS NOT BEEN INSTALLED WITHIN 12" OF THE METER BOX.
3. THE METER BOX MUST HAVE EASY ACCESS AT ALL TIMES.
4. DO NOT PLANT BUSHES WITHIN 4' OF THE METER BOX.
5. DO NOT INSTALL A FENCE WHERE THE METER BOX WILL BE INSIDE.
6. THE CUSTOMER IS RESPONSIBLE FOR LEAKS AT THE UNION NUT AND THEIR SERVICE LINE.
7. TOP OF BOX TO BE SET 4" ABOVE EXISTING GRADE.



3/4" & 1" WATER CONNECTION
 WITH ANGLE DUAL CHECK VALVE
 CITY OF DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 4/27/22
Scale: NTS
600.07
Sheet 1 of 2



NOTES:


1. PIPING TO BE 'NO LEAD' BRASS AND COPPER TUBING. METER INLET AND OUTLET TO BE EQUIPPED WITH FLANGED BALL ANGLE METER VALVES.
2. CUSTOM SETTERS SHALL BE EQUIPPED WITH STANDARD LOW BYPASS WITH BALL VALVE AND PADLOCK WINGS.
3. CUSTOM SETTERS SHALL BE AS LISTED ON CARY APPROVED PRODUCTS LIST.
4. ALL BRASS COMPONENTS SHALL BE 'NO LEAD' BRASS MEETING UNS C89833 AS PER ASTM B584.
5. ALL APPLICATIONS REQUIRE A SEPARATE ABOVE GROUND BACKFLOW PREVENTER.
6. CUSTOM SETTER SHALL BE INSTALLED SUCH THAT METER REGISTER IS LOCATED 5 TO 8 INCHES BELOW METER BOX COVER
7. TOP OF BOX TO BE SET 4" EXISTING GRADE.


NOTE:
TO ENSURE POSITIVE DRAINAGE, THE VAULT SHALL HAVE AN OPEN BOTTOM TO ALLOW DRAINAGE THROUGH STONE.

DIMENSIONS (INCHES)	
A	B
18 ³ / ₄ "	30 ³ / ₈ "

MOUSE HOLES (2)
4" x 4" OPENING WITH 4" x 4" KNOCKOUT ABOVE OPENING


VAULT COUPLING





NOTES:

1. ALL MATERIALS SHALL BE IN ACCORDANCE WITH CITY STANDARDS.
2. RESILIENT WEDGE GATE VALVE SHALL BE AS MANUFACTURED BY MUELLER CORP., AMERICAN DARLING OR CLOW CORP.
3. ALL VALVES SHALL HAVE 2" SQUARE OPERATING NUT AND SHALL OPEN COUNTERCLOCKWISE.
4. VALVE BODY, BONNET AND GATE SHALL BE IN ACCORDANCE WITH AWWA C-509/C-515 AND NSF61.
5. VALVE BODY AND BONNET SHALL BE COATED ON ALL INTERIOR AND EXTERIOR SURFACES WITH A FUSION BONDED EPOXY IN ACCORDANCE WITH AWWA C-550-90.
6. ALL VALVES 24" AND SMALLER SHALL HAVE A SAFE WORKING PRESSURE OF 250 PSI.
7. SEE VALVE BOX DETAIL FOR ADDITIONAL INFORMATION.
8. SEE VALVE BOX PROTECTOR RING DETAIL FOR ADDITIONAL INFORMATION.
9. VALVE BOX SECTIONS ARE REQUIRED. THE USE OF PIPE IN LIEU OF VALVE BOX SECTIONS SHALL NOT BE PERMITTED.




SECTION "A-A"




PLAN


5-1/4" DROP LID



TOP SECTION



BOTTOM




DROP LID

TOP SECTION

BOTTOM SECTION



NOTES:

1. VALVE BOX SHALL BE 3 PART SLIP-TYPE MANUFACTURED BY ALABAMA PIPE CO., CHAPMAN VALVE CO., COLOMBIAN IRON WORKS, R.D. WOOD CO. OR APPROVED EQUAL.
2. VALVE BOX SHALL BE 3-PIECE CLOSE GRAINED CAST IRON SLIP-TYPE VALVE BOX WITH A MINIMUM THICKNESS OF 3/16".
3. VALVE BOX SHALL HAVE RAISED LETTERS "WATER" CAST INTO COVER.
4. VALVE BOX SHALL HAVE 3/8" HOLE DRILLED IN TOP SECTION THRU WHICH A 1/4"x1-1/2" GALVANIZED BOLT SHALL BE USED TO SECURE A MINIMUM 12 GAUGE, SINGLE STRAND, COATED COPPER TRACER WIRE FOR NON-FERROUS PIPE. A 1/2" WASHER SHALL BE USED BETWEEN NUT AND INSIDE OF BOX. TIGHTEN HAND TIGHT.
5. SCREW TYPE VALVE BOXES ARE ACCEPTABLE.
6. DIMENSIONS SHOWN ARE FOR INFORMATION ONLY AND VARY BASED UPON THE MANUFACTURER.
7. VALVE BOX SECTIONS ARE REQUIRED. THE USE OF PIPE IN LIEU OF VALVE BOX SECTIONS SHALL NOT BE PERMITTED.
8. TRACING WIRE SHALL BE INSTALLED OUTSIDE OF BOX.



NOTES:

1. CONCRETE PROTECTOR RING SHALL BE 2500 P.S.I. PRECAST REINFORCED CONCRETE
2. VALVE BOX SHALL BE AT GRADE W/PROTECTOR RING EXTENDING 1/2" ABOVE GRADE
3. SEE GATE VALVE AND BOX DETAIL
4. VALVE BOX PROTECTOR RINGS SHALL BE INSTALLED AROUND VALVE BOX IN UNPAVED NON-TRAFFIC AREAS. AND SHALL NOT CREATE A HINDERANCE TO MOWING OPERATIONS.



CUT AWAY VIEW

VALVE BOX PROTECTOR RING

CITY of DUNN
NORTH CAROLINA
Department of Public Works

Revised: 1/28/11

Scale: NTS


600.11

Sheet 1 of 1

REQUIREMENTS FOR ABOVE GROUND INSTALLATIONS OF REDUCED PRESSURE
PRINCIPLE AND DOUBLE CHECK VALVE ASSEMBLIES

1. THE BACKFLOW PREVENTOR MUST BE INSTALLED A MINIMUM DISTANCE OF 5 (5) FEET FROM THE METER SERVICE. INSTALLATION OF BACKFLOW PREVENTORS WITHIN THE RIGHT-OF-WAY WILL NOT BE APPROVED.
2. REDUCED PRESSURE PRINCIPLE ASSEMBLIES MUST BE INSTALLED IN A HORIZONTAL POSITION AND IN A LOCATION IN WHICH NO PORTION OF THE ASSEMBLY CAN BE SUBMERGED UNDER ANY CIRCUMSTANCES.
3. DOUBLE CHECK VALVE ASSEMBLIES MAY BE INSTALLED IN A VERTICAL POSITION PROVIDED IT CANNOT BE INSTALLED HORIZONTALLY AND THE FLOW OF WATER IS IN AN UPWARDS DIRECTION.
4. REDUCE PRESSURE PRINCIPLE BACKFLOW PREVENTORS MUST BE INSTALLED ABOVE GROUND.

BACKFLOW PREVENTION ASSEMBLIES TWO AND ON-HALF (2 1/2) INCHES OR LARGER SHALL BE INSTALLED WITH DUCTILE IRON OR STEEL PIPE.
5. BACKFLOW PREVENTORS INSTALLED INSIDE MUST BE A MINIMUM DISTANCE OF TWELVE (12) INCHES ABOVE THE FLOOR, AND NO HIGHER THAN 4 (4) FEET ABOVE THE FLOOR, WITH ADEQUATE CLEARANCE AROUND THE BACKFLOW PREVENTOR FOR TESTING, AND/OR REPAIR. WHEREVER A REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTOR IS INSTALLED INSIDE A BUILDING, AN AIR GAP DRAIN LARGE ENOUGH TO CARRY OFF THE DISCHARGE OF WATER FROM THE RELIEF VALVE SHALL BE INSTALLED.
6. BACKFLOW PREVENTION ASSEMBLIES INSTALLED OUTSIDE, ABOVE GROUND MUST BE PROTECTED FROM FREEZING. THE BACKFLOW PREVENTION ASSEMBLY MUST BE INSTALLED A MINIMUM DISTANCE OF TWELVE (12) INCHES ABOVE GROUND, AND NO HIGHER THAN FOUR (4) FEET ABOVE GROUND. LANDSCAPING IS ALLOWED AROUND THE BACKFLOW PREVENTOR, BUT MUST NOT INTERFERE WITH THE REQUIRED ANNUAL TESTING AND/OR REPAIR.
7. SHOULD YOU HAVE ANY QUESTIONS CONCERNING THE REQUIREMENTS LISTED ABOVE CONTACT PUBLIC UTILITIES, AT (910)892-2948, TO ASSIST YOU TO INSURE PROPER INSTALLATION.



WILKINS REGULATOR CO. MODEL 975 R
 FOR THE FOLLOWING MAIN SIZES:
 2 1/2", 3", 4", 6", 8", & 10"
 WILKINS REGULATOR CO. MODEL 975 B
 FOR THE FOLLOWING MAIN SIZES:
 3/4", 1", 1 1/4", 1 1/2", & 2"
 WILKINS REGULATOR CO. MODEL 575 R
 FOR THE FOLLOWING MAIN SIZES:
 2 1/2", 3", 4", 6", M8", & M10"
 WILKINS REGULATOR CO. MODEL 975 AB
 FOR THE FOLLOWING MAIN SIZES:
 3/4", 1", 1 1/4", 1 1/2", & 2"

COMPACTED SUBGRADE

NOTES:

1. SEE CROSS CONNECTION NOTES FOR ADDITIONAL INFORMATION.
2. ASSEMBLY SHALL BE HOUSED IN AN ALUMINUM OR FIBERGLASS INSULATED ENCLOSURE.
3. ALL PIPING SHALL BE STEEL OR DUCTILE IRON

REDUCED PRESSURE PRINCIPLE ASSEMBLY

ABOVE GROUND INSTALLATION ONLY


CITY of DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 4/26/22


Scale: NTS

600.13

Sheet 1 of 1



NOTES:

1. STANDARD COLOR: MILL FINISHED SILVER (COLORS OPTIONAL).
2. INSULATION: POLYISOCYANURATE FOAM.
3.  CERTIFIED
4. ALL DIMENSIONS ARE APPROXIMATED IN INCHES.
5. RECOMMENDED SLAB SIZE SEE APPLICABLE DRAWINGS AND MANUFACTURERS' RECOMMENDATIONS.
6. SEE CROSS CONNECTION CONTROL NOTES FOR ADDITIONAL REQUIREMENTS.
7. PROVIDE MIN. 6" CLEARANCE TO ALL COMPONENTS.



STANDARD 2 SECTION ALUMINUM ENCLOSURE

LOK BOX 4" IPS THRU 8" IPS

CITY of DUNN
NORTH CAROLINA
Department of Public Works


Revised: 1/28/11

Scale: NTS


600.14

Sheet 1 of 1

MODEL 300-AL TO 1000T-PG



MODEL 100-AL TO 200-PG




NOTES:


1. SEE CROSS CONNECTION NOTES FOR ADDITIONAL INFORMATION.
2. 120 V 10 U.L. APPROVED EXTERIOR GFI SHALL BE MOUNTED A MINIMUM OF 18" ABOVE SLAB INSIDE ENCLOSURE IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS AND THE N.E.C.

PHYSICAL DIMENSIONS

MODEL No.	B.F.P. SIZE	INSIDE		
		W	L	H
100 - AL	1/4" - 1"	6"	26"	22"
100 - PG	1/4" - 1"	6"	26"	22"
200 - AL	1 1/4" - 2"	14"	40"	29"
200 - PG	1 1/4" - 2"	14"	40"	29"
300 - AL	3" NRS	22"	72"	38"
300 - PG	3" NRS	22"	72"	38"
300T - AL	3" OS&Y	22"	72"	50"
300T - PG	3" OS&Y	22"	72"	50"
400 - AL	4" NRS	26"	86"	44"
400 - PG	4" NRS	26"	86"	44"
400T - AL	4" OS&Y	26"	86"	54"
400T - PG	4" OS&Y	26"	86"	54"
600 - AL	6" NRS	36"	100"	56"
600 - PG	6" NRS	36"	100"	56"
600T - AL	6" OS&Y	36"	100"	64"
600T - PG	6" OS&Y	36"	100"	64"
800 - AL	8" NRS	38"	118"	56"
800 - PG	8" NRS	38"	118"	56"
800T - AL	8" OS&Y	38"	118"	80"
800T - PG	8" OS&Y	38"	118"	80"
1000 - AL	10" NRS	40"	144"	78"
1000 - PG	10" NRS	40"	144"	78"
1000T - AL	10" OS&Y	40"	144"	90"
1000T - PG	10" OS&Y	40"	144"	90"



WS




ST

ONE PIECE ENCLOSURES


MODEL #	DIMENSIONS			WEIGHT
	L	W	H	
A - 21WS	18"	18"	23"	16 LBS
A - 26WS	25"	25"	23"	25 LBS
A - 43WS	41"	26"	29"	54 LBS
A - 18ST	18"	12"	30"	20 LBS

NOTES:

1. SEE CROSS CONNECTION NOTES FOR ADDITIONAL INFORMATION.
2. 120 V 10 U.L. APPROVED EXTERIOR GFI SHALL BE MOUNTED A MINIMUM OF 18" ABOVE SLAB INSIDE ENCLOSURE IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS AND THE N.E.C.



MODEL # B-48WHS			
DIMENSIONS			WGT.
L	W	H	
47	36	34	76



MODEL # B-64WHS			
DIMENSIONS			WGT.
L	W	H	
62	37	40	96

MODEL #	DIMENSIONS						WGT.
	OUTSIDE			INSIDE			
	L	W	H	L	W	H	
A30-S	30"	13"	21"	27"	10"	18"	22 LBS
A41-S	41"	18"	27"	35"	12"	25"	36 LBS
B30-S/B30-E	32"	15"	28"	27"	10"	25"	30 LBS
B41-S/B41-E	42"	17"	33"	36"	13"	30"	48 LBS
B51-E	52"	17"	39"	47"	12"	36"	64 LBS
B66-EH	69"	35"	51"	88"	31"	48"	162 LBS
B110-EH	110"	35"	51"	106"	29"	48"	202 LBS
B80-EH	92"	35"	51"	88"	31"	48"	180 LBS
B155-EH	160"	49"	73"	150"	45"	69"	360 LBS

ENCLOSURE KEYS:

- PREFIX: A = ONE PIECE CONSTRUCTION
 B = TWO PIECE CONSTRUCTION
- SUFFIX: H = HANDLES
 S = SPRAY FOAM INSULATION
 E = ENCAPSULATED INSULATION
 EH = ENCAPSULATED W/HANDELS
 (STANDARD ON 66/80/110/155)
 W = WIDE BODY
 T = TALL

NOTES:

- SEE CROSS CONNECTION NOTES FOR ADDITIONAL INFORMATION.
- 120 V 10 U.L. APPROVED EXTERIOR GFI SHALL BE MOUNTED A MINIMUM OF 18" ABOVE SLAB INSIDE ENCLOSURE IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS AND THE N.E.C.



SMI 2 PIECE ENCLOSURES


CITY of DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 1/28/11

Scale: NTS

600.17

Sheet 1 of 1




FEBCO MODEL 880 N-SHAPE

THIS MODEL HAS BEEN APPROVED FOR THE FOLLOWING SIZES:
2 1/2", 3", 4", 6", 8", & 10"


NOTES:

1. SEE CROSS CONNECTION NOTES FOR ADDITIONAL INFORMATION.
2. ASSEMBLY SHALL BE HOUSED IN AN ALUMINUM INSULATED ENCLOSURE.
3. ALL PIPING SHALL BE STEEL OR DUCTILE IRON



NOTES:

1. THE CUSTOMER IS RESPONSIBLE TO PROTECT DEVICE FROM FREEZING
2. SEE CROSS CONNECTION ORDINANCE TO DETERMINE WHEN RPZ IS REQUIRED.



**BLOW-OFF ASSEMBLY
AT DEAD END LINES**

CITY of DUNN
NORTH CAROLINA
Department of Public Works


Revised: 2/21/22

Scale: NTS

600.20

Sheet 1 of 1

MANHOLE RING AND COVER
(DETAIL 700.04)



MANHOLE STEP
(DETAIL 700.03)

STEEL REINFORCEMENT
(NOTE 3 DETAIL 700.01)

FLEXIBLE RUBBER
SLEEVE BOOT (NOTE 5
DETAIL 700.01)


4'-0"
(SEE NOTE 8
DETAIL 700.01)

SEWER MAIN 1" PLASTER

SEWER MAIN FLOW



NOTES

1. ALL PRE CAST CONCRETE MANHOLES SHALL CONFORM TO THE LATEST REVISION OF ASTM C478.
2. CONCRETE SHALL BE 4000 PSI AT 28 DAYS MINIMUM.
3. STEEL REINFORCEMENT SHALL BE GRADE 40 BILLET STEEL CONFORMING TO THE LATEST REVISION OF ASTM-A-185 FOR WALL REINFORCEMENT, AND THE LATEST REVISION OF ASTM-A615 FOR THE BASE REINFORCEMENT.
4. STANDARD JOINTS SHALL BE; SEALED WITH PUTTY TYPE PLASTIC CEMENT PER FED. SPEC. SS-C-153 OR AN O-RING TYPE JOINT CONFORMING TO THE LATEST REVISION OF ASTM-C443.
5. MANHOLE INLETS AND OUTLETS SHALL BE CAST IN PLACE FLEXIBLE RUBBER SLEEVES BOOTS PER THE LATEST REVISION OF ASTM-C923.
6. INVERTS TO BE CONSTRUCTED OF BRICK WITH A CONCRETE BENCH (DETAIL 700.02).
7. A STANDARD 0.20 FOOT DROP SHALL BE PROVIDED AT EACH MANHOLE. THE MAXIMUM SEPARATION OR INVERT IN TO INVERT OUT WITHIN A MANHOLE IS 24 INCHES. WHEN THE SEPARATION IS GREATER THAN 24 INCHES A DROP MANHOLE MUST BE USED.
8. MANHOLES GREATER THAN 20 FEET IN DEPTH SHALL HAVE AN INSIDE DIAMETER OR 5'-0". FOR SANITARY SEWER MAINS GREATER THAN EIGHTEEN INCHES (18") IN DIAMETER, MANHOLES SHALL BE A MINIMUM OF 5'-0" IN DIAMETER.
9. RIM ELEVATIONS SHALL BE AT GRADE IN STREETS & PARKING LOTS.
10. MANHOLES NOT LOCATED IN ROADWAYS SHALL HAVE A TOP ELEVATION A MINIMUM OF 12 INCHES ABOVE FINISH GRADE. MANHOLES LOCATED ALONG OUTFALLS SHALL HAVE A TOP ELEVATION A MINIMUM OF 24 INCHES ABOVE FINISHE GRADE OR 100 YEAR FLOOD PLAIN, OR 12 INCHES ABOVE 500 YEAR FLOOD PLAIN, WHICHEVER IS HIGHER. THE 100-YEAR FLOOD ELEVATION SHALL BE NOTED ON THE CONSTRUCTION DRAWINGS.



NOTES:


1. PROVIDE RUNGS AT 16" O.C
ALIGNED WITH ACCESS OPENING.
2. INSTALL RUBBER BOOTS SIMILAR
TO CONCRETE MANHOLE.



DIMENSIONS OF STEPS MAY VARY
 DEPENDING ON MANHOLE WALL
 THICKNESS AND TYPE OF
 CONSTRUCTION.




SOLID COVER MAY BE
REQUIRED DEPENDING ON
FIELD CONDITIONS



MINIMUM AVERAGE WEIGHTS
RING = 190lbs.
COVER = 120lbs.
TOTAL 310lbs.

PLAN



SECTION

PROVIDE MANHOLE INSERTS MANUFACTURED FROM HIGH DENSITY POLYETHYLENE, MEETING THE REQUIREMENTS OF ASTM D-1248, CLASS A, CATEGORY 5, TYPE III. INSERTS SHALL BE EQUIPPED WITH 1 GAS RELIEF VALVE, 1 VACUUM RELIEF VALVE, A CROSS-LINKED POLYETHYLENE GASKET AND ONE HEAVY WEIGHT POLYPROPYLENE LIFTING STRAP.




**SANITARY SEWER MANHOLE
RING AND COVER**
CITY of DUNN
NORTH CAROLINA
Department of Public Works



Revised: 3/09/22
Scale: NTS

700.04

Sheet 1 of 1





- NOTES:
1. INVERT MATERIAL SHALL BE CONCRETE CAST IN PLACE WITH A SMOOTH FINISH.
 2. WIDTH OF INVERT SHALL MATCH INSIDE DIAMETER OF INCOMING AND OUTGOING PIPES.
 3. BRICK INVERT SHALL BE FORMED AS SHOWN.
 4. ALL INVERT ELEVATIONS SHALL BE AS SHOWN ON APPROVED CONSTRUCTION PLANS.
 5. BENCHES TO BE BUILT OUT OF CONCRETE, MORTARED BLOCK, OR BRICK. STONE IS NOT ACCEPTABLE.




NOTES:

1. THE MINIMUM SPACING FROM THE EDGE OF A CORE FOR A LATERAL TO THE EDGE OF THE NEXT CORE SHALL BE 6 INCHES.
2. SEWER LATERAL SHALL NOT ENTER A MANHOLE AT AN ANGLE LESS THAN 90° TO THE EFFLUENT PIPE.
3. ALL LATERALS TO BE INSTALLED AT THE TOP OF THE BENCH.
4. PROVIDE BRICK OR CONCRETE FOR INVERT.
5. INVERTS TO BE BUILT FROM LATERAL TO EFFLUENT PIPE.
6. THE MAXIMUM NUMBER OF LATERALS FOR ANY ONE MANHOLE IS FIVE (5).
7. ALL NEW LATERALS INTO MANHOLES MUST BE CORE DRILLED AND INSTALLED WITH A FLEXIBLE RUBBER BOOT.








WATER TIGHT SEAL AROUND
EXISTING SEWER MAIN

ISOMETRIC VIEW




CROSS-SECTION

NOTES:


1. MANHOLE TO BE SET ON CONCRETE BASE AND BASE TO BE ONE POUR.
2. FOR VITRIFIED CLAY PIPE, CONCRETE SHALL BE POURED TO NEXT EXISTING JOINT (BOTH SIDES OF MANHOLE).
3. PIPE OPENING SHALL BE PRECAST BY MANUFACTURER.
4. FLOW SHALL BE MAINTAINED DURING CONSTRUCTION.
5. MINIMUM OF 4000 PSI CONCRETE REQUIRED.
6. THE CONTRACTOR SHALL PROVIDE A MINIMUM 6" COMPACTED #57 STONE BASE.
7. INVERT TO BE BUILT FROM PROPOSED PIPE TO EFFLUENT PIPE, ACCORDING TO DETAIL ON INVERTS.

* INITIAL INSTALLATION BY CITY OR DEVELOPER SHALL BE TO A POINT WITHIN 5' OR LESS OF EXISTING GROUND REMAINDER OR INSTALLATION SHALL BE BY PLUMBER AT LATER DATE.




SECTION

STANDARD SEWER MAIN LATERAL STUB-OUT
PVC SEWER MAIN




CLEAN OUT DETAILS
INSTALLED BY PLUMBER

* INITIAL INSTALLATION BY CITY OR DEVELOPER SHALL BE TO A POINT WITHIN 5' OR LESS OF EXISTING GROUND REMAINDER OR INSTALLATION SHALL BE BY PLUMBER AT LATER DATE.



STANDARD SEWER MAIN LATERAL STUB-OUT
PVC SEWER MAIN




CLEAN OUT DETAILS
INSTALLED BY PLUMBER

2" SEWER AIR RELEASE VALVE
(A.R.I. MODEL D-025) WITH BACK
FLUSHING HOSE, QUICK
DISCONNECT, COUPLINGS, 1/2"
SHUTOFF, 1" DRAIN, ETC. AS REQ'D.

ARV NOTES:

1. USE AN APPROVED JOINT COMPOUND ON ALL THREADED CONNECTIONS.
2. ARV ASSEMBLY SHOULD BE OFFSET TO ONE SIDE OF THE BOX AS SHOWN TO ALLOW EASIER ACCESS TO QUICK DISCONNECT AND VALVE HANDLE.
3. 2" S.S. NIPPLES SHALL BE USED IF NEEDED.
4. ARV LOCATION TO BE FIELD DETERMINED.



5'-0" I.D. PRECAST DOGHOUSE—
CONCRETE MANHOLE W/FLAT TOP.
SEE SPECS. FOR MANUFACTURE
REQUIREMENTS

PLAN

GRADE RINGS OR
ADJUST TO GRADE
W/BRICK AND
MORTAR — 8" MAX.

DUCTILE IRON
RETURN BEND
W/INSECT SCREEN

ADD 4" STATIC AIR
VENT WHERE REQ'D

GROUT AS REQUIRED


MANHOLE COVER
AND FRAME

2" AWWA S.S. BALL
VALVE WITH LEVER
HANDLE: HAMMOND NO.
8433 OR NO. V108-32
OR APPROVED EQUAL.
INSTALL WITH HANDLE
UP FOR OPEN


PROVIDE TREATED WOOD
BLOCKING
FOR STABILITY OF ARV

DBL STRAP
SERVICE SADDLE

CORPORATION STOP





SECTION A-A




SECTION B-B


#57 WASHED
STONE









PLAN VIEW



SECTION VIEW




(4) 1" DIA HOLES ON
28 3/4" DIA. B.C.
(90° APART)




SECTION OF FRAME
WEIGHT OF FRAME= 100 LBS.


PLAN OF FRAME



PLAN OF COVER
TOP VIEW




PLAN OF COVER
BOTTOM VIEW




SECTION OF COVER
WEIGHT OF COVER= 125 LBS.

NOTES:


1. ALL LETTERING SHALL BE CLEAN, CRISP AND CLEARLY LEGIBLE.
2. SEE CASTING SPECIFICATIONS.
3. CASTINGS SHALL RECEIVE ONE COAT OF KOPPERS SUPER SERVICE BITUMASTIC BLACK PAINT. PAINT SHALL BE KEPT OFF OF BOLT THREADS. SURFACE SHALL BE THOROUGHLY WIRE BRUSHED BEFORE PAINTING.




COVER TOP AND BOTTOM DETAIL



CROSS SECTION RING DETAIL



COVER FACE




CROSS SECTION COVER DETAIL

NOTES:

- A. MINIMUM AVERAGE WEIGHT:
 COVER 125 lbs
 FRAME 190 lbs
 UNIT 315 lbs
- B. MANHOLE RING AND COVERS SHALL BE MADE OF GRAY CAST IRON AND SHALL CONFORM TO AASHTO M105 AND ASTM A 48, CLASS 35B.
- C. RING AND COVER SHALL HAVE MACHINE SEATS.
- D. APPROVED RING AND COVERS:
 1. US FOUNDRY & MFG. CORP. RING USF 669, COVER TYPE-KY.
 2. EAST JORDAN IRON WORKS RING V-1384-1, COVER V-1384.
 3. APPROVED EQUAL.

RING & COVER
CITY STD.

MAX 1"
MORTAR JOINTS








TYPICAL MANHOLE DIMENSIONS:

(UNLESS OTHERWISE NOTED ON PLANS)
 8" TO 18" RCP PIPE - 4'-0"
 21" TO 30" RCP PIPE - 5'-0"
 36" TO 48" RCP PIPE - 6'-0"

NOTES:

1. ALL PRECAST SEWER MANHOLE SECTIONS SHALL MEET THE REQUIREMENTS OF ASTM C-478 AND AASHTO M199. THE PRECAST CONCRETE COMPRESSIVE STRENGTH SHALL BE A MINIMUM OF 4000 psi.
2. ALL MANHOLE STEPS SHALL CONFORM TO CITY STD. 700.03 OR AN APPROVED EQUAL. STEPS SHALL BE INSTALLED IN LINE WITH THE VERTICAL SIDE OF THE CORE.
3. THE MANHOLE JOINTS SHALL BE SEALED BY A BUTYL RUBBER SEALANT. THE BUTYL RUBBER SEALANT SHALL BE 1-1/4" SQUARE (5' DIA) AND 1-1/2" SQUARE (6' DIA) AND SHALL CONFORM TO ASTM C-990 AND AASHTO M-198.
4. THE LIFT INSERT AND HOLES SHALL BE ACCORDING TO CITY SPECIFICATIONS. ALL LIFT HOLES SHALL BE COMPLETELY FILLED WITH NON-SHRINK GROUT AFTER MH INSTALLATION.
5. ALL PIPE ENTRANCES AND CONNECTIONS SHALL CONFORM TO SECTION 840 OF THE CURRENT EDITION OF THE NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES.
6. IF A FLAT TOP SECTION IS NECESSARY, IT SHALL BE APPROVED BY THE ENGINEER AND SHALL BE DESIGNED FOR HS-20 LOADING.
7. A REINFORCED CONCRETE FOOTING IS REQUIRED WHEN THE MANHOLE IS OVER 12' OR ON A POOR SOIL BASE. THE REINFORCED CONCRETE FOOTING MAY BE POURED OR PRECAST ACCORDING TO CURRENT NCDOT STD NO. 1525.01 SHEET 2 OF 2. THE CONTRACTOR HAS THE OPTION OF PROVIDING AN EXPANDED MANHOLE BASE SECTION AND SETTING THE BASE SECTION ON 12" MIN #57 STONE WITH NO EXTRA COST TO THE CITY.
8. ALL PIPE OPENINGS SHALL BE CAST TO ELEVATIONS SPECIFIED ON CONTRACT PLANS OR TO MEET JOB REQUIREMENTS.




NOTES:

1. BRICK MASONRY SHALL BE JUMBO BRICK, CONCRETE BRICK, OR SOLID CONCRETE BLOCKS WHICH MEETS THE SPECIFICATIONS OF SECTION 1040 OF THE LATEST EDITION OF THE NCDOT SPECIFICATIONS FOR ROADS AND STRUCTURES.
2. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO THE CITY STD. 700.03 OR APPROVED EQUAL.
3. GENERALLY, STEPS SHALL BE PLACED IN THE REAR WALL. IF THERE IS A CONFLICT WITH A PIPE ENTERING THE REAR WALL, THE STEPS SHALL BE MOVED TO A SIDE WALL WITH A CORRESPONDING SHIFT OF THE TOP, CAST IRON FRAME AND COVER. THE LOCATION OF THE SHIFTED STEPS AND FRAME & COVER SHALL BE APPROVED BY THE ENGINEER.
4. CLASS A, 3000 psi CONCRETE SHALL BE USED THROUGHOUT.
5. THE FRAME AND COVER SHALL BE CAST INTO THE PCC LID AND SHALL BE MANUFACTURED AS SPECIFIED IN THE CITY STD. 800.06.
6. CATCH BASIN BRICK MINIMUM WALL THICKNESS:

HEIGHT OF STRUCTURE	WALL THICKNESS
0' - 8'	8"
OVER 8' - 16'	*
OVER 16'	SPECIAL DESIGN

 * OVER 8'-0" IN HEIGHT, USE 12" WALL FROM THE BOTTOM OF THE WALL TO 6'-0" FROM THE TOP OF THE WALL. USE 8" WALL FOR REMAINING 6'-0".
7. USE FORMS FOR CONSTRUCTION OF THE BOTTOM SLAB OR USE A PRECAST SLAB.











BRICK MASONRY CATCH BASIN
 THROATED INLET
 CITY OF DUNN
 NORTH CAROLINA
 Department of Public Works

Revised: 1/28/11
Scale: NTS
800.04
Sheet 1 of 2

NOTES (CONTINUED):

8. OVER-LENGTH, OVER-WIDTH, AND OVER-LENGTH/OVER WIDTH CATCH BASINS, TYPE A SHALL BE SPECIFIED ON THE PLANS.
9. THE PRECAST CONCRETE INLET LID FOR THE OVER-LENGTH INLET SHALL HAVE FOUR #5 BARS IN THE STREET FACE.
10. IF POSSIBLE, THERE SHOULD BE A MINIMUM OF 6" LENGTH BETWEEN THE OUTSIDE EDGE OF A PIPE AND THE INSIDE EDGE OF THE INLET WALLS.







NOTES:

1. PRECAST DESIGN SPECIFICATIONS SHALL CONFORM TO THE LATEST ASTM C913 SPECIFICATIONS FOR "PRECAST CONCRETE WATER AND WASTE WATER STRUCTURES", NCDOT AND THE CITY OF DUNN SPECIFICATIONS.
2. PRECAST STRUCTURES SHALL BE DESIGNED FOR H-20-44 LOADING.
3. PRECAST STRUCTURE SHALL HAVE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 4000 psi. IF THE BOTTOM CONCRETE SLAB IS POURED, IT SHALL BE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 3000 psi AND SHALL BE POURED INTO FORMS.
4. STEEL REINFORCING DESIGN SHALL CONFORM TO THE REQUIREMENTS OF ASTM C890 SPECIFICATIONS FOR "STRUCTURAL DESIGN LOADING FOR WATER AND WASTEWATER STRUCTURES" AND SHALL UTILIZE GRADE 60 RE-BARS CONFORMING TO THE REQUIREMENTS OF ASTM A615 OR WWF CONFORMING TO THE REQUIREMENTS OF ASTM A185 OR BOTH.
5. ADDITIONAL STEEL REINFORCEMENT SHALL BE INSTALLED AT ALL OPENINGS.
6. THE FRAME AND COVER SHALL BE CAST INTO THE PCC LID AND SHALL BE MANUFACTURED AS SPECIFIED IN CITY OF DUNN STD. 800.06.
7. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO CITY OF DUNN STD. 700.03, OR AN APPROVED EQUAL.
8. GENERALLY, STEPS SHALL PLACED IN THE REAR WALL. IF THERE IS A CONFLICT WITH A PIPE ENTERING THE REAR WALL, THE STEPS SHALL BE MOVED TO A SIDE WALL WITH A CORRESPONDING SHIFT OF THE TOP, CAST IRON FRAME & COVER. THE LOCATION OF THE SHIFT STEPS AND FRAME & COVER SHALL BE APPROVED BY THE ENGINEER.
9. SEAL JOINTS WITH FLEXIBLE BUTYL RUBBER BASE CONFORMING TO FEDERAL SPECIFICATIONS SS-S-21A, ASSHTO M-198, TYPE B - BUTYL RUBBER.
10. PRECAST CATCH BASIN MINIMUM WALL THICKNESS (SOLID WALL AND BOTTOM SLAB):


HEIGHT OF STRUCTURE	WALL THICKNESS
0' TO 10'	6"
10' TO 16'	8"
OVER 16'	SPECIAL DESIGN



A-A OVER-LENGTH




A-A OVER-LENGTH



B-B OVER-WIDTH

NOTES (CONTINUED):


11. OVER-LENGTH, OVER-WIDTH, AND OVER-LENGTH/OVER WIDTH CATCH BASINS, TYPE A SHALL BE SPECIFIED ON THE PLANS.
12. THE PRECAST CONCRETE INLET LID FOR THE OVER-LENGTH INLET SHALL HAVE FOUR #5 BARS IN THE STREET FACE.
13. IF POSSIBLE, THERE SHOULD BE A MINIMUM OF 6" LENGTH BETWEEN THE OUTSIDE EDGE OF A PIPE AND THE INSIDE EDGE OF THE INLET WALLS.




COVER BACK




PREFERRED COVER FACE




COVER SECTION




FRAME TOP VIEW



OPTIONAL COVER FACE



(2) 1" DIA. CORED HOLES
CORED HOLE
DETAIL







FRAME SECTION

▼ = MACHINED SURFACE

NOTES:



1. FRAME AND COVER SHALL BE GRAY CAST IRON MEETING ASTM A48 CLASS 35B SPECIFICATIONS.
2. MINIMUM AVERAGE WEIGHT:
COVER 76 lbs
FRAME 61 lbs
UNIT 137 lbs
3. FRAME AND COVER SHALL CONTAIN THE FOLLOWING INFORMATION:
MANUFACTURER'S MARK
LOCATION OF FOUNDRY (COUNTRY)
MANUFACTURER'S CATALOG NUMBER
(SEE COMPONENT DIAGRAMS FOR SPECIFICS)
4. APPROVED MANUFACTURERS:
EAST JORDAN IRON WORKS, V-1887
US FOUNDRY, USF 1162 RING AND LV COVER



NO PCS.	MATERIAL	LENGTH	PART MARK
1	6" SCH 80 PIPE	5'-1"	ta1
1	5" X 3 1/2" X 1/2" ANGLE	5'-1"	aa1
2	5" X 3 1/2" X 1/2" ANGLE	5 1/2"	ab1
3	5 1/2" X 1/2" PLATE	4 1/2"	pa1
5	1/2" X 6" HEADED STUD		

NOTES:

1. THE USE OF THE REINFORCED NOSE PLATE SHALL BE SPECIFIED ON THE PLANS OR SPECIFIED IN THE CONTRACT DOCUMENTS.
2. NOSE PLATE SHALL BE PAINTED WITH A BLACK ASPHALTIC PAINT OR AN APPROVE EQUAL.




APPROVED HOOD DESIGNS


NOTES:


1. BRICK MASONRY SHALL BE JUMBO BRICK, CONCRETE BRICK, OR SOLID CONCRETE BLOCKS WHICH MEETS THE SPECIFICATIONS OF SECTION 1040 OF THE LATEST EDITION OF THE NCDOT SPECIFICATIONS FOR ROADS AND STRUCTURES.
2. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO THE CITY OF DUNN STD. 700.03 OR APPROVED EQUAL.
3. CLASS A, 3000 psi CONCRETE SHALL BE USED THROUGHOUT.
4. CATCH BASIN BRICK MINIMUM WALL THICKNESS:

HEIGHT OF STRUCTURE	WALL THICKNESS
0' - 8'	8"
OVER 8' - 16'	"
OVER 16'	SPECIAL DESIGN
- OVER 8'-0" IN HEIGHT, USE 12" WALL FROM THE BOTTOM OF THE WALL TO 6'-0" FROM THE TOP OF THE WALL. USE 8" WALL FOR REMAINING 6'-0".
5. USE FORMS FOR CONSTRUCTION OF THE BOTTOM SLAB OR USE A PRECAST SLAB.
6. USE NCDOT STD NO. 840.03/CITY OF DUNN STD NO. 800.10 FRAME GRATE AND HOOD UNLESS OTHERWISE INDICATED. USE TYPE "E", "F", OR "G" GRATES UNLESS OTHERWISE INDICATED.




FRAME, GRATE AND HOOD
 SEE NCDOT STD. NO. 840.03/
 CITY STD. NO.







PLAN OVER-WIDTH



PLAN OVER-LENGTH



OVER-WIDTH




OVER-LENGTH


DETAIL SHOWING METHOD OF RISER CONSTRUCTION

FRAME, GRATE AND HOOD
SEE NCDOT STD. NO. 840.03/
CITY STD.

STEPS CITY
STD. NO.





SECTION J-J
OVER-WIDTH



SECTION M-M
OVER-LENGTH

NOTES (CONTINUED):

7. OVER-LENGTH, OVER-WIDTH, AND OVER-LENGTH/OVER WIDTH CATCH BASINS, TYPE A SHALL BE SPECIFIED ON THE PLANS.
8. THE EXTRA SLAB TO ACCOMMODATE OVER-LENGTH AND OVER-WIDTH PIPES, SHALL BE DESIGNED ACCORDING TO SHEET 2 OF 2 OF THE CURRENT NCDOT STD. NO. 840.01.
9. IT IS PREFERRED THAT THERE BE A MINIMUM OF 8" LENGTH BETWEEN THE OUTSIDE EDGE OF A PIPE AND THE INSIDE EDGE OF THE INLET WALLS.




APPROVED HOOD DESIGNS

NOTES:


1. PRECAST DESIGN SPECIFICATIONS SHALL CONFORM TO THE LATEST ASTM C913 SPECIFICATIONS FOR "PRECAST CONCRETE WATER AND WASTE WATER STRUCTURES", NCDOT AND THE CITY OF DUNN SPECIFICATIONS.
2. PRECAST STRUCTURES SHALL BE DESIGNED FOR H-20-44 LOADING.
3. PRECAST STRUCTURE SHALL HAVE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 4000 psi. IF THE BOTTOM CONCRETE SLAB IS POURED, IT SHALL BE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 3000 psi AND SHALL BE POURED INTO FORMS.
4. STEEL REINFORCING DESIGN SHALL CONFORM TO THE REQUIREMENTS OF ASTM C890 SPECIFICATIONS FOR "STRUCTURAL DESIGN LOADING FOR WATER AND WASTEWATER STRUCTURES" AND SHALL UTILIZE GRADE 60 RE-BARS CONFORMING TO THE REQUIREMENTS OF ASTM A615 OR WWF CONFORMING TO THE REQUIREMENTS OF ASTM A185 OR BOTH.
5. ADDITIONAL STEEL REINFORCEMENT SHALL BE INSTALLED AT ALL OPENINGS.
6. USE NCDOT STD. NO. 840.03/CITY OF DUNN STD. 800.10 FRAME, GRATE AND HOOD UNLESS OTHERWISE INDICATED. USE TYPE "E", "F", OR "G" GRATES UNLESS OTHERWISE INDICATED.
7. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO CITY OF DUNN STD. 700.03, OR AN APPROVED EQUAL.
8. OPTIONAL CONSTRUCTION - MONOLITHIC CLASS A PCC POUR. USE 2" KEYWAY OR #4 BAR DOWELS AT 12" CENTERS AT THE CONSTRUCTION JOINT.
9. SEAL JOINTS WITH FLEXIBLE BUTYL RUBBER BASE CONFORMING TO FEDERAL SPECIFICATIONS SS-S-21A, ASSHTO M-198, TYPE B - BUTYL RUBBER.
10. PRECAST CATCH BASIN MINIMUM WALL THICKNESS (SOLID WALL AND BOTTOM SLAB):

HEIGHT OF STRUCTURE	WALL THICKNESS
0' TO 10'	6"
10' TO 16'	8"
OVER 16'	SPECIAL DESIGN




SECTION Y-Y


FRAME, GRATE AND HOOD
SEE NCDOT STD. NO. 840.03/
CITY STD. NO. 405.




SECTION X-X




PLAN OVER-WIDTH



PLAN OVER-LENGTH



OVER-WIDTH



OVER-LENGTH


DETAIL SHOWING METHOD OF RISER CONSTRUCTION

FRAME, GRATE AND HOOD
SEE NCDOT STD. NO. 840.03/
CITY STD. NO.


STEPS CITY
STD. NO.

TOP ELEVATION

STEPS CITY
STD. NO.




SECTION J-J
OVER-WIDTH



SECTION M-M
OVER-LENGTH


NOTES (CONTINUED):

11. OVER-LENGTH, OVER-WIDTH, AND OVER-LENGTH/OVER WIDTH CATCH BASINS, TYPE A SHALL BE SPECIFIED ON THE PLANS.
12. THE EXTRA SLAB TO ACCOMMODATE OVER-LENGTH AND OVER-WIDTH PIPES, SHALL BE DESIGNED ACCORDING TO SHEET 2 OF 2 OF THE CURRENT NCDOT STD. NO. 840.02.
13. IT IS PREFERRED THAT THERE SHOULD BE A MINIMUM OF 6" LENGTH BETWEEN THE OUTSIDE EDGE OF A PIPE AND THE INSIDE EDGE OF THE INLET WALLS.





TYPE OF GRATE TO BE DETERMINED BY ENGINEER.

PLAN




SECTION A-A

APPROVED HOOD DESIGNS:



ALIGN FRAME WITH INSIDE EDGE OF WALL TO ALLOW FOR VERTICAL ADJUSTMENT OF HOOD.








SECTION B-B

NOTES:


- FRAMES, GRATE AND HOOD SHALL BE GRAY CAST IRON MEETING ASTM A48 CLASS 35 SPECIFICATIONS. IT SHALL ALSO MEET THE CURRENT NCDOT STD. NO. 840.03.
- MINIMUM AVERAGE WEIGHT:

GRATE	220 lbs
BACK	140 lbs
FRAME	215 lbs
UNIT	575 lbs
- FRAME, GRATE AND HOOD SHALL CONTAIN THE FOLLOWING INFORMATION:
 MANUFACTURER'S MARK
 LOCATION OF FOUNDRY (COUNTRY)
 MANUFACTURER'S CATALOG NUMBER
 NCDOT STD NO.
- APPROVED MANUFACTURERS:
 EAST JORDAN IRON WORKS
 TYPE "E" V-4066-1
 TYPE "F" V-4066-3
 TYPE "G" V-4066-4
 US FOUNDRY & MANUF. CORP
 TYPE "E" USF 5181-6420
 TYPE "F" USF 5181-6425
 TYPE "G" USF 5181-6430
 OR APPROVED EQUAL






REINFORCED TOP SLAB



A-A




SIDE VIEW



TOP VIEW CASTING



B-B CASTING




TOP VIEW

NOTES:

1. BRICK MASONRY SHALL BE JUMBO BRICK, CONCRETE BRICK, OR SOLID CONCRETE BLOCKS WHICH MEETS THE SPECIFICATIONS OF SECTION 1040 OF THE LATEST EDITION OF THE NCDOT SPECIFICATIONS FOR ROADS AND STRUCTURES.
2. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO THE CITY STD. 700.03 OR APPROVED EQUAL.
3. CLASS A, 3000 psi CONCRETE SHALL BE USED THROUGHOUT.
4. THE FRAME AND COVER SHALL BE CAST INTO THE PCC LID AND SHALL BE MANUFACTURED AS SPECIFIED IN THE CITY STD. 800.06.
5. CATCH BASIN BRICK MINIMUM WALL THICKNESS:


HEIGHT OF STRUCTURE	WALL THICKNESS
0' - 8'	8"
OVER 8' - 16'	"
OVER 16'	SPECIAL DESIGN
- * OVER 8'-0" IN HEIGHT, USE 12" WALL FROM THE BOTTOM OF THE WALL TO 6'-0" FROM THE TOP OF THE WALL USE 8" WALL FOR REMAINING 6'-0".
6. USE FORMS FOR CONSTRUCTION OF THE BOTTOM SLAB OR USE A PRECAST SLAB.




REINFORCED TOP SLAB




TOP VIEW CASTING




B-B CASTING



A-A



SIDE VIEW




TOP VIEW


NOTES:

1. PRECAST DESIGN SPECIFICATIONS SHALL CONFORM TO THE LATEST ASTM C913 SPECIFICATIONS FOR "PRECAST CONCRETE WATER AND WASTE WATER STRUCTURES", NCDOT AND THE CITY OF DUNN SPECIFICATIONS.
2. PRECAST STRUCTURE SHALL HAVE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 4000 psi. IF THE BOTTOM CONCRETE SLAB IS POURED, IT SHALL BE A MINIMUM CONCRETE COMPRESSIVE STRENGTH OF 3000 psi AND SHALL BE POURED INTO FORMS.
3. STEEL REINFORCING DESIGN SHALL CONFORM TO THE REQUIREMENTS OF ASTM C890 SPECIFICATIONS FOR "STRUCTURAL DESIGN LOADING FOR WATER AND WASTEWATER STRUCTURES" AND SHALL UTILIZE GRADE 60 RE-BARS CONFORMING TO THE REQUIREMENTS OF ASTM A615 OR WWF CONFORMING TO THE REQUIREMENTS OF ASTM A185 OR BOTH.
4. ADDITIONAL STEEL REINFORCEMENT SHALL BE INSTALLED AT ALL OPENINGS.
5. THE FRAME AND COVER SHALL BE CAST INTO THE PCC LID AND SHALL BE MANUFACTURED AS SPECIFIED IN CITY OF DUNN STD. 800.06.
6. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO CITY OF DUNN STD. 700.03, OR AN APPROVED EQUAL.
7. SEAL JOINTS WITH FLEXIBLE BUTYL RUBBER BASE CONFORMING TO FEDERAL SPECIFICATIONS SS-S-21A, ASSHTO M-198, TYPE B - BUTYL RUBBER.
8. PRECAST CATCH BASIN MINIMUM WALL THICKNESS (SOLID WALL AND BOTTOM SLAB):


HEIGHT OF STRUCTURE	WALL THICKNESS
0' TO 10'	8"
10' TO 16'	8"
OVER 16'	SPECIAL DESIGN



**GRANULAR FOUNDATION
CLASS B**



**GRANULAR FOUNDATION
CLASS C**



**CONTINUOUS BEARING SUPPORT
MODIFIED CLASS D**

=LOOSELY PLACED APPROVED SUITABLE LOCAL MATERIAL OR SELECT MATERIAL FOR FOUNDATION CONDITIONING AS DIRECTED BY THE ENGINEER. (STONE WILL NOT BE ALLOWED)

TRENCH WIDTH:

MIN W = $B_c + 16"$
MAX W = $B_c + 4'$


IF CONTRACTOR CHOOSES TO EXCAVATE PAST THE MAX W, THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL COSTS IN THE EXCAVATION BEYOND THE MAX W LIMITS.

BACKFILLING NOTES ACCORDING TO CURRENT EDITION OF NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES:


1. EXCAVATION, TRENCHING AND BACKFILLING SHALL BE DONE ACCORDING TO SECTION 300 AND ACCORDING TO NCDOT STD. NO. 300.01, METHOD OF PIPE INSTALLATION, METHOD A.
2. BACKFILLING SHALL ALSO BE IN ACCORDANCE WITH ARTICLE 300-7 AND COMPACTED TO 95% OF THE AASHTO T99 NCDOT MODIFIED PROCTOR.
3. THE LAST 8" OF BACKFILL BELOW THE FINISHED SURFACE OF THE SUBGRADE SHALL BE COMPACTED TO 100% OF THE AASHTO T99 NCDOT PROCTOR.

TYPICAL INSTALLATION:

1. UNLESS OTHERWISE SPECIED, A MODIFIED CLASS D FOUNDATION SHALL BE USED.
2. UNLESS OTHERWISE SPECIFIED, METHOD A SHALL BE USED.




FRONT VIEW




SIDE VIEW

PIER SHALL AT LEAST
EXTEND TO THE BOTTOM
OF THE LOWER PIPE






PIPE DIA.	W	E	G
12"	1-7/8"	2'-0"	2'-3 3/4"
15"	1-7/8"	2'-6"	2'-3 3/4"
18"	2"	3'-0"	3'-4"
24"	2-1/2"	4'-0"	4'-5"
30"	2-3/4"	5'-0"	5'-5 1/2"
36"	3"	6'-0"	6'-6"
42"	3-1/2"	6'-6"	7'-1"
48"	4"	7'-0"	7'-8"
54"	4-1/2"	7'-6"	8'-3"




NOTES:


1. END BLOCK SHALL BE PRECAST OR CAST-IN-PLACE USING CLASS B CONCRETE, 2,500 psi.
2. THE PRECAST END BLOCK SHALL BE INSTALLED OR THE HOLE FOR THE POURED END BLOCK SHALL BE EXCAVATED, PRIOR TO THE INSTALLATION OF THE FLARED END SECTION.
3. THE END BLOCKS ARE MANDATORY FOR UPSTREAM F.E.S. AND REQUIRED, IF SPECIFIED IN THE PLANS, FOR DOWNSTREAM F.E.S. THE COST FOR THE END BLOCKS SHALL BE CONSIDERED INCIDENTAL TO THE COST OF F.E.S.



VIEWS - FRAME ORIENTATION



SECTION WITH DRAINAGE AT BACK OF CURB




SECTION WITH DRAINAGE UNDER STREET


NOTES:

1. BRICK MASONRY SHALL BE JUMBO BRICK, CONCRETE BRICK, OR SOLID CONCRETE BLOCKS WHICH MEETS THE SPECIFICATIONS OF SECTION 1040 OF THE LATEST EDITION OF THE NCDOT SPECIFICATIONS FOR ROADS AND STRUCTURES.
 2. FOR STRUCTURE HEIGHTS OVER 3'-6", INSTALL STEPS ON 12" CENTERS. ALL STEPS SHALL CONFORM TO THE CITY STD. 700.03 OR APPROVED EQUAL.
 3. CLASS A, 3000 psi CONCRETE SHALL BE USED THROUGHOUT.
 4. CATCH BASIN BRICK MINIMUM WALL THICKNESS:


HEIGHT OF STRUCTURE	WALL THICKNESS
0' - 8'	8"
OVER 8' - 16'	*
OVER 16'	SPECIAL DESIGN
- * OVER 8'-0" IN HEIGHT, USE 12" WALL FROM THE BOTTOM OF THE WALL TO 6'-0" FROM THE TOP OF THE WALL. USE 8" WALL FOR REMAINING 6'-0".
5. USE FORMS FOR CONSTRUCTION OF THE BOTTOM SLAB OR USE A PRECAST SLAB.
 6. USE FRAME AND GRATE AS SPECIFIED ON CITY OF DUNN STD. 800.17.
 7. THE EXTRA SLAB TO ACCOMMODATE OVER-LENGTH AND OVER-WIDTH PIPES, SHALL BE DESIGNED ACCORDING TO SHEET 2 OF 2 OF THE CURRENT NCDOT STD. NO. 840.01; UNLESS THE EXTENDED BOX WILL BE SUBJECT TO VEHICULAR TRAFFIC, THEN, THE EXTRA SLAB SHALL BE DESIGNED FOR HS20 LOADING.
 8. THE CONTRACTOR HAS THE OPTION OF FURNISHING A PRECAST PCC BOX. THE BOX SHALL MEET THE APPLICABLE SPECIFICATIONS OF THE CITY OF DUNN STD. 800.09.




FRAME TOP VIEW




GRATE TOP VIEW




GRATE SECTION A-A



GRATE SECTION B-B




FRAME SECTION C-C



FRAME SECTION D-D

NOTES:

1. FRAMES, GRATE AND HOOD SHALL BE GRAY CAST IRON MEETING ASTM A48 CLASS 35B SPECIFICATIONS.
2. GRATE SHALL BE SUITABLE FOR BICYCLE TRAFFIC.
3. FRAME, GRATE AND HOOD SHALL CONTAIN THE FOLLOWING INFORMATION:
 MANUFACTURER'S MARK
 LOCATION OF FOUNDRY (COUNTRY)
 MANUFACTURER'S CATALOG NUMBER
 GRATE: "DUMP NO WASTE/ DRAINS TO WATERWAYS".
4. ESTIMATED TOTAL WEIGHT: 529 lbs.
5. APPROVED MANUFACTURERS:
 US FOUNDRY & MANUF. CORP
 ITEM NO. 8040223
 EAST JORDAN IRON WORKS, INC
 V-4510 (DIFFERENT DIMENSIONS)
6. OPEN AREA IS APPROXIMATELY 310 sq in.



DO NOT DAMAGE OR CUT LEADER

TWO-PLY REINFORCED BLACK RUBBER HOSE

3/16" CABLE GUY WIRES WITH 6 1/2" GALVANIZED TUMBUCKLES.

4" HIGH SHREDDED BARK MULCH

CREATE 5" HIGH WATER BASIN (SAUCER) AROUND EVERGREEN TREE.

STEEL 'T' STAKE OR 2"x4" X 2"-4" NOTCHED WOOD STAKE (NOTCH 6" FROM TOP).

FINISHED GRADE


REMOVE TOP PORTION OF BURLAP IF TREE IS B&B STOCK.

ROOTBALL

COMPACTED TOPSOIL AND PLANTING BACKFILL
INSTALL FERTILIZER TABLETS TO A MIN. DEPTH OF 3".


SCARIFY PIT BOTTOM


SUBGRADE



WIDTH OF TREE PIT TO BE TWICE ROOTBALL DIAMETER.


- NOTE: 1. DO NOT ALLOW AIR POCKETS TO FORM WHEN BACKFILLING.
2. LEAVE A MINIMUM OF 6" OF STAKE ABOVE GRADE TO ALLOW FOR FUTURE REMOVAL.
3. POSITION CROWN OF ROOT BALL A MINIMUM OF 8" ABOVE FINISHED GRADE TO ALLOW FOR SETTLING.






LANDSCAPE NOTES:

1. THE LANDSCAPE CONTRACTOR SHALL MAKE HIMSELF AWARE OF EXISTING UTILITIES. HE SHALL NOTIFY THE RESPECTIVE PUBLIC UTILITIES PRIOR TO BEGINNING CONSTRUCTION.
2. PLANTING BEDS AND PLANT LOCATIONS SHALL BE STAKED BY THE CONTRACTOR AND APPROVED BY THE OWNER OR OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.
3. PLANTING BEDS SHALL BE CLEARED OF ALL GRASS AND WEEDS PRIOR TO INSTALLATION OF PLANTS, AND SHALL BE CULTIVATED AS SHOWN ON THE PLANTING DETAILS.
4. ALL DISTURBED AREAS TO BE SEEDED UNLESS OTHERWISE NOTED.
5. PLANTING BEDS SHALL HAVE 4" SHREDDED HARDWOOD BARK MULCH IN ENTIRE BED UNLESS OTHERWISE NOTED ON DRAWINGS.
6. ALL PLANTED AREAS SHALL BE TREATED WITH A WATER-SOLUBLE HERBICIDE FOR THE NON-SELECTIVE CONTROL OF ANNUAL AND PERENNIAL WEEDS PRIOR TO PLANTING.
7. ALL TREE AND SHRUB PITS SHALL BE BACKFILLED WITH A PLANTING SOIL MIXTURE OF 1 PART PEAT MOSS, 3 PARTS TOP SOIL AND 1 PART SAND, THOROUGHLY MIXED.
8. ALL PLANTED AREAS TO BE FERTILIZED WITH GRANULAR FERTILIZER. CONTRACTOR TO PROVIDE SOIL TEST AND FERTILIZER APPLICATION RATES IF REQUIRED FOR APPROVAL.
9. SPRAY TREES AND SHRUBS WITH AN ANTI-DESICCANT IF FOLIAGE IS PRESENT.
10. EVERGREEN TREES AND SHRUBS SHALL BE PLANTED THE SAME AS DECIDUOUS MATERIAL.
11. DO NOT PRUNE ANY MATERIAL UNTIL IT HAS BEEN VIEWED AND ACCEPTED BY THE OWNER OR OWNER'S REPRESENTATIVE.
12. ALL PLANT MATERIAL TO BE NURSERY GROWN AND TO COMPLY WITH AMERICAN STANDARD FOR NURSERY STOCK ANSI-Z60-1-1986.
13. ALL MATERIALS INSPECTED AT THE SITE AND FOUND NOT TO BE ACCEPTABLE SHALL BE REMOVED FROM THE SITE ON THE DAY OF REJECTION.
14. IMMEDIATELY AFTER A TREE IS PLANTED, IT SHOULD BE SUPPORTED WITH STAKES AND GUY WIRES TO FIRMLY HOLD IT IN PLACE. (SEE DETAIL-THIS SHEET) REMOVE STAKES AND TIES AFTER ONE YEAR.
15. THE LOWER TRUNKS OF NEW TREES SHOULD BE WRAPPED WITH BURLAP OR PAPER TO PREVENT EVAPORATION AND SUN SCALD. THE WRAPPING SHALL REMAIN ON THE TREE AT LEAST ONE YEAR.
16. PLANT ALL TREES AT LEAST 3 1/2 FEET FROM THE END OF HEAD-ON PARKING SPACES TO PREVENT DAMAGE FROM CAR OVERHANG.



PLAN VIEW



SECTION

PLANTING OF TREES ON SLOPES

N.T.S.